
Bid Letting: March 8, 2012

101 - YELLOWSTONE RIVER - 1 MILE N TERRY

Clarification:

Submitted: Wed. 29-Feb-2012 10:45 MST

Anchor Bolt clarification:

The Bulb Tee anchor bolts are to meet the requirements of AASHTO M 314 grade 36 and are to be galvanized in accordance with AASHTO M232.

Clarification:

Submitted: Wed, 29-Feb-2012 15:40

An Addendum has been posted for this project. Please click on the following link to access the information. [ADDENDUM](#)

To download the addendum bid file, click here. [BID FILES](#)

-1-

Submitted: Tue, 14-Feb-2012 16:11 MST

Company: SLETTEN CONSTRUCTION COMPANY

Contact: JIM WICKENS

Question:

In the preliminary plans/specs the contract time was 80 working days. This was reduced to 50 working days when the project was advertised for bids. Our preliminary schedule indicates that the 80 working days is the correct amount of time needed to complete the project. This is largely due to the fact that the project must be constructed 1/2 at a time. It takes considerably longer to build a project half at a time than if the entire bridge could be built at once. Also, if we allow the amount of time for drawing review times per the MDT standard specifications, it takes even longer to get the job done.

Answer:

Submitted: Tue. 21-Feb-2012 16:15 MST

Special Provision #2 - Contract Time is hereby revised as follows:

The work begins on the effective date stated in the "Notice to Proceed" and is to be completed in 80 Working Days. The notice to proceed will be issued with an approximate date of April 16, 2012.

An addendum will be issued for this change.