

Bid Letting: May 10, 2012 & May 24, 2012

Bid Letting: May 10, 2012

101 - SMELTER AVE - 3RD ST - DIVISION RD - GREAT FALLS

Clarification:

Submitted: Mon. 16-Apr-2012 9:15 MDT

Add the highlighted wording to Special Provision #33 - Fence - Special Design
- 33. B. 2)

2) Furnish 3-rail steel welded fence panels 4' high with ¾" square, 18 gauge pickets at 4" maximum spacing, spear tops and 1.5" by 1.5" 14 gauge steel rails. Furnish steel 2.5" square, 16 gauge posts to be set 3 feet in concrete.

Clarification:

Submitted: Tue. 08-May-2012 9:10 MDT

Plan sheets 16 and 33 have been revised as follows:

Sheet 16

1. In Sidewalk frame, the symbol "#" was added to the heading of the column "Remove Sidewalk".

Sheet 33

1. In the P.C.C.P. Mountable Curb Joint detail, the note "#32 M x 12" Long Smooth Epoxy Coated Dowels Spaced at 12" Centers" was changed to read "32 M x 24" Long Smooth Epoxy Coated Dowels Spaced at 12" Centers".

PLAN SHEETS 16 & 33

-1-

Submitted: Mon, 07-May-2012 08:48 MDT

Company: United Materials of Great Falls, Inc.

Contact: Scott

Question:

Plan sheet 033, P.C.C.P mountable curb joint detail. Should the reinforcing dowel be 24" instead of 12" in length?

Answer:

Submitted: Mon, 07-May-2012 11:32 MDT

Yes, the reinforcing dowels shown in the PCCP Mountable Curb Joint Detail should be #10(32mm) x 24".

102 - DENA MORA REST AREA

Clarification:

Submitted: Thu. 19-Apr-2012 10:40 MDT

Special Provision # 23, REVEGETATION, on page 24 of the proposal, the last sentence of Paragraph A. is revised;

"Total amount of ground disturbed is projected to be less than 1.0 acre."

-1-

Submitted: Wed, 25-Apr-2012 09:25 MDT

Company: Flathead Concrete Products

Contact: Tom

Question:

The summary sheet - G-5, shows 170 cleanout replacements. Are these the standard cleanout with an iron casting, or the lateral cleanouts? Where can I find the rim and invert elevations for the two 48" type 3 manholes?

Answer:

Submitted: Fri, 27-Apr-2012 08:46 MDT

The drainfield lateral cleanouts. Details shown on Sheet C-10.

The 48" Type 3 manhole rim and invert elevations are not specified. Expectations are that the advanced wastewater treatment system supplier and contractor will coordinate final tank arrangements within the reserved area identified on the plans. Final manhole elevations depend on final treatment system tank arrangement and resultant finished grading. Manhole elevations are to be depicted on shop drawing submittals for approval once the final layout is confirmed. The sectional drawings on Sheet C-12 provide information to estimate elevations.

-2-

Submitted: Wed, 02-May-2012 11:32 MDT

Company: Cretex

Contact: Mike Pardy

Question:

Note 4 on Plan sheet TS-1 limits the length of the Barrel to 5 ft. This requirement will require an additional piece to be cast as well as an additional waterproof joint in the walls of the structure.

Because the floor slab will be heavier than a 6 ft barrel section, lifting equipment capable of handling the 6 ft barrel will be on site at the time of the installation anyway. It makes sense to allow a 6 ft barrel section to eliminate the additional joint which must be leakproof and will reduce the cost to produce the structure as one less piece will need to be cast. Will 6 ft barrel lengths be allowed?

Answer:

Submitted: Thu, 03-May-2012 10:06 MDT

Six foot barrel lengths are acceptable.

103 - CLEMENTS RD & 3RD ST & 3 TIED MISSOULA PROJECTS

Clarification:

Submitted: Mon, 16-Apr-2012 8:45 MDT

Delete Special Provision #2 - Contract Time and replace it with the following:

2. Contract Time - Flex Time Proceed Date

A. General. This provision modifies Subsection 108.02 of the Standard Specifications.

B. Notice to Proceed. The Notice to Proceed will be issued with an effective date of July 9, 2012. The Contractor may change the Notice to Proceed date to an earlier date by submitting written notification to the Project Manager at least ten days in advance of the date selected. Include an updated schedule with the notification.

C. Contract Time. Contract time assessment will begin on the notice to proceed date issued by the Department or as changed by the Contractor, whichever is earlier. Work is to be completed in 50 working days.

Update: Thu. 19-Apr-2012 10:30 MDT

Special Provision #13. Traffic Control Plan & Sequence of Operations - Add:

D. Mountain Water Company will have a contractor working within the project limits (UPP 8108(2)) installing new water lines. The contractor plans to be out of the area east of Pattee Street by June 22nd, however, this date is not guaranteed. Coordinate project work with any contractors to minimize public disruption and traffic control issues. Coordination with project work will not be measured for payment.

Submitted: Mon, 30-Apr-2012 11:32 MDT

Company: Pavement Maintenance Solutions, Inc.

Contact: Chris Rasmussen

Question:

1. Will the Department allow side brooming on Clements and 3rd as there is no curb and gutter in this location?
2. Is the Cove Gutter near Station 19+41.38 on Main Street to remain in place?
3. Does the Department anticipate any increase in Additional Surfacing due to changes in curbs at various intersections?
4. Special Provision 26 talks about tree roots. What about tree limbs? Will the City of Missoula also be responsible for tree trimming?

Answer:

Submitted: Thu, 03-May-2012 8:22 MDT

1. No

2. Yes

3. The additional surfacing associated with the curb changes is listed in the Add Surfacing Frame.

4. Trimming should not be necessary. If trimming is needed, coordinate with the City of Missoula Urban Forester as discussed in Special Provision No. 26, Construction in Proximity to Existing Trees. Tree trimming will not be measured for payment. Contractor should review project site prior to bidding.

104 - SF089 SKYLINE S PABLO CANAL

Clarification:

Submitted: Thu. 12-Apr-2012 11:10 MDT

Special Provision No. 1, Project Description: The following sentence is hereby added to the end of the description.

This project is within the boundaries of the Flathead Indian Reservation.

Clarification:

Submitted: Thu. 12-Apr-2012 11:30 MDT

The linked special provisions are hereby made a part of this contract.

Reservation Special Provisions

No Questions at this time.