## SECTION 608 CONCRETE SIDEWALKS

608.01 DESCRIPTION. This work is the construction of concrete sidewalks.

**608.02 MATERIALS.** Furnish materials meeting the following requirements.

**608.03 CONSTRUCTION REQUIREMENTS.** Construct concrete sidewalks as specified in the Contract and as follows.

**608.03.1 Subgrade and Forms.** Excavate, shape, and compact the foundation to the specified width and grade.

Place and compact aggregate base to the specified thickness.

Use forms and form meeting Section 552 and Subsection 609.03 requirements.

**608.03.2 Concrete.** Furnish and place concrete meeting Section 551 requirements. Place reinforcing steel as specified.

Dampen the foundation and forms immediately before placing concrete.

Do not place concrete on a frozen foundation course or subgrade.

Construct sidewalks meeting Subsections 501.03.18 and .19 requirements.

**608.04 METHOD OF MEASUREMENT.** Concrete sidewalk is measured by the square yard (square meter), including wheelchair ramps.

Reinforcing steel, expansion joint material, excavation, backfill, and disposal of surplus material are not measured for payment.

**608.05 BASIS OF PAYMENT.** Payment for the completed and accepted quantities is made under the following:

Pay Item Sidewalk-Concrete **Pav Unit** 

Square Yard (square meter)

Payment at the contract unit price is full compensation for all resources necessary to complete the item of work under the Contract. Material specified or directed to be excavated and not related to the sidewalk construction but necessary to place the sidewalk is paid for under Section 203.