

## 620.03.3, Temporary and Interim Pavement Markings

### Qualification Requests

On the laboratory test report that is sent in with the request, the test data must show that the material is in compliance with subsection "714.04 Temporary and Interim Paint Markings or 714.07 Waterborne Pavement Marking Paint".

### Qualification Procedures

The requirements for samples that are received for QPL prequalification are as follows.

- ◆ The producer will submit a minimum of three samples (at least 1 quart of each component) and test results from an independent lab for each type of pavement marking to be considered.
- ◆ MDT will test each sample according to the tests outlined in subsection "714.04 Temporary and Interim Paint Markings or subsection 714.07 Waterborne Pavement Marking Paint." The material will be rejected if the material does not meet the requirements.

### Material Requirements

Temporary and Interim Pavement Marking Material must meet the requirements listed in the Standard Specifications for Road and Bridge Construction subsection 714.04. Also look in the Supplemental specifications to Montana Standard Specifications subsection 714.04. Waterborne Pavement Marking Paint must meet the requirements listed in the Standard Specifications for Road and Bridge Construction subsection 714.07. Also look in the Supplemental specifications to Montana Standard Specifications subsection 714.07. . All testing and reporting is to conform to the above requirements whether it is for the quality control test reports, random or auditing test, or for disqualification or requalification.