

PROPOSED DRAFT
AUGUST 2014

551.03.3 Batching, Mixing, Handling and Sampling

- H. **Job-Site Additions.** On-site addition of air entraining or high range water reducing admixtures is permitted up to two times. Do not re-dose with other admixtures without the approval of the Project Manager. On-site dosing of water or admixture in no way relieves the contractor of producing passing plastic and hardened concrete test results.

Deleted: Do not make any additions to the plastic concrete without the approval of the Project Manager.

551.03.8 Testing and Acceptance of Concrete

B. **Acceptance of Concrete**

1. **Classes General, Deck, Pave, Structure, Overlay and Drilled Shaft Concrete.**

- b. **Air Content.** Concrete air content will be determined in accordance with MT-102 on the same sample used to make the compression test cylinders for acceptance and on samples taken according to MT 601. A separate air content pay factor will be computed for each test result and the lot air content pay factor will be the average of the individual test result pay factors. The Pay Factor for each air content result is determined from Table 551-6.

Deleted: Concrete air content will be determined in accordance with MT 102 or ASTM C457. The lot acceptance air content is the average of all the test results for the lot. In cases where the measured air content within a lot varies by more than 2.5 percentage points, a separate air content pay factor will be computed for each test result and the lot air content pay factor will be the average of the individual test result pay factors. The pay factor for each lot based on air content is determined from the following table

NO COMMENTS RECEIVED

FINAL DRAFT
EFFECTIVE DECEMBER 11, 2014

551.03.3 Batching, Mixing, Handling and Sampling

- H. **Job-Site Additions.** On-site addition of air entraining or high range water reducing admixtures is permitted up to 2 times. Do not re-dose with other admixtures without the approval of the Project Manager. On-site dosing of water or admixture in no way relieves the contractor of producing passing plastic and hardened concrete test results.

Deleted: :

551.03.8 Testing and Acceptance of Concrete

B. **Acceptance of Concrete**

1. **Classes General, Deck, Pave, Structure, Overlay and Drilled Shaft Concrete.**

- b. **Air Content.** Concrete air content will be determined in accordance with MT-102 on the same sample used to make the compression test cylinders for acceptance and on samples taken according to MT 601. A separate air content pay factor will be computed for each test result and the lot air content pay factor will be the average of the individual test result pay factors. The Pay Factor for each air content result is determined from Table 551-6.