

620.03.3, Temporary and Interim Pavement Markings

Qualification Requests

On the laboratory test report that is sent in with the request, the test data must show that the material is in compliance with the material requirements.

Qualification Procedures

The requirements for samples that are received for QPL prequalification are as follows.

- ◆ The producer will submit a minimum of two samples of each paint along with test results from an independent lab for each type of pavement marking to be considered.
- ◆ MDT will test each sample according to the tests outlined in subsection "714.04 B Temporary and Interim Paint Markings." The material will be rejected if the material does not meet the requirements.

Material Requirements

Temporary and Interim Pavement Marking Material must meet the requirements listed in the Standard Specifications for Road and Bridge Construction subsection 714.04 B, the Supplemental specifications to Montana Standard Specifications subsection 714.04 B, or contract Special Provisions.