
MONTANA DEPARTMENT OF TRANSPORTATION STREAM MITIGATION MONITORING REPORT

*Bowser Creek
Flathead County, Montana*

*Project Completed: 2010
Monitoring Report #6: December, 2018*



Prepared for:



Prepared by:



MONTANA DEPARTMENT OF TRANSPORTATION

STREAM MITIGATION MONITORING REPORT #6

YEAR 2018

*Bowser Creek
Flathead County, Montana*

MDT Project Number: NH 15(93)
Control Number: 2038-011

USACE Number: NWO-2009-01808-MTM

Prepared for:

MONTANA DEPARTMENT OF TRANSPORTATION
2701 Prospect Ave
Helena, MT 59620-1001

Prepared by:

Confluence Consulting, Inc.
P.O. Box 1133
Bozeman, MT 59771

December 2018

TABLE OF CONTENTS

1.0	Introduction	1
2.0	Site Location	3
3.0	Monitoring Methods.....	3
4.0	Results	3
4.1.	Riparian and Stream Bank Vegetation Inventory	3
4.2.	Stream Bank Vegetation Composition	7
4.3.	Noxious Weed Inventory.....	7
4.4.	Woody Plant Survival.....	10
4.5.	Bank Erosion Inventory.....	10
4.6.	Perpendicular Transect Surveys.....	11
4.7.	Longitudinal Profile Survey	12
4.8.	Wildlife Documentation	12
5.0	Comparison of Results to Performance Standards	13
5.1.	Riparian Buffer Success	13
5.2.	Vegetation along Stream Banks	15
5.3.	Stream Bank Stability	15
5.4.	Channel Form Success.....	15
6.0	Literature Cited	16

TABLES AND FIGURES

Table 3.	Percent cover of vegetation transects at Bowser Creek in 2013 through 2018.	6
Table 4.	Vegetation community types observed at Bowser Creek in 2018.	6
Table 5.	Comprehensive vegetation species list for the Bowser Creek stream mitigation site from 2013 through 2018.	8
Table 6.	Plant species and their associated cover classes along the stream banks of the Bowser Creek stream mitigation site in 2018.....	9
Table 7.	Montana State-listed noxious weed species observed in 2018 at the Bowser Creek Stream Mitigation Site.....	10
Table 8.	Woody plant survival at Bowser Creek stream mitigation site from 2013 through 2018.....	10
Table 9.	Pool and riffle widths surveyed at Bowser Creek stream mitigation site from 2013 through 2018.....	12
Table 10.	Wildlife observations at Bowser Creek stream mitigation site from 2013 through 2018.....	13
Table 11.	Performance standards for the Bowser Creek Stream Mitigation Site.....	14
Figure 1.	Project location of Bowser Creek stream mitigation site.	4
Figure 2.	Bowser Creek 2017 Monitoring Features	Appendix A
Figure 3.	Bowser Creek Noxious Weeds and Community Map	Appendix A

APPENDICES

Appendix A: Project Site Maps

Appendix B: Perpendicular Transect and Longitudinal Profile Plots

Appendix C: Project Area Photos

Appendix D: Construction Detail Plans

1.0 INTRODUCTION

As part of construction of the Kalispell Bypass U.S. Highway 2 South, the Montana Department of Transportation (MDT) modified a segment of Bowser Creek to allow for highway widening and improved traffic. In order to offset the impacts of this project, MDT proposed on-site stream mitigation actions within the widened highway right of way. The following report includes results from the sixth year of post-project monitoring of the on-site mitigation actions along the modified segment of Bowser Creek. This monitoring report includes an evaluation of monitoring results in comparison to project performance standards outlined in the post-construction monitoring plan for the site. The project was constructed in 2010; therefore, these results provide documentation of the site's condition eight years following the project's completion.

Over several decades, the alignment of Bowser Creek was modified to fit between the original Highway 2 alignment and residential development. An expanded MDT right-of-way was acquired to provide additional space to relocate the stream away from the widened road footprint. The relocation of Bowser Creek was permitted in a modification to U.S. Army Corps of Engineers (USACE) permit NWO-2009-018098-MTM. The project proposed placement of 0.267 acres of wetland fill in the original Bowser Creek channel and 709 feet of stream impacts resulting from relocating 429 feet of the channel and placing a 218-foot segment of the creek into a culvert beneath MT Highway 2.

One goal of the project is to provide compensatory mitigation for stream impacts resulting from widening of U.S. Highway 2 at its intersection with the Alternate U.S. 93 Kalispell Bypass. MDT has selected on-site stream mitigation to meet this goal. Specific objectives intended to achieve this goal include:

- Constructing 430 linear feet of new Bowser Creek channel slightly north of the existing channel
- Laying back floodplain slopes adjacent to the channel from 1.5:1 to a 4:1 slope or flatter
- Implementing an aggressive revegetation plan to re-establish native riparian and upland vegetation.

If successful, the project will create, enhance, restore, and maintain permanent, naturally self-sustaining, native or native-like stream and riparian habitat. The project is designed to protect the functional values of riparian lands, floodplains, wetlands, and uplands for the benefit of fish and wildlife habitat, water quality, floodwater retention, groundwater recharge, open space, aesthetic values, and environmental education.

Provisions outlined in the USACE permit include monitoring the mitigation areas for at least five years following construction to determine whether the site is meeting, or moving toward meeting the performance criteria outlined in the monitoring plan. Specific success criteria for the Bowser Creek stream mitigation site include:

Quantitative success criteria:

1. **Riparian Buffer Success** will be achieved when
 - a. Woody and riparian vegetation becomes established, and noxious weeds do not exceed 10% cover within the riparian buffer areas.
 - b. Any area within the creditable buffer area disturbed by the project construction must have at least 50% areal cover of non-noxious weed species by the end of the monitoring period.
2. **Vegetation Success** will be achieved when
 - a. Combined areal cover of riparian and stream bank vegetation communities is $\geq 70\%$
 - b. Planted trees and shrubs will be considered successful where they exhibit 50% survival after 5 years.
3. **Vegetation along Stream Banks** will be considered successful when banks are vegetated with a majority of deep-rooting riparian plant species having root stability indices ≥ 6 (subject to 1.a and 1.b above).
4. **Stream Bank Stability Success** will be achieved where; following restoration, less than 25% of bank length is unstable and classified as eroding bank. For this purpose "eroding bank" will be defined as any bank greater than two feet in length that is more than 50% bare mineral soil and has no roots, surface vegetation, or other stabilizing structure (e.g. rock, woody debris) to inhibit erosion.

Qualitative performance criteria:

5. **Channel Form Success** will be achieved when the stream stabilizes, includes pools and riffles, allows for flood events to occupy the floodplain, and the habitat features such as riparian plant communities have successfully established along stream banks.

Additional reporting requirements:

6. **Photo Documenting** success of restored stream channel and stream bank vegetation community development showing distinct positive changes from pre-construction to final monitoring year in comparison with the establishment reference reach.

Results of the sixth year monitoring at the Bowser Creek stream mitigation site are presented in Section 4 and compared to performance standards in Section 5. Additional information to aid in documenting the site's condition are provided as appendices to this report, and include maps showing locations of riparian vegetation transects, perpendicular transects, and locations of noxious weeds; transect and longitudinal profile survey plots; photo documentation of the project site; and a planting schematic from the approved design.

2.0 SITE LOCATION

The modified segment of Bowser Creek flows east within a newly constructed channel immediately north of U.S. Hwy 2 near the intersection of U.S. Highway 2 and Alternate U.S. 93 Kalispell Bypass (Figure 1). This monitoring site is located in Section 12, Township 28 North, Range 22 West, in Flathead County, Montana.

3.0 MONITORING METHODS

Monitoring field crews visited the project site on August 9th, 2018 while topographic survey crews visited the site on August 14th, 2018. Field data collection and surveys followed methodologies as described in the 2013 monitoring report for the Bowser Creek mitigation site, which may be accessed at the following Montana Department of Transportation website:

https://www.mdt.mt.gov/other/webdata/external/planning/STREAM-MITIGATION/2013_REPORTS/2013_BOWSER_CREEK_MONITORING_REPORT.PDF

4.0 RESULTS

4.1. Riparian and Stream Bank Vegetation Inventory

Table 1 summarizes the areal percent cover of total vegetation, woody vegetation, and noxious weeds observed along each three-foot wide streambank transect adjacent to the stream, and each 25-foot wide riparian belt transect during the 2014 through 2018 monitoring events. In addition to presenting results for individual transects, Table 1 includes area-weighted, site-wide totals for each of these vegetation cover categories.

In 2018 the percent cover in riparian belt transects decreased to 91%, with 9% cover by woody species and 16% by noxious weeds. Stream bank transects displayed 100% cover, with 4% by woody species and 8% by noxious weeds. More bare ground was observed within both riparian areas as compared to stream bank areas, likely a result of the allelopathic influence and invasion by the nonnative weed species Canada thistle (*Cirsium arvense*), bull thistle (*Cirsium vulgare*), and scotch thistle (*Onopordium acanthium*). These nonnative species replace native species diversity, which are known to release phytotoxic compounds that inhibit the germination and growth of many surrounding plant species (Kazinczi et al. 2001; Ravlic et al. 2016; Fenner 2008; Watanabe et al. 2014). Additionally, stream bank areas were primarily dominated by reed canary grass (*Phalaris arundinacea*), an aggressive rhizomatous species that often grows in dense stands and outcompetes most surrounding vegetation. In total, using a length-based weighted average of vegetation cover for riparian and stream bank transects, the site exhibited 93% total vegetation cover, with 8% by woody species and 14% by noxious weeds.




Figure 1. Project location of Bowser Creek stream mitigation site.

Table 1. Percent cover of vegetation transects at Bowser Creek in 2013 through 2018.

Belt Transect	Length (ft)	Total % Vegetation Cover						% Woody Cover						% Noxious Weed Cover					
		2013	2014	2015	2016	2017	2018	2013	2014	2015	2016	2017	2018	2013	2014	2015	2016	2017	2018
Right (South) Riparian	204	100	100	100	100	95	90	2	5	7	5	5	6	2	5	10	13	15	15
Left (North) Riparian	167	100	100	100	100	95	93	14	15	17	15	15	13	5	10	12	15	17	17
Riparian Subtotal		100	100	100	100	95	91	8	10	12	10	10	9	4	7	11	14	16	16
Right (South) Stream Bank	465	100	100	100	100	100	100	17	20	15	7	7	3	4	5	6	10	10	7
Left (North) Stream Bank	465	100	100	100	100	100	99	12	10	10	5	5	5	4	10	10	10	10	8
Stream Bank Subtotal		100	100	100	100	100	100	15	15	13	6	6	4	4	8	8	10	10	8
Area Weighted Total		100	100	100	100	96	93	9	11	12	9	9	8	3	7	10	13	15	14

Dominant species recorded along the riparian and stream bank transects were combined with visual observations in other areas to develop a vegetation community map (Figure 3, Appendix A). Four vegetation community types were observed in 2018, and are included in Table 2.

Table 2. Vegetation community types observed at Bowser Creek in 2018.

Community Type	Dominant Species
2	<i>Phalaris arundinacea</i>
3	<i>Nasturtium officinale</i>
4	<i>Cirsium</i> spp./ <i>Bromus inermis</i>
5	<i>Elymus</i> spp./ <i>Festuca ovina</i>

Vegetation community Type 2 – *Phalaris arundinacea* was identified along both stream banks and riparian zones adjacent to the channel. Reed canary grass dominated this community type, with lesser cover provided by Canada thistle, bull thistle, Nebraska sedge (*Carex nebrascensis*), watercress (*Nasturtium officinale*) along both stream banks, fringed willowherb (*Epilobium ciliatum*), and others.

Vegetation community Type 3 – *Nasturtium officinale* was identified within the channel. Watercress dominated this community type with more than 50% cover growing in the channel bed and 6 to 10% cover along both stream banks. This community has been consistently observed in dense stands along the stream bed during the growing season, and had expanded to both stream banks during the 2017 and 2018 monitoring events.

Vegetation community Type 4 – *Cirsium* spp./*Bromus inermis* was observed in between community Types 2 and 5. Canada thistle, bull thistle, scotch thistle, and smooth brome (*Bromus inermis*) dominated this community type.

Vegetation community Type 5 – *Elymus* spp./*Festuca ovina* was identified along the upper side slopes of the project area. Sheep fescue (*Festuca ovina*), nodding wild rye (*Elymus canadensis*), slender wild rye (*Elymus trachycaulus*), and western-wheat grass (*Pascopyrum smithii*) were the most commonly observed species within this vegetation community.

Table 3 provides a comprehensive list of plant species observed on site during the 2013 through 2018 monitoring events. Since 2013, 100 plant species have been identified within the project area, including one new species observed in 2018. Flat pea (*Lathyris sylvestris*), a nonnative, invasive species that competes with native species for limited resources, was identified within the project area. In 2018, 50% of the species observed were hydrophytic based on the 2016 National Wetland Plant List (NWPL) (Lichvar *et al.* 2016).

4.2. Stream Bank Vegetation Composition

The stream bank vegetation inventory identified 44 plant species along the banks of Bowser Creek (Table 4). Reed canary grass comprised 21-50% cover along both stream banks in 2018 (see additional photos 1-3 in Appendix C). The Winward stability ratings are based on vegetation communities rather than individual species; therefore, a vegetation community was assigned to each stream bank based on one or more dominant species (Winward 2000). Vegetation community Type 2 – *Phalaris arundinacea* was the dominant vegetation community observed along the stream banks, with an associated Winward stability rating of 9.

4.3. Noxious Weed Inventory

A total of six Montana Listed Priority 2B noxious weeds were identified within the Bowser Creek stream mitigation site and are listed in Table 5. Locations of twenty-nine noxious weed infestations are provided on Figure 3 in Appendix A, with the exception of those observed as isolated occurrences and those in trace amounts (i.e., common tansy (*Tanacetum vulgare*)). A low cover class (1 to 5 percent) was identified for all mapped weed occurrences within the project area. In 2018, a visual estimate of 14% of the project area was colonized by noxious weeds, representing a decrease by 1% since the 2017 monitoring event. Infestations of Canada thistle, the most prevalent noxious weed, were located throughout the project area. In 2016 through 2018, Canada thistle was so commonly observed that it was identified as a dominant species in community Type 4 (Figure 3, Appendix A).

Table 3. Comprehensive vegetation species list for the Bowser Creek stream mitigation site from 2013 through 2018.

Scientific Name	Common Name	WMVC Indicator Status*	Scientific Name	Common Name	WMVC Indicator Status*
<i>Achillea millefolium</i>	Common Yarrow	FACU	<i>Leucanthemum vulgare</i>	Ox-Eye Daisy	FACU
<i>Acer negundo</i>	Ash-Leaf Maple	FAC	<i>Leymus cinereus</i>	Great Basin Lyme Grass	FAC
<i>Agastache urticifolia</i>	Nettle-Leaf Giant-Hyssop	FACU	<i>Linaria vulgaris</i>	Butter-and-Eggs	UPL
<i>Agropyron cristatum</i>	Crested Wheatgrass	UPL	<i>Lysichiton americanus</i>	Yellow-Skunk-Cabbage	OBL
<i>Agrostis gigantea</i>	Black Bent	FAC	<i>Medicago lupulina</i>	Black Medick	FACU
<i>Agrostis stolonifera</i>	Spreading Bent	FAC	<i>Medicago sativa</i>	Alfalfa	UPL
<i>Alnus incana</i>	Speckled Alder	FACW	<i>Melilotus albus</i>	White Sweetclover	UPL
<i>Alopecurus arundinaceus</i>	Creeping Meadow-Foxtail	FAC	<i>Melilotus officinalis</i>	Yellow Sweet-Clover	FACU
<i>Amelanchier alnifolia</i>	Saskatoon Service-Berry	FACU	<i>Mentha arvensis</i>	American Wild Mint	FACW
<i>Artemisia absinthium</i>	Absinthium	UPL	<i>Myosotis scorpioides</i>	True Forget-Me-Not	FACW
<i>Artemisia biennis</i>	Biennial Wormwood	FACW	<i>Nasturtium officinale</i>	Watercress	OBL
<i>Beckmannia syzigachne</i>	American Slough Grass	OBL	<i>Onopordum acanthium</i>	Scotch Thistle	UPL
<i>Betula pumila</i>	Bog Birch	OBL	<i>Pascopyrum smithii</i>	Western-Wheat Grass	FACU
<i>Bromus inermis</i>	Smooth Brome	UPL	<i>Persicaria amphibia</i>	Water Smartweed	OBL
<i>Carduus nutans</i>	Nodding Plumeless-Thistle	UPL	<i>Persicaria</i> sp.	Smartweed	UPL
<i>Carex nebrascensis</i>	Nebraska Sedge	OBL	<i>Phalaris arundinacea</i>	Reed Canary Grass	FACW
<i>Carex</i> sp.	Sedge	N/A	<i>Phleum pratense</i>	Common Timothy	FAC
<i>Carex stipata</i>	Stalk-Grain Sedge	OBL	<i>Plantago lanceolata</i>	English Plantain	FACU
<i>Carex utriculata</i>	Northwest Territory Sedge	OBL	<i>Plantago major</i>	Great Plantain	FAC
<i>Centaurea cyanus</i>	Garden Cornflower	FACU	<i>Poa palustris</i>	Fowl Blue Grass	FAC
<i>Centaurea stoebe</i>	Spotted Knapweed	UPL	<i>Poa pratensis</i>	Kentucky Blue Grass	FAC
<i>Chamaenerion angustifolium</i>	Narrow-Leaf Fireweed	FACU	<i>Prunus virginiana</i>	Choke Cherry	FACU
<i>Chenopodium album</i>	Lamb's-Quarters	FACU	<i>Ranunculus</i> sp.	Buttercup	N/A
<i>Chorispora tenella</i>	Common Blue-Mustard	UPL	<i>Rosa woodsii</i>	Woods' Rose	FACU
<i>Cicuta douglasii</i>	Western Water-Hemlock	OBL	<i>Rudbeckia hirta</i>	Black-Eyed-Susan	FACU
<i>Cirsium arvense</i>	Canadian Thistle	FAC	<i>Rumex crispus</i>	Curly Dock	FAC
<i>Cirsium vulgare</i>	Bull Thistle	FACU	<i>Salix bebbiana</i>	Gray Willow	FACW
<i>Cornus alba</i>	Red Osier	FACW	<i>Salix drummondiana</i>	Drummond's Willow	FACW
<i>Cynoglossum officinale</i>	Gypsy-Flower	FACU	<i>Salix exigua</i>	Narrow-Leaf Willow	FACW
<i>Descurainia sophia</i>	Herb Sophia	UPL	<i>Salix</i> sp.	Willow	N/A
<i>Elymus canadensis</i>	Nodding Wild Rye	FAC	<i>Scirpus microcarpus</i>	Red-Tinge Bulrush	OBL
<i>Elymus repens</i>	Creeping Wild Rye	FAC	<i>Silene vulgaris</i>	Maiden's-tears	UPL
<i>Elymus trachycaulus</i>	Slender Wild Rye	FAC	<i>Solanum dulcamara</i>	Climbing Nightshade	FAC
<i>Epilobium ciliatum</i>	Fringed Willowherb	FACW	<i>Solidago canadensis</i>	Canadian Goldenrod	FACU
<i>Equisetum arvense</i>	Field Horsetail	FAC	<i>Sonchus arvensis</i>	Field Sow-Thistle	FACU
<i>Festuca ovina</i>	Sheep Fescue	UPL	<i>Stachys byzantina</i>	Woolly Hedgenettle	UPL
<i>Geum macrophyllum</i>	Large-Leaf Avens	FAC	<i>Stuckenia pectinata</i>	Sago False Pondweed	OBL
<i>Geum</i> sp.	Avens	N/A	<i>Symphoricarpos albus</i>	Common Snowberry	FACU
<i>Geum triflorum</i>	Old-Man's-Whiskers	FACU	<i>Tanacetum vulgare</i>	Common Tansy	FACU
<i>Glyceria grandis</i>	American Manna Grass	OBL	<i>Taraxacum officinale</i>	Common Dandelion	FACU
<i>Glyceria striata</i>	Fowl Manna Grass	OBL	<i>Thlaspi arvense</i>	Field Pennycress	UPL
<i>Helianthus maximiliani</i>	Maximilian Sunflower	UPL	<i>Tragopogon dubius</i>	Meadow Goat's-beard	UPL
<i>Helianthus nuttallii</i>	Nuttall's Sunflower	FACW	<i>Trifolium pratense</i>	Red Clover	FACU
<i>Hordeum jubatum</i>	Fox-Tail Barley	FAC	<i>Trifolium repens</i>	White Clover	FAC
<i>Hypericum perforatum</i>	Common St. John's-Wort	FACU	<i>Triglochin maritima</i>	Seaside Arrow-Grass	OBL
<i>Juncus balticus</i>	Baltic Rush	FACW	<i>Typha latifolia</i>	Broad-Leaf Cat-Tail	OBL
<i>Juncus</i> sp.	Rush	N/A	<i>Urtica dioica</i>	Stinging Nettle	FAC
<i>Lactuca serriola</i>	Prickly Lettuce	FACU	<i>Verbascum thapsus</i>	Great Mullein	FACU
<i>Lathyrus sylvestris</i>	Flat Pea	UPL	<i>Veronica americana</i>	American Brooklime	OBL
<i>Lemna minor</i>	Common Duckweed	OBL	<i>Vicia americana</i>	American Purple Vetch	FAC

*2016 National Wetland Plant List; *Western Mountains, Valleys, and Coasts* (WMVC) (Lichvar *et al.* 2016)

New species identified in 2018 are **bolded**.

Species identified to genus level have been assigned an indicator status of N/A.

Table 4. Plant species and their associated cover classes along the stream banks of the Bowser Creek stream mitigation site in 2018.

Streambank Species	Left bank	Left Bank Cover Class	Right bank	Right Bank Cover Class	WMVC Indicator Status*
<i>Agrostis stolonifera</i>	X	0	X	0	FAC
<i>Alnus incana</i>			X	0	FACW
<i>Alopecurus arundinaceus</i>	X	2	X	2	FAC
<i>Artemisia absinthium</i>			X	0	UPL
<i>Bromus inermis</i>	X	1	X	1	UPL
<i>Carex nebrascensis</i>	X	2	X	1	OBL
<i>Carex utriculata</i>	X	2	X	2	OBL
<i>Cirsium arvense</i>	X	1	X	1	FAC
<i>Cirsium vulgare</i>	X	0	X	1	FACU
<i>Cornus alba</i>	X	0	X	0	FACW
<i>Cynoglossum officinale</i>		0	X	0	FACU
<i>Elymus repens</i>	X	0	X	0	FAC
<i>Epilobium ciliatum</i>	X	1	X	1	FACW
<i>Equisetum arvense</i>	X	1	X	1	FAC
<i>Geum macrophyllum</i>			X	0	FAC
<i>Glyceria striata</i>	X	0	X	0	OBL
<i>Helianthus maximiliani</i>	X	0	X	1	UPL
<i>Juncus balticus</i>	X	1			FACW
<i>Lactuca serriola</i>			X	0	FACU
<i>Leucanthemum vulgare</i>			X	0	FACU
<i>Medicago lupulina</i>			X	0	FACU
<i>Medicago sativa</i>			X	0	UPL
<i>Melilotus officinalis</i>	X	0	X	0	FACU
<i>Mentha arvensis</i>	X	0	X	1	FACW
<i>Myosotis scorpioides</i>			X	0	FACW
<i>Nasturtium officinale</i> ***	X	2	X	2	OBL
<i>Phalaris arundinacea</i> **	X	4	X	4	FACW
<i>Poa palustris</i>	X	1	X	1	FAC
<i>Poa pratensis</i>	X	1	X	1	FAC
<i>Rumex crispus</i>	X	0	X	0	FAC
<i>Salix bebbiana</i>	X	0	X	0	FACW
<i>Salix drummondiana</i>	X	0	X	1	FACW
<i>Salix exigua</i>			X	0	FACW
<i>Scirpus microcarpus</i>	X	0	X	0	OBL
<i>Solanum dulcamara</i>			X	0	FAC
<i>Sonchus arvensis</i>	X	0			FACU
<i>Taraxacum officinale</i>	X	0	X	0	FACU
<i>Trifolium pratense</i>	X	0	X	0	FACU
<i>Trifolium repens</i>	X	0	X	0	FAC
<i>Typha latifolia</i>	X	1	X	1	OBL
<i>Urtica dioica</i>			X	0	FAC
<i>Verbascum thapsus</i>			X	0	FACU
<i>Veronica americana</i>	X	0	X	0	OBL
<i>Vicia americana</i>	X	0	X	0	FAC

*2016 National Wetland Plant List; Western Mountains, Valleys, and Coasts (WMVC) (Lichvar *et al.* 2016)

** Dominant species observed along Bowser Creek stream banks

*** Dominant species observed along Bowser Creek stream bed

Classification Values and Percent Cover Classes: 0 = <1%, 1 = 1-5%, 2 = 6-10%, 3 = 11-20%, 4 = 21-50%, 5 = >50%

Table 5. Montana State-listed noxious weed species observed in 2018 at the Bowser Creek Stream Mitigation Site.

Category*	Scientific Name	Common Name
Priority 2B	<i>Centaurea stoebe</i>	Spotted Knapweed
	<i>Cirsium arvense</i>	Canada Thistle
	<i>Cynoglossum officinale</i>	Houndstongue
	<i>Leucanthemum vulgare</i>	Oxeye Daisy
	<i>Linaria vulgaris</i>	Yellow Toadflax
	<i>Tanacetum vulgare</i>	Common Tansy

*Based on the Montana Department of Agriculture's Noxious Weed List, February 2017

4.4. Woody Plant Survival

Willows (*Salix* spp.), speckled alder (*Alnus incana*), red osier dogwood (*Cornus alba*), common snowberry (*Symphoricarpos albus*), chokecherry (*Prunus virginiana*), bog birch (*Betula pumila*), and Woods' rose (*Rosa woodsii*) were observed as planted woody vegetation species. In 2018, 190 planted trees and shrubs were located, with 176 of those observed alive (Table 6). It is unknown how many plants were installed during construction of the project; however, the revegetation plan called for planting 505 trees and shrubs. As compared to the revegetation plan, 35% (176 of 505) have survived eight years following construction. While a few of the surviving shrubs have grown to between 4 and 5 feet tall, the majority of these shrubs remain small and don't substantially contribute to the percent cover of the site by woody species. Overall, the project site includes less than 10% cover by woody species.

Table 6. Woody plant survival at Bowser Creek stream mitigation site from 2013 through 2018.

Year	Total Plants Inspected	Surviving Plants	# of Woody Plantings in Design	Woody plant survival based on planting plan
2013	127	122	505	24%
2014	127	119		24%
2015	312	279		55%
2016	181	143		28%
2017	188	147		29%
2018	190	176		35%

4.5. Bank Erosion Inventory

The prevalence of dense groundcover along the stream banks and thick mats of watercress across much of the stream bed during the late summer created challenging conditions to accurately determine the extent and cause of bank erosion, as well as photo-documenting erosion along banks that were covered with vegetation. As a result, a bank inventory was performed in April, 2016 prior to the growing season to determine causes of erosion. Currently eroding bank locations are provided on Figure 2 in Appendix A, while photos of each eroding bank can be found in Appendix C.

Observations of the reconstructed segment of Bowser Creek during the April, 2016 field visit indicated:

- Bank erosion along the left (north) side of the channel does not appear caused by scour during high flows as is typical of snowmelt driven streams.
- A retention pond has been constructed approximately 100 feet north of Bowser Creek. It appears the water surface elevation of the pond is higher than Bowser Creek, and may be a source of water seeping into Bowser Creek.
- The seepage of water from either the retention pond or from a naturally high groundwater table saturates the north bank and create localized instability where the seeps daylight along the north side of the stream channel.
- Saturated, fine grained materials along the north bank of Bowser Creek are transported downstream during high water events, resulting in bank retreat in locations where seeps enter Bowser Creek.

The bank erosion inventory conducted in 2016 identified slumping and washing of materials at three locations along the left (north) bank; however, no new erosion has been observed during the past two monitoring events. Based on these observations, the majority of bank length previously identified as eroding has stabilized. Continued calving along 15 feet of the bank at EBL3 is due to a seep entering the channel at this location, and remains the only actively eroding bank section. This bank length represents less than 2% of the overall reconstructed bank length of 880 feet.

4.6. Perpendicular Transect Surveys

Two perpendicular cross section transects were surveyed at pools and two at riffles, with maximum depth and bankfull width for each indicated in Table 7 (plots for each transect included in Appendix B). In 2018, maximum bankfull depths ranged from 1.8 to 3.1 feet and bankfull widths ranged from 6.4 to 13.7 feet. Over the past three years, the dimensions at each surveyed cross section have shown minimal adjustments.

Two segments of the channel are wider than originally constructed due to a combination of the natural degradation of coir logs placed during construction and bank slumping where seeps enter the channel from the north. These channel segments are unlikely to recover back to the design dimension due to the unnatural hydrology and continuous saturation caused by seepage from the adjacent retention pond; however they provide a diversity in channel form and are not continuing to degrade or erode. Based on the vast majority of the reconstructed channel performing as intended, attempts to narrow the channel through these relatively short, over-wide segments remains unwarranted.

Table 7. Pool and riffle widths surveyed at Bowser Creek stream mitigation site from 2013 through 2018.

Transect	Type	Max Depth (ft)						Bankfull Width (ft)					
		2013	2014	2015	2016	2017	2018	2013	2014	2015	2016	2017	2018
1	Pool	1.9	1.9	1.5	1.7	1.7	1.8	6.0	6.1	5.0	6.0	6.3	6.4
2	Riffle	2.2	2.2	1.9	2	1.9	2.1	12.7	13.5	12.5	11.8	12.8	13.1
3	Pool	3.6	3.9	3.6	3.5	3.0	3.1	14.8	13.8	13.6	13.8	13.5	13.7
4	Riffle	1.9	2	1.7	1.9	1.9	2.1	7.8	8.1	7.6	7.5	7.5	7.3
Average Riffles		2.1	2.1	1.8	2.0	1.9	2.1	10.3	10.8	10.1	9.7	10.2	10.2
Average Pools		2.8	2.9	2.6	2.6	2.4	2.5	10.4	10.0	9.3	9.9	9.9	10.1
Average All		2.4	2.5	2.2	2.3	2.1	2.3	10.3	10.4	9.7	9.8	10.0	10.1

4.7. Longitudinal Profile Survey

Repeated longitudinal profile surveys of the channel thalweg indicate the presence of at least three distinct pools within the project reach (plotted profile included in Appendix B). Surveys conducted in 2017 indicated sediment deposits had shortened two of the pools; however the most recent survey provides evidence some of this sediment may have flushed through the channel in the past year. The bed elevation of the channel has remained relatively consistent over the past year and has maintained a variety of shallower and deeper water habitat despite the gently meandering planform of the constructed channel.

Fine sediment deposits have been commonly observed in the channel, and may be due to a combination of factors, including 1) increased roughness of the channel bed and water column caused by proliferation of watercress during the growing season, 2) the reduced ability of the channel to transport fine sediments through the short reaches that have widened, 3) upstream development along Bowser Creek that may be contributing fine sediment, and 4) the inability of the channel to scour pool features due to the relatively straight channel alignment. Although reference reach data was not collected as part of this monitoring effort, Bowser Creek may also have a naturally high sediment load. The dense watercress observed in the channel will trap some of the sediment moving downstream during the growing season, and may help to narrow some of the over-wide areas along the channel if the depositional areas are able to vegetate with annual or perennial species.

4.8. Wildlife Documentation

Wildlife observations at the Bowser Creek Stream Mitigation site from 2013 through 2018 have thus far been relatively limited. No new wildlife species were observed in 2018. Limited use of this area by wildlife may be due to the proximity MT Highway 2 and U.S. Highway 93 and lack of high quality habitat.

Table 8. Wildlife observations at Bowser Creek stream mitigation site from 2013 through 2018.

Common Name	Scientific Name
Mammals	
Raccoon (scat, tracks)	<i>Procyon lotor</i>
White-tailed Deer	<i>Odocoileus virginianus</i>
Birds	
Gull sp.	<i>Larus</i> sp.
American Robin	<i>Turdus migratorius</i>
Mallard	<i>Anas platyrhynchos</i>
Red-tailed Hawk	<i>Buteo jamaicensis</i>
Sparrow sp.	<i>Passer</i> sp.

5.0 COMPARISON OF RESULTS TO PERFORMANCE STANDARDS

Monitoring of the Bowser Creek stream mitigation site is intended to document whether the reconstructed segment of the channel is meeting, or moving toward meeting the performance standards outlined in the monitoring plan. Results from the sixth year of monitoring suggests four of the six quantitative performance standards are being met eight years following completion of the project (Table 9). Thus far, the project has met the physical objectives of a) constructing 430 linear feet of new channel; b) laying back floodplain slopes adjacent to the channel from 1.5:1 to 4:1 slope or flatter; and c) implementing a revegetation plan to re-establish native riparian and upland vegetation. Channel form success is considered a qualitative criterion, and is discussed in more detail in Section 5.4.

5.1. Riparian Buffer Success

The results in Table 1 indicate the reconstructed segment of Bowser Creek has developed a densely vegetated understory, which primarily consists of herbaceous vegetation along the riparian and stream bank zones. Woody riparian vegetation is also establishing, with a 6% increase in woody planting survival observed during the 2018 monitoring event. Despite this increase in survival, the plantings are relatively small in size, and therefore offer a limited percent of the overall cover.

Vegetation monitoring of the riparian buffer indicated 75% of disturbed areas have revegetated with non-noxious weed species following construction. Non-noxious vegetation cover was determined by subtracting the percent noxious weed cover observed in the riparian transects (16%) from the total vegetation cover observed in the riparian transects (91%). Performance criteria specify at least 50% of the disturbed areas within the creditable buffer area must be vegetated with non-noxious weed species; therefore, this criterion is currently being met. Noxious weeds comprise 14% of the vegetation cover site-wide, which is above the maximum allowable limit to meet the performance criterion. The percent cover estimates recorded for all vegetation categories, including noxious weeds, may have been influenced by a combination of factors, including, but not limited to, adjacent land management, previous herbicide applications, differences in annual precipitation and temperature, calibration training completed by field staff, and other unknown factors that make it difficult to determine the exact cause(s) for increases or decreases in coverage.

Table 9. Performance standards for the Bowser Creek Stream Mitigation Site.

Type	Parameter	Performance Standard	Status	Site Meeting Performance Criteria?
Performance Criteria	Riparian Buffer Success	1a. Areas within creditable riparian buffer disturbed during construction must have 50% or greater aerial cover of non-noxious weed species by the end of the monitoring period	Vegetation transects indicate 75% cover of the riparian zones with non-noxious weed species	YES
		1b. Noxious weeds do not exceed 10% cover within the riparian buffer areas.	Vegetation transects indicate 16% cover of noxious weeds within riparian zones.	NO
	Vegetation Success	2a. Combined aerial cover of riparian and stream bank vegetation communities is at least 70%	Combined aerial cover of riparian and stream bank vegetation is 93%	YES
		2b. Planted trees and shrubs must exhibit 50% survival after 5 years	Planted tree and shrub survival documented at 35% .	NO
	Vegetation along Streambanks	3. Majority of plants on the stream bank must have root stability indices of at least 6	Dominant streambank community along both stream banks is community Type 2- <i>Phalaris arundinacea</i> , with a root stability index of 9.	YES
	Streambank Stability Success	4. Less than 25% of bank length is unstable and classified as eroding bank.	Observations noted less than 2% of the stream banks are eroding or unstable.	YES
Qualitative Criteria	Channel Form	5. Will be achieved when the stream stabilizes, includes pools and riffles, allows for flood events to occupy the floodplain, and the habitat features such as riparian plant communities have successfully established along streambanks.	Evidence of channel form success provided in Section 5.4	YES

Total combined areal vegetation cover of the riparian zone and both right and left stream banks along Bowser Creek decreased in 2018 to 93%. Both riparian and stream bank zones are primarily vegetated with herbaceous species, while woody species are establishing along the sloped areas adjacent to the channel. The performance criterion for this category specifies $\geq 70\%$ of the combined riparian and stream bank vegetation communities must have vegetation establishment; therefore, this criterion is currently being met.

Woody vegetation plantings indicated a survival rate of 35% eight years following the project's completion. The performance criteria states 50% or more of the woody plants installed must survive after five years; therefore, this criterion is not currently being met. If the remaining woody plantings survive, their continued growth and maturation should provide increased areal percent cover to the site. Percent cover by woody vegetation is currently 8%, as many of the planted shrubs and trees have yet to grow above the understory layer. Those that have are providing a more substantial overstory layer that may be utilized by migratory birds.

5.2. Vegetation along Stream Banks

Reed canary grass comprised between 21-50% cover (closer to 50%) along both stream banks in 2018. As a result, vegetation community Type 2 – *Phalaris arundinacea* was the dominant vegetation community observed along the stream banks, with an associated Winward stability rating of 9. Therefore, stream bank vegetation is successfully meeting the associated performance criteria.

5.3. Stream Bank Stability

Bank instability has primarily been tied to saturation along the north bank causing segments of the bank to slough into the channel. The majority of these areas have stabilized over the past three years. One 15-foot bank segment (EBL3) continues to exhibit soil losses where a seep is entering the channel. This bank segment represents less than 2% of the overall stream bank length of 880 feet, which is well below the 25% eroding bank success criteria threshold.

5.4. Channel Form Success

The channel form success criteria states, “will be achieved when the stream stabilizes, includes pools and riffles, allows for flood events to occupy the floodplain, and the habitat features such as riparian plant communities have successfully established along streambanks”. The following section addresses each of these channel form components as observed along Bowser Creek.

5.4.1. Channel stability

Measures to document stability of the project reach include 1) surveying a longitudinal profile along the channel thalweg, 2) surveying channel cross sections, and 3) conducting an erosion inventory along both banks. The longitudinal profile of the stream bed has thus far offered no evidence of vertical instability such as head cutting or degradation of the stream bed. Cross section surveys reveal portions of the channel have become wider since the project was constructed; however, the channel has not

continued to widen over the past five years. The channel width increased along portions of the channel within the first two years following construction and prior to the first monitoring event in 2013. Bank erosion inventories conducted over the past five years indicate erosion is due to saturated banks resulting from drainage of the adjacent retention pond, all but 15 feet of which have stabilized. While one bank continues to slough into the channel as a result of a seep, overall bank stability is good throughout the project.

5.4.2. Pool and riffle features

Inspection of the longitudinal profile indicates the presence of three distinct pool features separated by riffles. Cross section surveys indicate channel depth ranges between 1.8 and 3.1 feet. These results indicate the channel provides a variety of shallow and deep water habitat features, and supports of aquatic organisms such as salmonids and macroinvertebrates that flourish in diverse habitat types (shallow versus deep water), and variable flow velocities.

5.4.3. Floodplain connectivity

The reconstructed segment of Bowser Creek was designed to convey an estimated 2 year return interval discharge within the low flow channel. Discharges greater than the 2 year flow are able to access a floodplain approximately 14 feet wide with a design grade of 5% slope toward the channel. Beyond this floodplain, the floodway has been designed to convey up to a 100 year discharge without over-topping Highway 2.

5.4.4. Riparian habitat along stream banks

The vegetation along the banks of Bowser Creek is dominated by reed canarygrass, although several additional species have been documented along the banks (see Section 4.2). The reed canarygrass provides excellent resistance to bank erosion. Although five species of planted and/or volunteer woody shrubs were observed, their contribution to cover along the banks is limited to an estimated 1%. The unrooted willow stems installed along the outside meander bends either did not successfully establish or were washed out where the channel widened. As a result, woody species composition along the banks is lacking. Photo documentation of the stream channel is provided in Appendix C and offers additional evidence of riparian vegetation composition along Bowser Creek's banks and riparian corridor. Based on these results and the condition of the riparian corridor along Bowser Creek, this success criterion is currently being met.

6.0 LITERATURE CITED

- Elzinga, C.L., D.W. Salzer, and J.W. Willoughby. 1998. *Measuring and monitoring plant populations*. Bureau of Land Management (BLM) Technical Reference 1730-1. Washington, DC: U.S. Department of the Interior.
- Fenner, Patti. 2008. *Effects of invasive plants on public land management of pinyon-juniper woodlands in Arizona*. In: Gottfried, Gerald J.; Shaw, John D.; Ford, Paulette L., compilers. 2008. Ecology, management, and restoration of pinon-juniper and

ponderosa pine ecosystems: combined proceedings of the 2005 St. George, Utah and 2006 Albuquerque, New Mexico workshops. Proceedings RMRS-P-51. Fort Collins, CO: U.S. Department of Agriculture, Forest Service, Rocky Mountain Research Station. p. 113-120.

Kazinczi, G., I. Beres, and S.S. Narwal. 2001. *Allelopathic Plants. 1. Canada thistle [Cirsium arvense (L.) Scop]*. Allelopathy Journal 8(2): 29-40.

Lichvar, R.W., D.L. Banks, W.N. Kirchner, and N.C. Melvin. 2016. *The National Wetland Plant List: 2016 Update of Wetland Ratings*. Phytoneuron 2016-30: 1-17. Published 28 April 2016. ISSN 2153 733X

Montana Department of Agriculture. *Montana Noxious Weed List*. February 2017. Accessed October 2018 at:
<http://agr.mt.gov/Portals/168/Documents/Weeds/2017%20Noxious%20Weed%20List.pdf>.

Ravlić M., B. R. Baličević, M. Knežević, and J. Ravlić. 2013. *Allelopathic effect of creeping thistle (Cirsium arvense (L.) Scop.) on germination and early growth of winter wheat and winter barley*. In: 48th Croatian & 8th International Symposium on Agriculture February 17 - 22, 2013 . Dubrovnik . Croatia. eProceedings. Published by: Faculty of Agriculture.


Watanabe, Y., P. Novaes, R.M. Varela, J.M.G. Molinillo, H. Kato-Noguchi, F.A. Macias. 2014. *Phytotoxic Potential of Onopordum acanthium L. (Asteraceae)*. Chemistry & Biodiversity. 11. 1247-55. 10.1002/cbdv.201400070.

Winward, 2000. Monitoring the Vegetation Resources in Riparian Areas. Gen. Tech. Report RMRS-GTR.47. Ogden, UT: U.S. Department of Agriculture, Forest Service, Rocky Mountain Research Station.

Appendix A

Project Site Maps

MDT Stream Mitigation Monitoring
Bowser Creek
Flathead County, Montana



Legend

- Photo Points
- Channel Thalweg
- Major Station (100')
- Minor Station (25')
- Eroding Banks
- Pool and Riffle Transects
- Riparian Transects

0 37.5 75 150 Feet




Bowser Creek - 2018 Monitoring Features

Figure 2

Date: 10/24/2018

Bowser_features2018.mxd



Legend

- Project Boundary
- Vegetation Community Boundary

- ✕ *Centaurea stoebe*
- ◆ *Cirsium arvense*
- ◆ *Cynoglossum officinale*
- ◆ *Leucanthemum vulgare*
- ✱ *Linaria vulgaris*

- ② *Phalaris arundinacea* Community
- ③ *Nasturtium officinale* Community
- ④ *Cirsium* spp./*Bromus inermis* Community
- ⑤ *Elymus* spp./*Festuca ovina* Community



Bowser Creek - 2018 Noxious Weeds and Vegetation Community

Figure 3

Date: 10/19/2018


Bowser_monitor2018.mxd

Appendix B


Perpendicular Transect and Longitudinal Profile Plots

MDT Stream Mitigation Monitoring
Bowser Creek
Flathead County, Montana


Bowser Creek Longitudinal Profiles: 2014 - 2018




Bowser Transect #1 - Pool




Bowser Transect #2 - Riffle



Bowser Transect #3 - Pool



Bowser Transect #4 - Riffle



Appendix C

Project Area Photos

MDT Stream Mitigation Monitoring
Bowser Creek
Flathead County, Montana

PHOTO INFORMATION

PROJECT NAME: Bowser Creek Stream Mitigation Site

DATE: 2013 and 2018 Monitoring Events



2013



2018

Photo 1: View looking west (upstream) of Bowser Creek.



2013



2018

Photo 2.1: View looking northwest at Bowser Creek.



2013



2018

Photo 2.2: View across Bowser Creek looking north.

PHOTO INFORMATION

PROJECT NAME: Bowser Creek Stream Mitigation Site

DATE: 2013 and 2018 Monitoring Events



2013



2018

Photo 2.3: View looking east (downstream) of Bowser Creek from photo point 3.



2013



2018

Photo 2.4: View looking east across Bowser Creek. from photo point 2.



2013



2018

Photo 3: View looking east (downstream) of Bowser Creek from photo point 3.

PHOTO INFORMATION

PROJECT NAME: Bowser Creek Stream Mitigation Site

DATE: 2013 and 2018 Monitoring Events



2013



2018

Additional Photo 1: Prolific watercress growth shown in 2013 was less prevalent in 2018.



2013



2018

Additional Photo 2: Eroding bank EBL4.



2013



2018

Additional Photo 3: Widened channel segment.

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T1 LEFT: LOOKING SOUTHWEST TO T1 RIGHT



T1 RIGHT: LOOKING NORTHEAST TO T1 LEFT

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T1 LEFT: LOOKING WEST UPSTREAM



T1 LEFT: LOOKING SOUTH DOWNSTREAM

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T1: LOOKING WEST UPSTREAM FROM MIDDLE OF CREEK



T1: LOOKING EAST DOWNSTREAM FROM MIDDLE CREEK

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T1 RIGHT: LOOKING WEST UPSTREAM



T1 RIGHT: LOOKING EAST DOWNSTREAM

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T2 LEFT: LOOKING SOUTH TO T2 RIGHT



T2 RIGHT: LOOKING NORTH TO T2 LEFT

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T2 LEFT: LOOKING WEST UPSTREAM



T2 LEFT: LOOKING SOUTH EAST DOWNSTREAM

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T2: LOOKING WEST UPSTREAM FROM MIDDLE CREEK



T2: LOOKING EAST DOWNSTREAM FROM MIDDLE CREEK

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T2 RIGHT: LOOKING WEST UPSTREAM



T2 RIGHT: LOOKING EAST DOWNSTREAM

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T3 LEFT: LOOKING SOUTH TO T3 RIGHT



T3 RIGHT: LOOKING NORTH TO T3 LEFT

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T3 LEFT: LOOKING WEST UPSTREAM



T3 LEFT: LOOKING EAST DOWNSTREAM

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T3: LOOKING WEST UPSTREAM FROM MIDDLE OF CREEK



T3: LOOKING EAST DOWNSTREAM FROM MIDDLE CREEK

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T3 RIGHT: LOOKING WEST UPSTREAM



T3 RIGHT: LOOKING EAST DOWNSTREAM

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T4 LEFT: LOOKING SOUTH TO T4 RIGHT



T4 RIGHT: LOOKING NORTH TO T4 LEFT

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T4 LEFT: LOOKING WEST UPSTREAM



T4 LEFT: LOOKING EAST DOWNSTREAM

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T4: LOOKING WEST UPSTREAM FROM MIDDLE OF CREEK



T4: LOOKING EAST DOWNSTREAM FROM MIDDLE CREEK

PROJECT NAME: 2018 MDT STREAM MITIGATION—BOWSER CREEK

DATE: 8-14-18



T4 RIGHT: LOOKING WEST UPSTREAM



T4 RIGHT: LOOKING EAST DOWNSTREAM

Appendix D

Construction Plan Sheets


MDT Stream Mitigation Monitoring
Bowser Creek
Flathead County, Montana

DETAIL

TABLE OF CONTENTS & DETAILS




ZONE D COR BUNDLES WITH WILLOW CUTTINGS AND LAYERING
SCALE: NOT TO SCALE



ZONE D RIPARIAN PLUG PLANTING
FOR INSTALLED AND REMOVED PLUGS
SCALE: NOT TO SCALE

SPACING



SHRUB PLANTING
SCALE: NOT TO SCALE

DESIGNER
DRAWN
APPROVED
REVIEWED
CHECKED
DATE


INITIALS DATE

TABLE OF CONTENTS

DETAILS

TABLE OF CONTENTS & DETAILS	SHEET NO.
BOWSER CREEK	V1
VEGETATION TYPICAL SECTIONS & SUMMARY	V2
BOWSER CREEK	V3
VEGETATION PLAN	V4
US HWY 2 DETENTION POND	
VEGETATION PLAN	

NOTE: PLACE JUTE NETTING ON SLOPES GREATER THAN 33%. CUT NETTING TO MATCH SLOPE. SEE SPECIAL PROVISIONS FOR JUTE SPECIFICATION.



TREE PLANTING
SCALE: NOT TO SCALE


KBP - US 2 WIDENING
TABLE OF CONTENTS &
DETAILS

NO SCALE


NOTES: 1. SEE ROADWAY PLANS FOR CHANNEL CONSTRUCTION DETAILS. GENERAL CONCEPTUAL DESIGN. FOR INFORMATION ONLY.

DETAIL
BOWSER CREEK VEGETATION TYPICAL SECTIONS & SUMMARY

STATE PROJECT NUMBER SHEET NO
MONTANA NH 154931 V2
CSF - 0.999470385



BOWSER CREEK CHANNEL CHANGE RIFFLE TYPICAL SECTION
SCALE: NOT TO SCALE



BOWSER CREEK CHANNEL CHANGE POOL TYPICAL SECTION
SCALE: NOT TO SCALE

CHANNEL PLANTING SEQUENCE

1. PLACE COR ROLL AS PER COR ROLLS DETAIL IN ROADWAY PLANS AND SPECIAL PROVISIONS.
2. INSTALL PLANTS BETWEEN THE DATES OF OCTOBER 1 AND MAY 15 PROVIDED THE GROUND IS NOT FROZEN.
3. PLANT WILLOW CUTTINGS AND BUNDLES AS DETAIL.
4. PLANT WILLOW CUTTINGS AND BUNDLES AS DETAIL.
5. INSTALL JUTE NETTING ON SLOPES GREATER THAN 3:1 AS PER SPECIAL PROVISIONS.
6. SEED UPLAND AREA 4 AND RIPARIAN AREA 5 AS PER SEEDING SPECIAL PROVISIONS.
7. APPLY INTERGRANULAR FUNGUS AS PER SPECIAL PROVISIONS.
8. APPLY INTERGRANULAR FUNGUS AS PER SPECIAL PROVISIONS.
9. APPLY NEED FREE ORGANIC COMPOST MULCH AS PER SPECIAL PROVISIONS.

BOWSER CREEK CHANNEL CHANGE PLANT LIST				
ZONE A UPLAND				
TREES				
TYPE	BOTANICAL NAME	COMMON NAME	QTY	SIZE
TP	BETULA PAPERIFERA	PAPER BIRCH	6	10' BAB
PP	PINUS STROBILATA	PINE	1	7' BAB
ZONE B TRANSITIONAL				
TREES				
TYPE	BOTANICAL NAME	COMMON NAME	QTY	SIZE
TP	AM. LANCEOLATA	AMERICAN LARCH	124	8' GAL.
PP	PINUS VIRGINIANA	PINE	174	8' GAL.
TP	QUERCUS ROBUR	WHITE OAK	174	8' GAL.
PP	PINUS STROBILATA	PINE	174	8' GAL.
TP	QUERCUS ROBUR	WHITE OAK	174	8' GAL.
PP	PINUS STROBILATA	PINE	174	8' GAL.
ZONE C SEASONALLY FLOODED				
TREES				
TYPE	BOTANICAL NAME	COMMON NAME	QTY	SIZE
TP	BETULA PAPERIFERA	PAPER BIRCH	5	15' GAL.
PP	PINUS STROBILATA	PINE	5	15' GAL.
ZONE D SEMI-PERMANENTLY FLOODED				
TREES				
TYPE	BOTANICAL NAME	COMMON NAME	QTY	SIZE
TP	BETULA PAPERIFERA	PAPER BIRCH	5	15' GAL.
PP	PINUS STROBILATA	PINE	5	15' GAL.
COR ROLL LAYERING				
TYPE	BOTANICAL NAME	COMMON NAME	QTY	SIZE
TP	BETULA PAPERIFERA	PAPER BIRCH	27	5' GAL.
PP	PINUS STROBILATA	PINE	27	5' GAL.
TP	BETULA PAPERIFERA	PAPER BIRCH	27	5' GAL.
PP	PINUS STROBILATA	PINE	27	5' GAL.
STREAMBANK PLUGS				
TYPE	BOTANICAL NAME	COMMON NAME	QTY	SIZE
TP	BETULA PAPERIFERA	PAPER BIRCH	666	CUTTINGS
PP	PINUS STROBILATA	PINE	666	CUTTINGS
JUTE NETTING				
TYPE	BOTANICAL NAME	COMMON NAME	QTY	SIZE
TP	BETULA PAPERIFERA	PAPER BIRCH	120	PLUGS
PP	PINUS STROBILATA	PINE	120	PLUGS
TP	BETULA PAPERIFERA	PAPER BIRCH	120	PLUGS
PP	PINUS STROBILATA	PINE	120	PLUGS

* FOR INFORMATION ONLY. INCLUDE ALL COSTS AND INCIDENTAL ITEMS ASSOCIATED WITH THE INSTALLATION OF THIS ITEM IN THE LUMP SUM BID PRICE FOR "VEGETATION".

JUTE NETTING		
STATION		
FROM	TO	square meters
35+34.77	38+58.67	200
TOTAL		200

* FOR INFORMATION ONLY. INCLUDE ALL COSTS AND INCIDENTAL ITEMS ASSOCIATED WITH THE INSTALLATION OF THIS ITEM IN THE LUMP SUM BID PRICE FOR "VEGETATION".

KBP - US 2 WIDENING
BOWSER CREEK
VEGETATION TYPICAL SECTIONS
& SUMMARY


NO SCALE

LEGEND	
	AREA 4 UPLAND SEED MIX
	AREA 5 RIPARIAN SEED MIX
	PROPOSED SHRUB PLANTING
	COR ROLLS
	PROPOSED TREE PLANTING

DETAIL BOWSER CREEK VEGETATION PLAN

STATE	PROJECT NUMBER	SHEET NO
MONTANA	NH 15(93)	V3
CSF - 0.999470385		

MDTX MONTANA DEPARTMENT OF TRANSPORTATION
CAAD



KBP - US 2 WIDENING
BOWSER CREEK
VEGETATION PLAN
SCALE = 1:250

NOTE: THIS PLAN IS A GRAPHIC REPRESENTATION REFER TO SECTIONS AND PLANT LISTS FOR DETAILED ZONAL PLACEMENT.

DESIGNER	DATE
INMAN	
APPROVED	
REVISED	

1/2/2010	REVISED BY	1/2/2010
1/2/2010	CHECKED BY	1/2/2010
1/2/2010	DESIGNED BY	1/2/2010

SE Engineering, Inc.