





NOTES:

- INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
- USE WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS. AFFIX BLOCKS TO POSTS WITH TWO 16 PENNY GALV. NAILS OR 14 GAUGE WIRE WRAP.
- ATTACH REFLECTORS TO POSTS EVERY 25 FEET [7.62 m], INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FABRICATE REFLECTORS FROM 0.063" [1.6] THICK ALUMINUM ALLOY PER SECTION 704 OR PLASTIC REFLECTORS WITH A URETHANE HINGE. FASTEN REFLECTOR TO WOOD POST USING TWO 16 PENNY RING-SHANKED GALVANIZED NAILS AND TWO 3/16" [4.8] DIA. WASHERS IN PRE-DRILLED HOLES.
- ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 27 3/4" [705.]
- WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" [0.6 m] FROM THE TRAFFIC LANE.
- DO NOT INSTALL W-BEAM GUARDRAIL FOR OBSTACLES WITHIN 5.3' [1.6 m] OF THE FACE OF THE RAIL.
- USE LOWER HOLE ON NEW CONSTRUCTION INSTALLATIONS.
- USE 6' [1830] POSTS FOR STANDARD INSTALLATIONS.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.




DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 704	DWG. NO. 606-05A
METAL GUARDRAIL - WOOD POSTS (MGS)	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	




NOTES:

- INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
- USE ROUTED WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS.
- ATTACH REFLECTORS TO POSTS EVERY 25 FEET [7.62 m], INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FASTEN REFLECTOR TO STEEL POST USING AN APPROVED ADHESIVE. REFLECTORS MAY BE BOLTED TO POSTS PROVIDED HOLES IN POSTS ARE DRILLED BEFORE BEING GALVANIZED.
- ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 27 3/4" [705].
- WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" [0.6 m] FROM THE TRAFFIC LANE.
- STEEL POSTS WITH OTHER POST HOLE CONFIGURATIONS MAY BE ACCEPTED, PROVIDED THEY HAVE AT LEAST THE HOLES DETAILED ON THIS DRAWING AND THEY MEET AASHTO'S PUBLICATION, "A GUIDE TO STANDARDIZED HIGHWAY BARRIER HARDWARE" AND "MASH" REQUIREMENTS.
- DO NOT INSTALL W-BEAM GUARDRAIL FOR OBSTACLES WITHIN 5.3' [1.6 m] OF THE FACE OF THE RAIL.
- USE LOWER HOLE ON NEW CONSTRUCTION INSTALLATIONS.
- USE 6' [1830] POSTS FOR STANDARD INSTALLATIONS.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-05B
METAL GUARDRAIL - STEEL POSTS (MGS)	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	



QUARTER POST SPACING


NOTES:







- ① SEE DTL. DWG. NO. 606-05A AND 606-05B FOR STANDARD MGS GUARDRAIL AND ASSOCIATED HARDWARE.
 - ② OBSTACLES CLOSER TO THE FACE OF RAIL THAN THE INDICATED LIMITS REQUIRE THE USE OF A RIGID BARRIER SYSTEM WITH LITTLE TO NO DYNAMIC DEFLECTION.
 - ③ LAP ALL RAIL IN THE DIRECTION OF ADJACENT TRAFFIC.
 - ④ ALL POSTS AND BLOCKS ARE STANDARD DIMENSIONS AS PER DETAILED DRAWING NO. 606-05A AND 606-05B.
 - ⑤ RAIL IS RWM08a-b*.
 - ⑥ PAY LIMIT DEFINED BY RAILS CONTAINING A SECTION OF REDUCED POST SPACING. LIMITS SHOWN ARE FOR EXAMPLE ONLY, ACTUAL PAY LIMITS WILL DIFFER DEPENDING UPON SPLICE LOCATIONS.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



HALF POST SPACING

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-07
SECTION 606	
STIFFENED GUARDRAIL SECTIONS (MGS)	
 MONTANA DEPARTMENT OF TRANSPORTATION	



SECTION A-A

NOTES:

- SEE DTL. DWG. NO. 606-05A AND 606-05B FOR STANDARD MGS GUARDRAIL AND ASSOCIATED HARDWARE.
- LAP ALL RAIL IN THE DIRECTION OF ADJACENT TRAFFIC.
- TYPICAL SPLICE LOCATIONS SHOWN, MAY VARY BASED ON ACTUAL RAIL SEGMENTS INSTALLED. PAY LIMITS NOT DEPENDENT ON SPLICE LOCATION.
- DO NOT INSTALL MGS LONG SPAN GUARDRAIL FOR ABOVE-GRADE OBSTACLES WITHIN 9.7' OF THE FACE OF THE RAIL.
- THE OBSTRUCTION (CULVERT OPENING OR EDGE OF BRIDGE DECK) MUST BE LOCATED AT OR BEYOND THE BACK OF THE CRT POSTS.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

DETAILED DRAWINGS

REFERENCE DWG. NO. 606-09
STANDARD SPEC. SECTION 606

LONG SPAN GUARDRAIL (MGS)






EFFECTIVE: JAN 23, 2020



--REVISED--
JAN 15, 2026


12/12/2025 11:20 AM

STDDR606009.DWG



- NOTES:
1. INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
 2. USE WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS. AFFIX BLOCKS TO POSTS WITH TWO 16 PENNY GALV. NAILS OR 14 GAUGE WIRE WRAP.
 3. ATTACH REFLECTORS TO POSTS EVERY 25', INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FABRICATE REFLECTORS FROM 0.063" THICK ALUMINUM ALLOY PER SECTION 704 OR PLASTIC REFLECTORS WITH A URETHANE HINGE. FASTEN REFLECTOR TO WOOD POST USING TWO 16 PENNY RING-SHANKED GALVANIZED NAILS AND TWO 3/16" DIA. WASHERS IN PRE-DRILLED HOLES.
 4. ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 27 3/4".

5. DO NOT INSTALL LONG POST W-BEAM GUARDRAIL FOR OBSTACLES WITHIN 5.9' OF THE FACE OF THE RAIL.
 6. USE LOWER HOLE ON NEW CONSTRUCTION INSTALLATIONS.
 7. BEGIN INSLOPE BREAK AT CENTER OF POST.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



DETAILED DRAWINGS

REFERENCE DWG. NO.
STANDARD SPEC. 606-11A
SECTION 606, 704






METAL GUARDRAIL - LONG POSTS - WOOD (MGS)

EFFECTIVE: JAN 23, 2020




--REVISED--
JAN 15, 2026

12/12/2025 11:22 AM STDDR606011A.DWG




- NOTES:
- ① INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
 - ② USE ROUTED WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS.
 - ③ ATTACH REFLECTORS TO POSTS EVERY 25', INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FASTEN REFLECTOR TO STEEL POST USING AN APPROVED ADHESIVE. REFLECTORS MAY BE BOLTED TO POSTS PROVIDED HOLES IN POSTS ARE DRILLED BEFORE BEING GALVANIZED.
 - ④ ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 27 $\frac{3}{4}$ ".
 - ⑤ DO NOT INSTALL LONG POST W-BEAM GUARDRAIL FOR OBSTACLES WITHIN 5.9' OF THE FACE OF THE RAIL.
 - ⑥ USE LOWER HOLE ON NEW CONSTRUCTION INSTALLATIONS.
 - ⑦ LOCATE POST 12" (MAXIMUM) FROM INSLOPE BREAK.
 - ⑧ STEEL POSTS WITH OTHER POST HOLE CONFIGURATIONS MAY BE ACCEPTED, PROVIDED THEY HAVE AT LEAST THE HOLES DETAILED ON THIS DRAWING AND THEY MEET AASHTO'S PUBLICATION, "A GUIDE TO STANDARDIZED HIGHWAY BARRIER HARDWARE" AND "MASH" REQUIREMENTS.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




DETAILED DRAWINGS	
REFERENCE STANDARD SPEC. SECTION 606, 704	DWG. NO. 606-11B
METAL GUARDRAIL - LONG POSTS - STEEL (MGS)	
EFFECTIVE: JAN 23, 2020	

--REVISED--
JAN 15, 2026




TRINITY SOFTSTOP ①





ROAD SYSTEMS MSKT WITH 9'-4 1/2" RAIL PANEL ①


- ① OPTIONAL TERMINAL SECTION SYSTEMS VARY, REFER TO MANUFACTURER'S DETAIL AND ASSEMBLY INSTRUCTIONS.
- ② SEE DTL. DWG. NO. 606-05A AND 606-05B FOR MGS GUARDRAIL. SEE DTL. DWG. NO. 606-20 IF CONNECTING TO EXISTING RAIL THAT IS NOT WITHIN THE MANUFACTURER'S HEIGHT TOLERANCE.
- ③ LENGTH OF NEED POST LOCATION EQUALS STATION LIMITS INDICATED IN THE PLANS.
- ④ 7'-0" [2.13m] WIDENING DIMENSION ALLOWS FOR OPTIONAL TERMINAL SECTION FLARE AND SYSTEM WIDTH. A MINIMUM WIDENING DISTANCE OF 5'-0" [1.52m] IS REQUIRED BEHIND POST LOCATION #1.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.



DETAILED DRAWINGS	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-13
SECTION 606, 203	
MASH OPTIONAL TERMINAL SECTIONS	
EFFECTIVE: JAN 23, 2020	
	
<div> <div> --REVISED-- JUN 27, 2024 </div> <div> 5/24/2024 1:01 PM STDDRD606013.DWG </div> </div>	



MGS FOUNDATION TUBE DETAILS
PTE06*



MGS END POST DETAILS
PDF01* - MGS HEIGHT




NOTES:


- ① SEE DTL. DWG. NO. 606-05A AND 606-05B FOR MGS GUARDRAIL.
 - ② LAP GUARDRAIL IN THE DIRECTION OF ADJACENT TRAFFIC LANE.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-18
ONE-WAY DEPARTURE TERMINAL SECTION (MGS)	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	



HEIGHT TRANSITION DETAIL - IRREGULAR RAIL OPTION
(TRANSITION FROM 27 3/4" (OR GREATER) TO 31" GUARDRAIL MOUNTING HEIGHT)



HEIGHT TRANSITION DETAIL - IRREGULAR POST SPACING OPTION
(TRANSITION FROM 27 3/4" (OR GREATER) TO 31" GUARDRAIL MOUNTING HEIGHT)

NOTES:

- ① THE MGS TO METAL GUARDRAIL TRANSITION IS PAID FOR AS LINEAR FEET OF MGS GUARDRAIL.
- ② SEE DTL. DWG. NO. 606-05A, 606-05B, 606-11A, AND 606-11B FOR MGS GUARDRAIL AND ASSOCIATED HARDWARE.
- ③ LAP ALL W-BEAM RAIL IN THE DIRECTION OF ADJACENT TRAFFIC.

DETAILED DRAWINGS

REFERENCE DWG. NO.
STANDARD SPEC. 606-20
SECTION 606

**MGS TO METAL GUARDRAIL
TRANSITION**


EFFECTIVE: JAN 23, 2020








--REVISED--
JAN 15, 2026

11/29/2025 8:43 AM

STDDRD606020.DWG




- NOTES:
- ① SEE DTL. DWG. NO. 606-05A FOR STANDARD MGS GUARDRAIL AND ASSOCIATED HARDWARE.
 - ② LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
 - ③ DO NOT FLARE BRIDGE APPROACH SECTIONS.
 - ④ WHERE CURB EXTENDS UPSTREAM OF POST NO. 5, FURNISH 2 NESTED 12-GAUGE W-BEAM RAILS FOR THIS 12'-6\"/>
 - ⑤ USE WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS. AFFIX BLOCKS TO POSTS WITH TWO 16 PENNY GALV. NAILS OR 14 GAUGE WIRE WRAP.
 - ⑥ SEE BRIDGE PLANS FOR CONNECTION DETAILS AND BOLT LOCATIONS.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-23A
MGS THRIE BEAM BRIDGE APPROACH SECTION -WOOD POSTS	
MDT★ MONTANA DEPARTMENT OF TRANSPORTATION	









NOTES:

- ① SEE DTL. DWG. NO. 606-05A FOR STANDARD MGS GUARDRAIL AND ASSOCIATED HARDWARE.
- ② LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
- ③ DO NOT FLARE BRIDGE APPROACH SECTIONS.
- ④ WHERE CURB EXTENDS UPSTREAM OF POST NO. 5, FURNISH 2 NESTED 12-GAUGE W-BEAM RAILS FOR THIS 12'-6" [3810] SECTION. INCLUDE THIS ADDITIONAL RAIL IN THE COST OF THE BRIDGE APPROACH SECTION.
- ⑤ USE WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS. AFFIX BLOCKS TO POSTS WITH TWO 16 PENNY GALV. NAILS OR 14 GAUGE WIRE WRAP.
- ⑥ SEE BRIDGE PLANS FOR CONNECTION DETAILS AND BOLT LOCATIONS.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



W-BEAM TO THRIE-BEAM TRANSITION SECTION
RWT02a*
(RWT02b* FOR OPPOSITE DIRECTION)



UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-23B
MGS THRIE BEAM BRIDGE APPROACH SECTION - STEEL POSTS	
MDT★ MONTANA DEPARTMENT OF TRANSPORTATION	

ELEVATION

PLAN

DETAIL "A"

PLATE WASHER

SECTION A-A


METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1
(FOR BRIDGES USING CONCRETE BARRIER RAIL)

METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 2
(FOR BRIDGES WITHOUT CURBS)


METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3
(FOR BRIDGES WITH EXISTING CONCRETE CURBS)

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

<i>DETAILED DRAWING</i>	
<i>REFERENCE</i>	<i>DWG. NO.</i>
<i>STANDARD SPEC.</i>	<i>606-24A</i>
<i>SECTION 606</i>	
<i>BRIDGE APPROACH</i>	
<i>SECTIONS -</i>	
<i>WOOD POSTS</i>	



**MONTANA DEPARTMENT
OF TRANSPORTATION**



25'-0" [7.62 m] BRIDGE APPROACH SECTION PAY LIMITS

W6 x 8.5 (MIN.) x 6'-0" [W152 x 12.6 kg/m (MIN.) x 1830]
STEEL POST
W/ 7 5/8" x 5 5/8" (MIN.) x 1'-2" [195 x 145 (MIN.) x 350]
BLOCKOUT

1'-6 3/4" [476.25]
3'-1 1/2" [952.50]
6'-3" [1905.00]

STANDARD W-BEAM GUARDRAIL
PAY LIMITS ⑨

* GUARDRAIL BLOCKOUT FOR STANDARD P

12'-6" [3810.00]
USE DOUBLED GUARDRAIL BEAMS

METAL GUARDRAIL ⑨

Diagram illustrating the cross-section of a bridge approach section, showing various components and dimensions.

Dimensions and Labels:

- 25'-0" [7.62 m] BRIDGE APPROACH SECTION PAY LIMITS** (Overall length)
- END OF EXISTING CURB** (Left boundary)
- RAIL SPLICE** (Left boundary)
- 6 5/8" [168.28]** (Dimension for the leftmost section)
- 1'-6 3/4" [476.25]** (Dimension for the first section)
- 3'-1 1/2" [952.50]** (Dimension for the second section)
- 12'-6" [3810.00]** (Dimension for the third section)
- USE DOUBLED GUARDRAIL BEAMS** (Label for the third section)
- METAL GUARDRAIL ⑨** (Label for the guardrail)
- STANDARD W-BEAM GUARDRAIL** (Label for the guardrail)
- PAY LIMITS ⑨** (Right boundary)

Components and Materials:

- ① W8 x 21 (MIN.) x 8'-0"**
[W203 x 31 kg/m (MIN.) x 2440] STEEL POST W/ 11 5/8" x 5 5/8" (MIN.) x 1'-2" [295 x 145 (MIN.) x 350] BLOCKOUT
- ② W6 x 8.5 x 7'-0"**
[W152 x 12.6 kg/m x 2135] STEEL POST W/ 11 5/8" x 5 5/8" (MIN.) x 1'-2" [295 x 145 (MIN.) x 350] BLOCKOUT
- ③ W6 x 8.5 x 6'-0"**
[W152 x 12.6 kg/m x 1830] STEEL POST W/ 7 5/8" x 5 5/8" (MIN.) x 1'-2" [195 x 145 (MIN.) x 350] BLOCKOUT

Notes:


- PER CONCRETE DETAILS SEE DTL. 606-27
- SEE DTL. 606-88
- OTHERWISE USE BRIDGE PLANS

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

UNITS SHOWN IN BRACKETS [] ARE
METRIC AND ARE IN MILLIMETERS (mm)
UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-24B
SECTION 606	


BRIDGE APPROACH
SECTIONS -
STEEL POSTS




NOTES:

- ① TAPERED CONCRETE CURBS:
TYPE 1, SEE DTL. DWG. NO. 606-26
TYPE 3, SEE DTL. DWG. NO. 606-27
- ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
- ③ PORTIONS OF GUARDRAIL & BLOCKOUTS ARE OMITTED FOR CLARITY.
- ④ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE. (SEE DTL. DWG. NO. 606-05B).
- ⑤ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
- ⑥ USE ROUTED WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
- ⑦ DO NOT FLARE BRIDGE APPROACH SECTIONS.
- ⑧ SEE DTL. DWG. NO. 606-25B FOR SKEWED BRIDGES.
- ⑨ SEE DTL. DWG. NO. 606-05B FOR METAL GUARDRAIL (W-BEAM).

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1
(FOR SKEWED BRIDGES USING CONCRETE BARRIER RAIL)





METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3
(FOR SKEWED BRIDGES WITH EXISTING CONCRETE CURBS)

NOTES:


- ① TAPERED CONCRETE CURBS:
TYPE 1, SEE DTL. DWG. NO. 606-26
TYPE 3, SEE DTL. DWG. NO. 606-27
- ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
- ③ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
(SEE DTL. DWG. NO. 606-05A).
- ④ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
- ⑤ USE WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
- ⑥ DO NOT FLARE BRIDGE APPROACH SECTIONS.
- ⑦ SEE DTL. DWG. NO. 606-24A FOR ADDITIONAL INFORMATION.
- ⑧ SEE DTL. DWG. NO. 606-05A FOR METAL GUARDRAIL (W-BEAM).

UNITS SHOWN IN BRACKETS [] ARE
METRIC AND ARE IN MILLIMETERS (mm)
UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-25A
SECTION 606	
SKEWED BRIDGE APPROACH SECTIONS - WOOD POSTS	
 MONTANA DEPARTMENT OF TRANSPORTATION	



METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1
(FOR SKEWED BRIDGES USING CONCRETE BARRIER RAIL)









METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3
(FOR SKEWED BRIDGES WITH EXISTING CONCRETE CURBS)

NOTES:

- ① TAPERED CONCRETE CURBS:
TYPE 1, SEE DTL. DWG. NO. 606-26
TYPE 3, SEE DTL. DWG. NO. 606-27
- ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
- ③ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
(SEE DTL. DWG. NO. 606-05B).
- ④ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
- ⑤ USE WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
- ⑥ DO NOT FLARE BRIDGE APPROACH SECTIONS.
- ⑦ SEE DTL. DWG. NO. 606-24B FOR ADDITIONAL INFORMATION.
- ⑧ SEE DTL. DWG. NO. 606-05B FOR METAL GUARDRAIL (W-BEAM).

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-25B
SECTION 606	
SKEWED BRIDGE APPROACH SECTIONS - STEEL POSTS	
 MONTANA DEPARTMENT OF TRANSPORTATION	




- NOTES:
- ① TAPERED CONCRETE CURB IS USED WITH BRIDGE APPROACH SECTION TYPE 1 (SEE DTL. DWG. NO. 606-24A AND 606-24B).
 - ② FURNISH WIRE ROPE MEETING SECTION 705.
 - ③ FURNISH GRADE 60 [420] REINFORCING STEEL MEETING SECTION 711..
 - ④ ALL CONCRETE IS CLASS GENERAL.
TOTAL CONCRETE PER 7' [2100 mm] TAPERED CURB EST. = 0.2 C.Y. [0.17 m³]
TOTAL REBAR WEIGHT PER 7' [2100 mm] TAPERED CURB EST. = 34 LB [15.1 kg].

BILL OF REINFORCING STEEL (ONE SECTION ONLY)									
<p style="text-align: center;">TYPE 1</p>									
BENT BARS (ALL DIMENSIONS ARE OUT TO OUT)									
MARK	SIZE	NO.	TYPE	LENGTH	A	B	C	D	E
C1	#4	1	1	4'-8"	11"	1'-4"	1'-1"	9"	3 1/2"
C2				4'-2"	9 1/2"	1'-2"	11 1/2"	8"	
C3				3'-9"	8 1/2"	1'- 1/2"	10"	7"	
C4				3'-3"	7"	10 1/2"	8"	6 1/2"	
C5				2'-11"	6"	9"	7"	6"	
C6				2'-4"	4"	7"	5"	5"	
C7				2'-0"	3 1/2"	5 1/2"	3 1/2"	4 1/2"	3 1/2"
C8		1	1	1'-6"	2"	3 1/2"	2"	3 1/2"	1 1/2"
B1	#4	4	STRAIGHT	6'-9"	~	~	~	~	~


METRIC BILL OF REINFORCING STEEL (ONE SECTION ONLY)									
<p style="text-align: center;">TYPE 1</p>									
BENT BARS (ALL DIMENSIONS ARE OUT TO OUT IN mm)									
MARK	SIZE	NO.	TYPE	LENGTH	A	B	C	D	E
C1	#13	1	1	1360	270	395	330	205	80
C2				1225	240	350	290	185	
C3				1090	205	310	255	160	
C4				955	175	265	215	140	
C5				820	145	220	175	120	
C6				695	115	180	140	100	
C7				555	80	135	100	80	80
C8		1	1	415	50	90	60	55	40
B1	#13	4	STRAIGHT	2020	~	~	~	~	~

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-26
TAPERED CONCRETE CURB DETAIL	



PLAN



ELEVATION



END VIEW

NOTES:


- 1 REMOVE THE EXISTING SURFACE UNDER THE NEW TAPERED CONCRETE CURB AS APPROVED BY THE PROJECT MANAGER. EMBED THE TAPERED CONCRETE CURB A MINIMUM OF 4" [100] BELOW THE GRADE MEASURED AT THE INSIDE FACE OF THE TAPER.
- 2 FURNISH GRADE 60 [420] REINFORCING STEEL MEETING SECTION 555 AND 711.
- 3 ALL CONCRETE IS CLASS GENERAL.
TOTAL CONCRETE PER 6' [1800] TAPERED CURB EST. = 0.2 C.Y. [0.16 m³]
TOTAL REBAR WEIGHT PER 6' [1800] TAPERED CURB EST. = 27 LB. [11.7 kg]
- 4 TAPERED CONCRETE CURB IS USED WITH BRIDGE APPROACH SECTION TYPE 3 (SEE DTL. DWG. NO. 606-24A AND 606-24B).
- 5 ADJUST DIMENSION TO MATCH EXISTING CURB.

BILL OF REINFORCING STEEL (ONE SECTION ONLY)						
<div style="text-align: center;"> <p>TYPE 1</p> </div>						
BENT BARS (ALL DIMENSIONS ARE OUT TO OUT)						
MARK	SIZE	NO.	TYPE	LENGTH	A	B
C1	#4	1	1	1'-4"	6"	4"
C2				1'-8"	7"	6"
C3				1'-11"	8"	7"
C4				2'-3"	9"	9"
C5				2'-6"	10"	10"
C6		1	1	2'-10"	11"	1'-0"
B1		4	STRAIGHT	5'-8"	~	~
B2	#4	2	STRAIGHT	2'-0"	~	~


METRIC BILL OF REINFORCING STEEL (ONE SECTION ONLY)						
<div style="text-align: center;"> <p>TYPE 1</p> </div>						
BENT BARS (ALL DIMENSIONS ARE OUT TO OUT)						
MARK	SIZE	NO.	TYPE	LENGTH (mm)	A (mm)	B (mm)
C1	#13	1	1	390	150	90
C2				480	175	130
C3				570	200	170
C4				665	225	215
C5				755	250	255
C6		1	1	845	270	295
B1		4	STRAIGHT	1720	~	~
B2	#13	2	STRAIGHT	600	~	~

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-27
SECTION 606	
TAPERED CONCRETE CURB DETAIL	




PLAN




SOIL PLATE DETAIL

PLS03*



BEARING PLATE DETAIL

FPB01*



CONTROLLED RELEASING TERMINAL (CRT) POST

CRT POST DETAIL


PDE09*

NOTES:


- DO NOT INSTALL ON SLOPES STEEPER THAN 2:1.
- DO NOT OMIT OR SHORTEN ANCHOR SECTION.
- SEE DTL. DWG. NO. 606-05A FOR GUARDRAIL WIDENING REQUIREMENTS.
- DO NOT BOLT THE RAIL TO THE CRT POST LOCATED AT THE CENTER OF THE BENT RAIL.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.




DETAIL A



MGS FOUNDATION TUBE DETAILS

PTE06*



WOOD BREAKAWAY POST DETAILS



PDF04*

DETAILED DRAWING

REFERENCE DWG. NO.
STANDARD SPEC. 606-46
SECTION 606

INTERSECTING ROADWAY
TERMINAL SECTION (MGS)

MDT MONTANA DEPARTMENT OF TRANSPORTATION



SECTION A-A


ELEVATION

SPLICE DETAIL

NOTES:

- USE BOX BEAM RAIL IN MINIMUM NOMINAL LENGTHS OF 18 FEET UNLESS APPROVED BY THE PROJECT MANAGER.
- INSTALL EXPANSION JOINTS ON ALL BOX BEAM GUARDRAIL INSTALLATIONS GREATER THAN 300 FEET IN LENGTH AT INTERVALS NOT TO EXCEED 500 FEET.
- ATTACH REFLECTIVE TABS TO EVERY FOURTH POST (24 FEET TYP.). ANGLE TABS SLIGHTLY TOWARDS TRAFFIC. DO NOT USE REFLECTIVE TABS ON WY-BET TERMINALS. WY-BET TERMINALS RECEIVE REFLECTIVE CHANNELS.
- DO NOT INSTALL BOX BEAM GUARDRAIL FOR OBSTACLES WITHIN 5.6' OF THE FACE OF THE RAIL.
- WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" FROM THE TRAFFIC LANE.
- PROVIDE SHOP BENT BOX BEAM RAIL FOR ROADWAY CURVATURE WITH RADII OF LESS THAN 715 FEET.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



DETAILED DRAWINGS

REFERENCE STANDARD SPEC. SECTION 606, 704	DWG. NO. 606-50
---	-----------------

BOX BEAM GUARDRAIL


EFFECTIVE: JAN 23, 2020




--REVISED--
JAN 15, 2026


11/29/2025 8:43 AM

STDDRD606050.DWG





PLAN



ELEVATION

NOTES:

- ① INCLUDE COST OF ENTIRE ANCHOR RAIL SECTION, ALONG WITH ALL HARDWARE NECESSARY FOR ATTACHMENT TO CONCRETE BRIDGE RAIL, IN COST OF BRIDGE APPROACH SECTION.
- ② THE LENGTHS OF CONCRETE ANCHOR BOLTS, TYPE OF RUB RAIL ANCHOR BRACKET AND THE NEED FOR THE 1/4" [6.4] SHIM PLATE IS DEPENDENT UPON THE SHAPE AND THE THICKNESS OF THE CONCRETE BRIDGE RAIL.

- ③ WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" [0.6 m] FROM THE TRAFFIC LANE.



- ④ SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.


** SEE BRIDGE PLANS.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-53A
BOX BEAM BRIDGE APPROACH SECTION- TYPE 3	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	




SECTION A-A
(TYP. AT POSTS P1 - P5)




SECTION B-B
(TYP. AT POSTS P6 - P9)




SECTION C-C
(TYP. AT POSTS P10 & P11)



SECTION D-D
(TYP. AT POST P12)



T-1 & R-1 RAIL CONNECTION DETAIL



GUARDRAIL WIDENING DETAIL


- NOTES:
- SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM AND ASSOCIATED DETAILS.
 - WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" FROM THE TRAFFIC LANE.
 - PLACE HARDENED WASHERS (FWC20b*) UNDER BOLT HEAD AND NUT. ADD LARGER DIAMETER WASHER (FWC20a*) AGAINST BRACKET SLOT.
- *SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.
- **SEE BRIDGE PLANS

DETAILED DRAWINGS	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-53B
BOX BEAM BRIDGE APPROACH SECTION - TYPE 4	
EFFECTIVE: JUN 27, 2024	
<div> <div>11/29/2025 8:44 AM</div> <div>STDDRD606053B.DWG</div> </div>	


--REVISED--
JAN 15, 2026

1" [25.4] DIA. HOLES IN BOX BEAM
RAIL FOR 3/4" DIA. x 8" [M20 x 203]
HIGH STRENGTH HEX BOLT (FBX20b*)
AND NUT (FNX20b*) WITH TWO
HARDENED FLAT WASHERS (FWC20b*)

CONNECTION SLEEVE ATTACHED TO
BRIDGE RAIL (TYP.)** (1/4" [6.4] THICK
STEEL FORM FIT TUBE TO RECEIVE
T56 x 6 x 3/16 [TS152 x 152 x 4.8]
BOX BEAM RAIL)



PLAN



ELEVATION

NOTES:

① SEE DTL. DWG. NO. 606-50 FOR STANDARD
BOX BEAM GUARDRAIL AND ASSOCIATED
DETAILS.

② USE ON EXIT END OF ONE-WAY TRAFFIC
BRIDGES ONLY.

* SEE DTL. DWG. NO. 606-80 FOR
SCHEDULE OF GUARDRAIL HARDWARE.


** SEE BRIDGE PLANS FOR MORE DETAILED
INFORMATION ON BRIDGE RAIL AND
CONNECTION DETAILS.

UNITS SHOWN IN BRACKETS [] ARE
METRIC AND ARE IN MILLIMETERS (mm)
UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING

REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-54
--	--------------------

BOX BEAM ONE-WAY BRIDGE
DEPARTURE SECTION



ROAD SYSTEMS MBEAT TERMINAL (FLARED) ①



ROAD SYSTEMS MBEAT TERMINAL (TANGENT) ①

① REFER TO MANUFACTURER'S DETAIL AND ASSEMBLY INSTRUCTIONS.

② THE MBEAT REQUIRES AN 18'-0" [5.49 m] LONG (MINIMUM) SECTION OF STANDARD BOX BEAM RAIL FOR MASH TEST LEVEL 3 APPLICATIONS.

③ LOCATION EQUALS STATION LIMITS INDICATED IN THE PLANS.

④ SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.

⑤ FLARE THE END SECTION AWAY FROM TRAFFIC AT A RATE OF 25:1 FOR 30 FEET [9.14 m] (ILLUSTRATED). FLARES OF 25:1 FOR 48 FEET [14.63 m] MAY ALSO BE USED.

⑥ THE FLARE MAY BE OMITTED ON ROADS WITH SHOULDERS GREATER THAN 2 FEET [0.6 m] IN WIDTH. DO NOT FLARE THE END SECTION ON INTERSTATE APPLICATIONS.

⑦ 7'-0" [2134] WIDENING DIMENSION ALLOWS FOR BOX BEAM TERMINAL SECTION FLARE AND SYSTEM WIDTH. A MINIMUM WIDENING DISTANCE OF 5'-0" [1524] IS REQUIRED BEHIND POST LOCATION #1.

⑧ PLACE A SELF-ADHESIVE OBJECT MARKER ON THE FACE OF THE NOSE ASSEMBLY, HAVING ALTERNATING RETRO-REFLECTIVE BLACK AND YELLOW STRIPES SLOPED DOWNWARD AT AN ANGLE OF 45° TOWARDS THE SIDE ON WHICH TRAFFIC IS TO PASS.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWINGS

REFERENCE DWG. NO.
STANDARD SPEC. 606-55
SECTION 606

BOX BEAM TERMINAL SECTION - MBEAT

EFFECTIVE: APR 28, 2022







MONTANA
Department of Transportation

--REVISED--
JUN 27, 2024

5/13/2024 1:37 PM


STDDRD606055.DWG



NOTES:

- ① SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.
- ② SEE DTL. DWG. NO. 606-05A AND 606-05B FOR STANDARD MGS GUARDRAIL AND ASSOCIATED DETAILS. SEE DTL. DWG. NO. 606-20 FOR HEIGHT AND SPlice TRANSITION DETAILS.
- ③ MANUFACTURE ANCHOR ANGLES USING AASHTO M 270 [270M] GRADE 36 [250] STEEL MEETING SECTION 711. WELD PER SECTION 711.
- ④ GALVANIZE ANCHOR ANGLES PER SECTION 711. NO PUNCHING, DRILLING, WELDING OR CUTTING IS PERMITTED ON COMPONENTS AFTER GALVANIZING.
- ⑤ USE CLASS GENERAL CONCRETE TO CONSTRUCT ANCHOR.
- ⑥ PAINT ANY AREAS WHERE GALVANIZING IS BROKEN OR METAL IS BARE ON W-BEAM OR BOX BEAM RAIL WITH ONE COAT OF ZINC RICH PAINT AND TWO COATS OF ALUMINUM PAINT PER SECTION 710.
- ⑦ LAP ALL W-BEAM SPLICES IN THE DIRECTION OF ADJACENT TRAFFIC.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

<i>DETAILED DRAWING</i>	
<i>REFERENCE</i>	<i>DWG. NO.</i>
<i>STANDARD SPEC.</i>	<i>606-58</i>
<i>SECTION 606.710.711</i>	
<i>BOX BEAM TO MGS TRANSITION SECTION</i>	
 MONTANA DEPARTMENT OF TRANSPORTATION	

SCHEDULE OF GUARDRAIL HARDWARE				DTL. DWGS. WHERE PARTS USED																				
DESIGNATION ①	DESCRIPTION	DTL.DWG.NO (606-####)	GUARDRAIL TYPE ②	606-05A	606-05B	606-07	606-09	606-11A	606-11B	606-18	606-23A	606-23B	606-24A	606-24B	606-25A	606-25B	606-46	606-50	606-52	606-53	606-53A	606-53B	606-54	606-58
FBB01-05	5/8" DIA. GUARDRAIL BOLT & RECESS NUT	82	W	X																				X
FBB01-05	5/8" DIA. GUARDRAIL BOLT	82	W		X																			
FBB06-07	5/8" DIA. GUARDRAIL BOLT & RECESS NUT	82	W																					
FBX10a	3/8" DIA. HEX BOLT	82	B																					
FBX12a	1/2" DIA. HEX BOLT	82	B																					
FBX14a	9/16" DIA. HEX BOLT	82	B																					
FBX16a	5/8" DIA. HEX BOLT	82	W																					
FBX20a	3/4" DIA. HEX BOLT	82	W																					
FBX20b	3/4" DIA. HIGH STRENGTH HEX BOLT*	82	B																					
FBX22a	7/8" DIA. HEX BOLT	82	W																					
FBX22b	7/8" DIA. HIGH STRENGTH HEX BOLT*	82	W																					
FBX24b	1" DIA. HIGH STRENGTH HEX BOLT*	82	B																					
FCA01	CABLE ASSEMBLY	84	W																					
FMM01	CABLE WEDGE	94	C																					
FMM02	POST SLEEVE	84	W																					
FNS20	3/4" DIA. SQUARE NUT	82	C																					
FNX10a	3/8" DIA. HEX NUT	82	B																					
FNX12a	1/2" DIA. HEX NUT	82	B																					
FNX14a	9/16" DIA. HEX NUT	82	B																					
FNX16a	5/8" DIA. HEX NUT	82	W		X																			
FNX20a	3/4" DIA. HEX NUT	82	C,W																					
FNX20b	3/4" DIA. HIGH STRENGTH HEX NUT	82	B																					
FNX22b	7/8" DIA. HIGH STRENGTH HEX NUT	82	B																					
FNX24a	1" DIA. HEX NUT	82	W																					
FNX24b	1" DIA. HIGH STRENGTH HEX NUT	82	B																					
FPA01	GUARDRAIL ANCHOR BRACKET & END PLATE	84	W																					
FPB01	BEARING PLATE	18 & 46	W																					
FPP01	BOX BEAM SUPPORT BRACKET	97	B																					
FRH20a	3/4" DIA. HOOKED ANCHOR ROD	82	C																					
FWC10a	3/8" DIA. FLAT WASHER	82	B																					
FWC12a	1/2" DIA. FLAT WASHER	82	B																					
FWC14a	9/16" DIA. FLAT WASHER	82	B																					
FWC16a	5/8" DIA. FLAT WASHER	82	W	X	X		X	X	X	X	X	X												
FWC20a	3/4" DIA. FLAT WASHER	82	C,W																					
FWC20b	3/4" DIA. HARDENED FLAT WASHER	82	B																					
FWC24a	1" DIA. FLAT WASHER	82	W																					
FWR03	RECTANGULAR PLATE WASHER	84	W																					
PDB01	8" WOOD BLOCKOUT	05A & 05B, 11A & 11B	W	X	X				X	X														
PDB11	12" WOOD BLOCKOUT	09, 23A & 23B	W				X					X	X											
PDE02	WOOD GUARDRAIL POST	05A & 11A	W	X					X															
PDE09	CRT POST	46	W				X																	
PDF01	WOOD BREAKAWAY POST	46	W																					
PFP01	STRUT AND YOKE ASSEMBLY	18	W																					
PLS01	SOIL PLATE	92 & 97	B																					
PLS03	SOIL PLATE	46	W																					
PSE05	TYPE D BOX BEAM POST	97	B																					
PSE08	TYPE A BOX BEAM POST	97	B																					
PTE05	STEEL TUBE	46	W																					
PTE06	STEEL TUBE	18	W																					
PWE01	STEEL GUARDRAIL POST	05B	W		X				X															
RBM01	BOX BEAM RAIL	98	B																					
RBM05	BOX BEAM TERMINAL RAIL	98	B																					
RBS01	BOX BEAM SPLICE PLATE	98	B																					
RCE03	CABLE END ASSEMBLY	94	C																					
RCM01	3/4" DIA. CABLE	94	C																					
RTE01b	THRIE-BEAM TERMINAL CONNECTOR	23A & 23B	W																					
RTM01a-b	4-SPACE THRIE-BEAM (6'-3" LENGTH)	23A & 23B	W																					
RTM02a-b	8-SPACE THRIE-BEAM (12'-6" LENGTH)	23A & 23B	W																					
RWE01a-b	W-BEAM END SECTION (FLARED)	88	W																					
RWE02a-b	W-BEAM TERMINAL CONNECTOR	88	W																					
RWE06a-b	W-BEAM END SECTION (BUFFER)	88	W																					
RWM02a-b	2-SPACE W-BEAM (12'-6" LENGTH)	88	W																					
RWM04a-b	4-SPACE W-BEAM (12'-6" LENGTH)	88	W	X	X		X	X	X	X	X	X												
RWM08a-b	8-SPACE W-BEAM (12'-6" LENGTH)	88	W				X																	
RWM14a	BCT TERMINAL RAIL SECTION	18	W																					
RWM22a-b	W-BEAM (25'-0" LENGTH)	88	W	X	X		X	X	X	X														
RWT02a-b	W-BEAM TO THRIE-BEAM TRANSITION SECTION (7'-3 1/2" LENGTH)	23A & 23B	W																					

* FURNISH HIGH STRENGTH BOLTS IN ACCORDANCE WITH ASTM F3125 GRADE A325

NOTES:

- ① SEE AASHTO-AGC-ARTBA JOINT COMMITTEE TASK FORCE 13 REPORT "A GUIDE TO STANDARDIZED HIGHWAY BARRIER HARDWARE" PUBLICATION FOR ADDITIONAL AND DETAILED HARDWARE SPECIFICATIONS.

- ② GUARDRAIL TYPE CODES:

W = W-BEAM METAL GUARDRAIL
C = CABLE GUARDRAIL
B = BOX BEAM GUARDRAIL

DETAILED DRAWINGS

REFERENCE DWG. NO.
STANDARD SPEC. 606-80
SECTION 606

SCHEDULE OF GUARDRAIL HARDWARE

EFFECTIVE: JAN 23, 2020



--REVISED--
JUN 27, 2024
JAN 15, 2026

11/29/2025 8:45 AM D:\DRD606080 - STD-8.5X11-606080A.DWG

SCHEDULE OF GUARDRAIL HARDWARE				DTL DWGS. WHERE PARTS USED																				
DESIGNATIO N①	DESCRIPTION	DTL.DWG.NO (606-###)	GUARDRAI L TYPE ②	606-05A	606-05B	606-07	606-09	606-11A	606-11B	606-18	606-23A	606-23B	606-24A	606-24B	606-25A	606-25B	606-46	606-50	606-52	606-53	606-53A	606-53B	606-54	606-58
N/A	TYPE B BOX BEAM POST	97	B																	X		X		
N/A	TYPE 4 BOX BEAM SUPPORT BRACKET	97	B																			X		
N/A	SUPPORT BRACKET WITH TS6 x 6 x 3/16 BLOCKOUT	97	B																		X			
N/A	TRANSITION POST	97	B																		X			
N/A	TYPE D TRANSITION POST	97	B																			X		
N/A	TS6 x 6 x 3/16 BR. APP. SECT. UPPER RAIL NO. 1	98	B																	X				
N/A	TS6 x 2 x 1/4 BR. APP. SECT. LOWER RAIL NO. 1	98	B																	X				
N/A	TS6 x 2 x 1/4 BR. APP. SECT. LOWER RAIL NO. 2	98	B																	X				
N/A	TS6 x 2 TO TS6 x 6 CONNECTION SLEEVE	98	B																	X				
N/A	TS6 x 2 CONNECTION SLEEVE	98	B																	X				
N/A	TS6 x 6 x 3/16 TRANSITION RAIL	98	B																		X			
N/A	T-1 TRANSITION RAIL	98A	B																				X	
N/A	R-1 TRANSITION RUB RAIL	98A	B																				X	
N/A	R-2 TRANSITION RUB RAIL	98A	B																				X	
N/A	R-3 TRANSITION RUB RAIL	98A	B																				X	
N/A	UPPER BRIDGE RAIL CONNECTION SLEEVE	98A	B																				X	
N/A	LOWER BRIDGE RAIL CONNECTION SLEEVE	98A	B																				X	
N/A	RUB RAIL SPLICE SLEEVE	98A	B																				X	
N/A	RUB RAIL FLAIR SLEEVE	98A	B																				X	
N/A	1/4" SHIM PLATE	99	B																		X			
N/A	ANCHOR RAIL SECTION	99	B																		X			
N/A	RUB RAIL ANCHOR BRACKET (JERSEY RAIL)	99	B																		X			
N/A	RUB RAIL ANCHOR BRACKET (VERTICAL BRIDGE RAIL)	99	B																		X			
N/A	TS6 x 2 x 3/16 RUB RAIL	99	B																		X			
N/A	RUB RAIL FLARE SLEEVE	98A	B																				X	
N/A	TYPE 4 TRANSITION ATTACHMENT (BENT PLATE)	99A	B																				X	
N/A	TYPE 4 TRANSITION ATTACHMENT (TOP STIFFENER)	99A	B																				X	
N/A	TYPE 4 TRANSITION ATTACHMENT (SIDE STIFFENER)	99A	B																				X	
N/A	TYPE 4 TRANSITION ATTACHMENT (BOTTOM STIFFENER)	99A	B																				X	
N/A	TYPE 4 TRANSITION ATTACHMENT (UPPER RAIL ATTACHMENT)	99A	B																				X	
N/A	TYPE 4 TRANSITION ATTACHMENT (RUB RAIL ATTACHMENT)	99A	B																				X	
N/A	TYPE 4 TRANSITION ATTACHMENT (MOUNTING TAB)	99A	B																				X	
N/A	TYPE 4 TRANSITION ATTACHMENT (GUSSET)	99A	B																				X	

* FURNISH HIGH STRENGTH BOLTS IN ACCORDANCE WITH ASTM F3125 GRADE A325

NOTES:

- ① SEE AASHTO-AGC-ARTBA JOINT COMMITTEE
TASK FORCE 13 REPORT "A GUIDE TO
STANDARDIZED HIGHWAY BARRIER HARDWARE"
PUBLICATION FOR ADDITIONAL AND DETAILED
HARDWARE SPECIFICATIONS.

- ② GUARDRAIL TYPE CODES:

W = W-BEAM METAL GUARDRAIL
C = CABLE GUARDRAIL
B = BOX BEAM GUARDRAIL

DETAILED DRAWINGS

REFERENCE DWG. NO.
STANDARD SPEC. 606-80A
SECTION 606

SCHEDULE OF GUARDRAIL HARDWARE


EFFECTIVE: JAN 23, 2020



MONTANA
Department of Transportation


--REVISED--
JUN 27, 2024
JAN 15, 2026

GUARDRAIL HARDWARE




HEX BOLTS

BOLT SIZE	DESIGNATION *	L	T (MIN.)
REGULAR HEX BOLTS			
3/8" DIA.	FBX10a	3 1/2"	1 1/2"
3/8" DIA.	FBX10a	7 1/2"	1 1/2"
1/2" DIA.	FBX12a	1 1/2"	FULL
1/2" DIA.	FBX12a	2 1/2"	1 3/4"
9/16" DIA.	FBX14a	8"	2"
5/8" DIA.	FBX16a	1 1/2"	FULL
3/4" DIA.	FBX20a	8"	2"
3/4" DIA.	FBX20a	9 1/2"	2"
HIGH STRENGTH HEX BOLTS			
3/4" DIA.	FBX20b	2"	1 1/2"
3/4" DIA.	FBX20b	4"	2"
3/4" DIA.	FBX20b	8"	2"
7/8" DIA.	FBX22b	1'-0"	AS REQUIRED
1" DIA.	FBX24b	AS REQUIRED	AS REQUIRED




HEX NUT

NUT SIZE	DESIGNATION *
REGULAR HEX NUTS	
3/8" DIA.	FNX10a
1/2" DIA.	FNX12a
9/16" DIA.	FNX14a
5/8" DIA.	FNX16a
3/4" DIA.	FNX20a
1" DIA.	FNX24a
HIGH STRENGTH HEX NUTS	
3/4" DIA.	FNX20b
7/8" DIA.	FNX22b
1" DIA.	FNX24b



FLAT WASHERS


WASHER SIZE	DESIGNATION *
REGULAR FLAT WASHERS	
3/8" DIA.	FWC10a
1/2" DIA.	FWC12a
9/16" DIA.	FWC14a
5/8" DIA.	FWC16a
3/4" DIA.	FWC20a
1" DIA.	FWC24a
HARDENED FLAT WASHERS	
3/4" DIA.	FWC20b



5/8" DIA. GUARDRAIL BOLT & RECESSED NUT


FBB01-07*

DESIGNATION *	L	T (MIN.)
FBB01	1 1/4"	1 1/8"
FBB02	2"	1 3/4"
FBB03	10"	4"
FBB04	1'-6"	4"
FBB05	2'-1"	4"
FBB06	1'-2"	4 1/16"
FBB07	1'-9"	4 1/16"



3/4" DIA. SQUARE NUT

FNS20*



3/4" DIA. HOOKED ANCHOR ROD


FRH20a*

NOTES:

- FURNISH BOLTS AND ANCHOR RODS MEETING THE REQUIREMENTS OF SUBSECTION 705.01.1.
- FURNISH HIGH STRENGTH BOLTS MEETING THE REQUIREMENTS OF SUBSECTION 711.06.
- GALVANIZE BOLTS, NUTS AND WASHERS IN ACCORDANCE WITH SUBSECTION 705.01.1.
- 35° THREAD ANGLE FOR BOLTS FBB06-07.


* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

METRIC GUARDRAIL HARDWARE




HEX BOLTS

BOLT SIZE	DESIGNATION *	L	T (MIN.)
REGULAR HEX BOLTS			
M10	FBX10a	89	38
M10	FBX10a	191	38
M12	FBX12a	38	FULL
M12	FBX12a	63	44
M14	FBX14a	203	51
M16	FBX16a	38	FULL
M20	FBX20a	203	51
M20	FBX20a	241	51
HIGH STRENGTH HEX BOLTS			
M20	FBX20b	51	38
M20	FBX20b	102	51
M20	FBX20b	203	51
M22	FBX22b	305	AS REQUIRED
M24	FBX24b	AS REQUIRED	AS REQUIRED




HEX NUT

NUT SIZE	DESIGNATION *
REGULAR HEX NUTS	
M10	FNX10a
M12	FNX12a
M14	FNX14a
M16	FNX16a
M20	FNX20a
M24	FNX24a
HIGH STRENGTH HEX NUTS	
M20	FNX20b
M22	FNX22b
M24	FNX24b



FLAT WASHERS


WASHER SIZE	DESIGNATION *
REGULAR FLAT WASHERS	
M10	FWC10a
M12	FWC12a
M14	FWC14a
M16	FWC16a
M20	FWC20a
M24	FWC24a
HARDENED FLAT WASHERS	
M20	FWC20b



M16 GUARDRAIL BOLT & RECESSED NUT


FBB01-07*

DESIGNATION *	L	T (MIN.)
FBB01	32	29
FBB02	51	44
FBB03	254	102
FBB04	457	102
FBB05	635	102
FBB06	356	103
FBB07	533	103



M20 SQUARE NUT

FNS20*



M20 HOOKED ANCHOR ROD

FRH20a*


NOTES:

- FURNISH BOLTS AND ANCHOR RODS MEETING THE REQUIREMENTS OF SUBSECTION 705.01.1.
- FURNISH HIGH STRENGTH BOLTS MEETING THE REQUIREMENTS OF SUBSECTION 711.06.
- GALVANIZE BOLTS, NUTS AND WASHERS IN ACCORDANCE WITH SUBSECTION 705.01.1.
- 35° THREAD ANGLE FOR BOLTS FBB06-07.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

ALL DIMENSIONS ARE MILLIMETERS (mm) UNLESS OTHERWISE NOTED.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 705, 711	DWG. NO. 606-82
GUARDRAIL HARDWARE	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	








NOTES:

- ① FOR RELATED FASTENER HARDWARE SEE FWC24a*, FNX24a* AND FPA01*.
- ② MACHINE THE SWAGED FITTING FROM HOT-ROLLED CARBON STEEL CONFORMING TO THE REQUIREMENTS OF ASTM A576 [A576 M], GRADE 1035, AND ANNEAL SUITABLE FOR COLD SWAGING. GALVANIZE THE SWAGED FITTING IN ACCORDANCE WITH SUBSECTION 711.08 BEFORE SWAGING. DRILL A LOCK PIN HOLE TO ACCOMMODATE A 1/4" [6.4 mm], PLATED SPRING STEEL PIN THROUGH THE HEAD OF THE SWAGED FITTING TO RETAIN THE STUD IN THE PROPER POSITION.
- ③ THE SWAGED FITTING, STUD AND NUT (FNX24a*) MUST DEVELOP THE BREAKING STRENGTH OF THE WIRE ROPE.
- ④ WIRE ROPE IS TO CONFORM TO THE REQUIREMENTS OF AASHTO M30 [M30M] AND BE 3/4" [19.1 mm] PREFORMED, 6 x 19, WIRE STRAND CORE OR INDEPENDENT WIRE ROPE CORE (IWRC), GALVANIZED, RIGHT REGULAR LAY, MANUFACTURED OF IMPROVED PLOW STEEL WITH A MINIMUM BREAKING STRENGTH OF 42,800 POUNDS [190.4 kN].
- ⑤ THE STUD IS TO CONFORM TO THE REQUIREMENTS OF ASTM F568 [F568M] CLASS 8.8 AND BE GALVANIZED IN ACCORDANCE WITH AASHTO M232 [M232M] (ASTM A153 [153M]). PRIOR TO GALVANIZING, MILL A 3/8" [9.5 mm] SLOT INTO THE STUD END FOR THE LOCKING PIN.

CABLE ASSEMBLY

FCA01*




ANCHOR BRACKET & END PLATE

FPA01*

POST SLEEVE

FMM02*



RECTANGULAR PLATE WASHER

FWR03*

NOTES:

- ⑥ ANCHOR BRACKETS, END PLATES AND RECTANGULAR PLATE WASHERS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M270 [M270M] (ASTM A709 [A709M]) GRADE 36 [250] STEEL PLATE. POST SLEEVES ARE TO CONFORM TO THE REQUIREMENTS OF ASTM A53 [A53M] GRADE B.
- ⑦ GALVANIZE FABRICATED PARTS IN ACCORDANCE WITH SUBSECTION 711.08. DO NOT PUNCH, DRILL, OR CUT AFTER GALVANIZING.



* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING

REFERENCE DWG. NO.
STANDARD SPEC. 606-84
SECTION 606, 711

W-BEAM METAL
GUARDRAIL HARDWARE





W-BEAM

RWM02a-b*
RWM04a-b*
RWM08a-b*
(12'-6" [3.81 m] LENGTH)



OR

RWM22a-b*
(25'-0" [7.62 m] LENGTH)





W-BEAM END SECTION (FLARED)

RWE01a-b*



W-BEAM END SECTION (BUFFER)

RWE06a-b*



W-BEAM TERMINAL CONNECTOR

RWE02a-b*

NOTES:

* DESTINATION SUFFIX	METAL THICKNESS
a	12 GAUGE [2.7 mm]
b	10 GAUGE [3.5 mm]

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.


UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING


REFERENCE DWG. NO.
STANDARD SPEC. 606-88
SECTION 606

W-BEAM METAL
GUARDRAIL HARDWARE


R.H. = RIGHT HAND
L.H. = LEFT HAND



CABLE END ASSEMBLY
RCE03*



CABLE WEDGE
FMM01*



3/4" [19.1] DIA. - 3 x 7 WIRE ROPE

3/4" [19.1] DIA. CABLE
RCM01*


NOTES:

- ① WIRE ROPE AND CONNECTING HARDWARE ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M30 [M30M] TYPE 1 CLASS A, 3/4" [19.1] ROPE. CONNECTING HARDWARE MUST DEVELOP THE FULL STRENGTH OF A SINGLE CABLE (25,000 LB [111.2 kN]). CAST STEEL COMPONENTS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M103 [M103M] (ASTM A27 [A27M]). MALLEABLE IRON CASTINGS ARE TO CONFORM TO THE REQUIREMENTS OF ASTM A47 [A47M].
- ② AT ALL LOCATIONS WHERE THE CABLE IS CONNECTED TO A CABLE SOCKET WITH A WEDGE TYPE CONNECTION, CRIMP ONE WIRE OF THE CABLE OVER THE BASE OF THE WEDGE TO HOLD IT FIRMLY IN PLACE.
- ③ DESIGN SOCKET BASKETS FOR USE WITH THE WEDGE DETAILED IN THIS DRAWING.
- ④ ALTERNATE HARDWARE DESIGNS WILL BE CONSIDERED FOR APPROVAL PROVIDED THEIR CONNECTION DETAILS, FOR THE PURPOSE OF MAINTENANCE SUBSTITUTIONS, ARE COMPATIBLE WITH THE DETAILS OF THIS DRAWING AND THEIR OPERATING CHARACTERISTICS ARE SIMILAR TO THOSE OF THE HARDWARE IN THIS DRAWING.


* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-94
LOW-TENSION CABLE GUARDRAIL HARDWARE	
MDT ★ MONTANA DEPARTMENT OF TRANSPORTATION	




TYPE A BOX BEAM POST AND SOIL PLATE
PSE08* AND PLS01*



TYPE B BOX BEAM
POST AND SOIL PLATE
PLS01*




TYPE D BOX BEAM POST AND SOIL PLATE
PSE05* AND PLS01*




TRANSITION POST


W6 x 9 OR W6 x 8.5
ASTM A992




TYPE D TRANSITION POST




BOX BEAM SUPPORT BRACKET
FPP01*



TYPE 4 BOX BEAM SUPPORT BRACKET



SUPPORT BRACKET W/BLOCKOUT




GUSSET
(1/4" STEEL PLATE)

NOTES:

- MANUFACTURE POSTS USING STEEL CONFORMING TO AASHTO M 183 (ASTM A 36). MANUFACTURE SOIL PLATES, SUPPORT BRACKETS AND MISC. COMPONENTS USING AASHTO M 270 (ASTM A 709) GRADE 36 STEEL. ALL WELDING IS TO CONFORM TO THE APPLICABLE AWS CODE.
- MANUFACTURE BLOCKOUTS FROM EITHER ASTM A 500 GRADE B COLD-ROLLED TUBING, ASTM A 501 HOT-ROLLED TUBING OR AUTOMOTIVE ROLLOVER PROTECTIVE STEEL (ROPS). WHEN ASTM A 500 GRADE B STEEL IS USED, TEST THE MATERIAL PER ASTM E 436.
- GALVANIZE FABRICATED POSTS, BLOCKOUTS, BRACKETS AND MISC. COMPONENTS IN ACCORDANCE WITH SUBSECTION 711.08. DO NOT PUNCH, DRILL, OR CUT AFTER GALVANIZING.
- SEE DTL. DWG. NO. 606-53 OR 606-53B (BOX BEAM BR. APP. SECT.) FOR REQUIRED LOCATION OF LOWER HOLES IN TYPE A AND B POSTS.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



DETAILED DRAWINGS

REFERENCE DWG. NO.
STANDARD SPEC. 606-97
SECTION 606


BOX BEAM GUARDRAIL HARDWARE

EFFECTIVE: JAN 23, 2020




--REVISED--
JUN 27, 2024
JAN 15, 2026

11/29/2025 8:43 AM STDDR606097.DWG




BOX BEAM RAIL (TS6 x 6 x 3/16 [TS152 x 152 x 4.8])

RBM01*




BOX BEAM EXPANSION SPLICE END

ONE END OF BOX BEAM RAIL ONLY. REQUIRED FOR BOTH RAILS AT THE EXPANSION SPLICE.




BOX BEAM TERMINAL RAIL (TS6 x 6 x 3/16 [TS152 x 152 x 4.8])


RBM05*



END COVER PLATE DETAIL
(BAR 5" x 3/16" x 0'-5 3/4" [127 x 4.8 x 146])




TS6 x 6 x 3/16 [TS152 x 152 x 4.8] BR. APP. SECT. UPPER RAIL NO.1




BOX BEAM SPLICE PLATE


RBS01*





TS6 x 2 x 1/4 [TS152 x 51 x 6.4] BR. APP. SECT. LOWER RAIL NO.1




TS6 x 2 x 1/4 [TS152 x 51 x 6.4] BR. APP. SECT. LOWER RAIL NO. 2



TRANSITION RAIL (TS6 x 6 x 3/16 [TS152 x 152 x 4.8])



TS6 x 6 x 3/16 [TS152 x 152 x 4.8] SECTION VIEW



TS6 x 2 x 1/4 [TS152 x 51 x 6.4] SECTION VIEW


NOTES:

- MANUFACTURE BOX BEAM RAIL ELEMENTS FROM EITHER ASTM A 500 GRADE B COLD ROLLED TUBING, ASTM A 501 HOT-ROLLED TUBING OR AUTOMOTIVE ROLLOVER PROTECTIVE STEEL (ROPS). WHEN ASTM A 500 GRADE B STEEL IS USED, TEST THE MATERIAL PER ASTM E 436.
- FABRICATE SPLICE PLATES AND CONNECTION SLEEVES FROM AASHTO M 270 (270M) (ASTM A 709 (709M)) GRADE 36 [250] STEEL PLATE. THE NUTS ARE TO BE PLAIN UN-COATED 3/4" DIA. [M20] HIGH STRENGTH HEX NUTS. WELD THE NUTS TO THE PLATES IN ACCORDANCE WITH THE APPLICABLE AWS CODE.
- GALVANIZE FABRICATED RAIL, CONNECTION SLEEVES, AND SPLICE PLATES IN ACCORDANCE WITH SUBSECTION 711.08. DO NOT PUNCH, DRILL, OR CUT AFTER GALVANIZING.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.


UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 711	DWG. NO. 606-98
BOX BEAM GUARDRAIL HARDWARE	




T-1 TRANSITION RAIL

HSS 6x6x3/8
ASTM A500 GRADE B




R-1 TRANSITION RUB RAIL

HSS 6x2x1/4
ASTM A500 GRADE B





R-2 TRANSITION RUB RAIL

HSS 6x2x1/4
ASTM A500 GRADE B



R-3 TRANSITION RUB RAIL



HSS 6x2x1/4
ASTM A500 GRADE B



NOTE:
WELD & GRIND SMOOTH TO FIT
INSIDE 6" x 6" x 3/8"

UPPER BRIDGE RAIL CONNECTION SLEEVE



ASTM A36 PLATE, 18" x 3/8"
3/4" DIA. x 7 1/2" HIGH STRENGTH HEX BOLT (FBX20b*)
AND NUT (FNX20b*) WITH 2 HARDENED FLAT
WASHERS (FWC20b*)



NOTE:
WELD & GRIND SMOOTH TO FIT
INSIDE 6" x 2" x 1/4"

LOWER BRIDGE RAIL CONNECTION SLEEVE


ASTM A36 PLATE, 18" x 3/8"
3/4" DIA. x 3 1/2" HIGH STRENGTH HEX BOLT (FBX20b*)
AND NUT (FNX20b*) WITH 2 HARDENED FLAT
WASHERS (FWC20b*)





NOTE:
WELD & GRIND SMOOTH TO FIT
INSIDE 6" x 2" x 1/4"

RUB RAIL SPLICE SLEEVE

ASTM A36 PLATE, 27" x 3/8"
3/4" DIA. x 3 1/2" HIGH STRENGTH HEX BOLT (FBX20b*)
AND NUT (FNX20b*) WITH 2 HARDENED FLAT
WASHERS (FWC20b*)



NOTE:
WELD & GRIND SMOOTH
TO FIT INSIDE 6" x 2" x 1/4"



RUB RAIL FLARE SLEEVE

3/16" ASTM A36 PLATE
3/4" DIA. x 3 1/2" HIGH STRENGTH HEX BOLT (FBX20b*)
AND NUT (FNX20b*) WITH 2 HARDENED FLAT
WASHERS (FWX20b*)

NOTES:
*SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF
GUARDRAIL HARDWARE.

DETAILED DRAWINGS	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-98A
SECTION 606	






BOX BEAM
GUARDRAIL HARDWARE


EFFECTIVE: JUN 27, 2024




--REVISED--
JAN 15, 2026

11/29/2025 8:42 AM STDDRD606098A.DWG







TOP VIEW
BENT



PLATE, 33 $\frac{1}{4}$ " x $\frac{1}{4}$ " x 39 $\frac{1}{4}$ "
[845 x 6.4 x 997]
ASTM A572 GRADE 50


NOTE:
MAIN PLATE DETAILS SHOWN ARE FOR LEFT SIDE TRANSITION ATTACHMENT PART.
MAIN PLATE FOR RIGHT SIDE IS A MIRROR IMAGE OF THIS ONE (PRE-BEND DETAILS
ARE IDENTICAL, BUT BENT IN OPPOSITE DIRECTIONS).

BENT PLATE





BENT

PLATE, 3" x $\frac{1}{4}$ " x 60 $\frac{13}{16}$ "
[76 x 6.4 x 1545]
ASTM A572 GRADE 50




SIDE STIFFENER




UPPER RAIL ATTACHMENT

RUB RAIL ATTACHMENT

BOTTOM STIFFENER




FIELD SIDE VIEW



TOP STIFFENER

UNITS SHOWN IN BRACKETS [] ARE
METRIC AND ARE IN MILLIMETERS (mm)
UNLESS OTHER UNITS ARE SHOWN.



PLATE, 3" x $\frac{1}{4}$ " x 4 $\frac{3}{8}$ "
[76 x 6.4 x 111]
ASTM A572 GRADE 50
(2 REQUIRED)

GUSSET

DETAILED DRAWINGS

REFERENCE
STANDARD SPEC.
SECTION 606

DWG. NO.
606-99A

BOX BEAM GUARDRAIL HARDWARE

EFFECTIVE: JUN 27, 2024



MONTANA
Department of Transportation

5/14/2024 8:56 AM

STDDRD606099A.DWG