

1. RAMP CROSSOVER

A. Description. Construct Temporary Ramp Crossover at locations shown in the plans according to field conditions approved by the Project Manager and meeting the requirements in the Detailed Drawings.

1) Provide a smooth transition surface for ramp traffic. Sign, stripe and place traffic control devised in accordance with the Detailed Drawings, MUTCD, and Standard Specifications.

2) Maintain the surfacing, striping, signing, drainage, erosion control, and all traffic control associated with the ramp crossovers. Maintain Ramp Crossovers in a manner that will provide traveling public with a safe and smooth riding surface to the satisfaction of the Project Manager.

3) Remove Ramp Crossover upon completion of construction activities. Remove all temporary signing, striping, and traffic control devices. Obliterate any conflicting pavement devices.

B. Measurement and Payment. Payment for Ramp Crossover will be for each Ramp Crossover. This includes materials, labor, equipment and all costs necessary to construct, sign, maintain, and remove the ramp crossovers.