

SUMMARY

GRADING				
STATION	cu. yards			REMARKS
	UNCL. EXC.	EXCESS EXC.	EMB.+	
110+99.57				
	96,277	94,595	1,682	I-90 UNDIVIDED
289+00.00				
	97	-315	412	ADDITIONAL GRADING
TOTAL	96,374	# 94,280	# 2,094	

FOR INFORMATION ONLY

RUMBLE STRIPS				
STATION		miles		REMARKS
		RUMBLE STRIPS		
		CONTINUOUS	INTERMITTENT	
FROM	TO			
111+01.04	2013+50.00	2.6	2.6	I-90 EASTBOUND
111+01.04	3013+50.00	2.6	2.6	I-90 WESTBOUND
SUBTOTAL		5.2	5.2	
TOTAL		10.4		

PAVEMENT REMOVAL				
STATION		sq. yards	sq. yards	REMARKS
		REMOVE CONCRETE PAVEMENT	REMOVE BITUMINOUS PAVEMENT	
FROM	TO			
110+99.57	289+00.00	95,426	176,410	I-90 UNDIVIDED RECONSTRUCTION (EB & WB)
TOTAL		95,426	176,410	

NOTE: PAVEMENT REMOVAL QUANTITIES ARE NOT INCLUDED IN GRADING QUANTITIES.

TRAFFIC CONTROL					
STATION		each		miles	REMARKS
		RAMP CROSSOVER	CLOSED MEDIAN CROSSOVER	TWO-WAY TRAFFIC	
FROM	TO				
		1			WB RAMP CROSSOVER - LOOKOUT PASS
		1			EB RAMP CROSSOVER - LOOKOUT PASS
106+20.00	110+00.00		2		CLOSED MEDIAN CROSSOVER 1
427+20.00	431+00.00		2		CLOSED MEDIAN CROSSOVER 2
110+00.00	427+20.00			6.0	PHASE 1 - CONSTRUCT EB I-90 & BRIDGE REPAIR
110+00.00	427+20.00			6.0	PHASE 2 - CONSTRUCT WB I-90 & BRIDGE REPAIR
TOTAL		2	4	12.0	

ADDITIONAL GRADING					
STATION		cu. yards			REMARKS
		INCL. IN GRAD. FRAME		ADD. UNCL. EXC.	
		UNCL. EXC.	EMB.+		
FROM	TO				
129+94.00			5		DITCH BLOCK LT.
135+42.00			9		DITCH BLOCK LT.
146+80.00			11		DITCH BLOCK LT.
150+08.00	150+83.00	97			DITCH GRADING LT.
160+80.00			13		DITCH BLOCK LT.
164+85.00			14		DITCH BLOCK LT.
178+11.00			65		DITCH BLOCK LT.
181+62.00	181+79.00		65		SEDIMENT BASIN LT.
183+85.00			3		DITCH BLOCK LT.
188+92.00			28		DITCH BLOCK LT.
193+92.00			22		DITCH BLOCK LT.
269+32.00	269+51.00		120		SEDIMENT BASIN LT.
277+18.00			56		DITCH BLOCK LT.
286+51.00			1		DITCH BLOCK LT.
TOTAL		97	412	~	

REMOVE BRIDGE APPROACH SLAB		
STRUCTURE NO.	each	REMARKS
	REMOVE BRIDGE APPROACH SLAB	
BRIDGE NO.		
01298	1	EB APPROACH SLAB - REPLACE WITH PCCP
TOTAL	1	

PAVEMENT MARKINGS				
ITEM	UNIT	INTERIM APPLICATION #	FINAL APPLICATION	TOTAL
STRIPING - WHITE PAINT	gallon	196		196
STRIPING - YELLOW PAINT	gallon	155		155
WORDS & SYMBOLS - WHITE PAINT	gallon	7		7
STRIPING - WHITE EPOXY	gallon		131	131
STRIPING - YELLOW EPOXY	gallon		103	103
WORDS & SYMBOLS - WHITE EPOXY	gallon		5	5
STRIPING - 6 IN WHITE - HIGH PERF TAPE	linear feet			8,900
STRIPING - 6 IN BLACK - HIGH PERF TAPE	linear feet			8,900
STRIPE GROOVING	linear feet			116,384
TEMPORARY STRIPING	linear feet			8,900
FINAL SWEEP AND BROOM	course mile			6.7

BASED ON 2 APPLICATIONS.

SHEET NO.

RD-13

SUMMARY

PROJECT NAME
LOOKOUT PASS - EAST

COUNTY
MINERAL COUNTY

PROJECT ID
SSS-NHFP-JM-NHPB 90-1(251)0

UPN
9487001

CHECKED BY
LFISCHER

REVIEWED BY
SMARSHALL

DESIGNED BY
BUCHINSON

9487000RD\SUNZ01.DWG