

1. SEQUENCE OF OPERATIONS

A. Description. This project requires phasing of work and a resulting sequence of operations. Some geologic or other site conditions will not become clear until after some work is complete. Sequence operations to meet the requirements as described below.

1) Detour two-way two-lane traffic as shown in plans and described in DETOUR – MAINTAIN Special Provision.

2) Clean the ditch and remove loose material before any scaling to provide catchment of materials removed from the rock cut. Removal of material from the ditch and the roadway will be necessary throughout the project. See DITCH CLEAN-OUT and DISPOSAL OF SCALED MATERIAL special provisions.

3) Set up Mobile Rockfall Barrier(s) (MRB(s)) and other rockfall retaining elements such as temporary concrete barrier and establish the detour prior to beginning scaling operations.

4) When debris fills the ditch to the point that catchment is inadequate, pause scaling and clean the ditch. When scaling is complete, clean the ditch as described in the contract and plans.

5) An alternate Sequence of operations may be submitted to the Project Manager.

B. Method of Measurement and Basis of Payment. No separate measurement will be made for requirements of Sequence of Operations