

Quantities shown are preliminary and meant for planning purposes only.

Montana Department of Transportation  
Preliminary Quantities

Proj Number: S-482 Repair - S of Libby  
10760000

Prepared By:  
Date: 3/31/2026 1:11:24 PM

UPN Number: 10760000

County: Lincoln

Design Stage: Plan In Hand Review

District: Missoula

CostEstimate: 10760000BREST002

Type of Work:

Item Number	Quantity	Description	Unit
104030030	1,200.00	MISCELLANEOUS ITEMS-INSTALL	LNFT
551020035	112.20	CONCRETE-CLASS STRUCTURE	CUYD
551020036	300.90	CONCRETE-CLASS STRUCTURE LOW SLUMP	CUYD
552010140	876.80	TRANSVERSE DECK GROOVING	SQYD
555010100	18,500.00	REINFORCING STEEL	LB
555010200	63,500.00	REINFORCING STEEL-EPOXY COATED	LB
559010202	3.00	RE-DRIVE TEST PILE	EACH
559040035	3.00	DYNAMIC LOAD TEST	EACH
559050115	220,000.00	FURN STEEL PILE-PIPE	LB
559060115	1,650.00	DRIVE STEEL PILE	LNFT
559060200	20.00	PILE CUTTING SHOE	EACH
605000092	611.33	36 IN SS CONCRETE BARRIER RAIL-BR	LNFT

Quantities shown do not represent final quantities or all bid items on the project.

Quantities shown are preliminary and meant for planning purposes only.

**Montana Department of Transportation  
Preliminary Quantities**

<b>Proj Number:</b>	S-482 Repair - S of Libby 10760000	<b>Prepared By:</b>	state\U3484
		<b>Date:</b>	2/23/2026 10:50:24 AM
<b>UPN Number:</b>	10760000	<b>County:</b>	Lincoln
<b>Design Stage:</b>	Scope of Work	<b>District:</b>	Missoula
<b>CostEstimate:</b>	10760000RDEST001	<b>Type of Work:</b>	

Item Number	Quantity	Description	Unit
104030010	55,000.00	MISCELLANEOUS WORK	UNIT
108000010	1.00	STRUCTURE ANALYSIS	LS
109200005	1.00	MOBILIZATION	LS
201130005	1.00	CLEARING AND GRUBBING	ACRE
202020041	1.00	REMOVE STRUCTURE	LS
203020100	2,848.00	EXCAVATION-UNCLASSIFIED	CUYD
208010000	1.00	BMP ADMINISTRATION-LS	LS
208010015	1.00	AQUATIC RESOURCE MONITOR	LS
208010200	500.00	TEMPORARY EROSION CONTROL-FIXED	UNIT
208010500	1.00	BIOENGINEERED BANK	LS
209010150	1.00	SHORING AND CRIBS	LS
301020252	970.00	BRIDGE END BACKFILL-TYPE 1	CUYD
301020340	1,403.00	CRUSHED AGGREGATE COURSE	CUYD
301020625	1,440.00	AGGREGATE TREATMENT	SQYD
401020064	136.00	COMMERCIAL PLANT MIX-MISC	TON
401020157	431.00	COMMERCIAL MIX-3/8 IN-PG 58H-34	TON
402020315	295.00	EMULSIFIED ASPHALT PAVEMENT	TON
411011145	0.10	SINUSOIDAL RUMBLE STRIPS	MILE
603013413	148.00	PIPE-CORR POLYETHYLENE DR 8 IN	LNFT
603015270	126.00	EMBANKMENT PROTECTOR 18 IN	LNFT
606010330	100.00	MGS GUARDRAIL	LNFT
606010335	3.00	MASH W-BEAM TERMINAL SECTION	EACH
606010342	3.00	MASH THRIE BEAM BR APPRCH SECTION	EACH
606010385	241.30	REMOVE GUARDRAIL	LNFT
606011510	1.00	REMOVE IMPACT ATTENUATOR	EACH
606011520	1.00	IMPACT ATTENUATOR	EACH
609010010	275.00	CURB-CONCRETE	LNFT
609010112	132.00	CURB 4 IN-CONCRETE	LNFT
610100559	1.00	REVEGETATION	LS
610100560	870.00	RIPRAP REVEGETATION	SQYD
613100040	714.00	RIPRAP-CLASS 2 RANDOM	CUYD
613300050	9.00	BANK PROTECTION-TYPE 3	CUYD
618030015	500.00	TRAFFIC CONTROL-FIXED	UNIT
618030080	1.00	TRAFFIC CONTROL-LS	LS

Quantities shown do not represent final quantities or all bid items on the project.

Quantities shown are preliminary and meant for planning purposes only.

**Montana Department of Transportation  
Preliminary Quantities**

620013960	6.00	STRIPING-WHITE EPOXY	GAL
620014960	6.00	STRIPING-YELLOW EPOXY	GAL
622011043	870.00	PERM EROSION CONTROL-HIGH SURV	SQYD
622011086	1,948.00	SEPARATION GEOTEXTILE - HIGH	SQYD

Quantities shown do not represent final quantities or all bid items on the project.

PRELIMINARY