

# SUMMARY

STATION		linear feet				FOR	AGGREGATE					BITUMINOUS MATERIAL				GEOTEXTILE	REMARKS
		GROSS	NET	+	-		HYDRATED LIME	square yards			cubic yards		tons		gallons	square yards	
								COVER TYPE 2	PLANT MIX BIT. SURF. GR. 5 - 3/4"	PLANT MIX BIT. SURF. GR. 5 - 3/4" MISC	COMM. MIX BIT. SURF. GR. 5 - 3/8" PG 58-28	CRUSHED AGG. COURSE	TRAFFIC GRAVEL	ASPHALT CEMENT PG 64-28	EMULSIFIED ASPHALT CHFRS-2P	EMULSIFIED ASPHALT TACK*	
FROM	TO																
5+10.00	10+00.00	490.00	490.00			CONNECTION TO PTW	2,342	640			622	34.5	4.2	265	2,636	2,793	TRANS. FROM TYP. NO. 1 TO TYP. NO. 2
10+00.00	20+00.00	1,000.00	1,000.00				6,000	1,620		1,528	87.5	10.7	660	6,600	6,910		TYPICAL NO. 2
20+00.00	44+80.00	2,480.00	2,480.00				14,880	4,018		3,789	217.0	26.5	1,637	16,368			TYPICAL NO. 3
44+80.00	45+00.00	20.00	20.00				120	32		31	1.8	1.0	13	132			TRANS. TYP. NO. 3 TO TYP. NO. 4
45+00.00	53+28.75	828.75	828.75				4,973	1,343		1,266	72.5	8.9	547	5,470			TYPICAL NO. 4
53+28.75	54+28.75	100.00	100.00				599	160		149	8.6	1.0	65	645			TRANS. TYP. NO. 4 TO TYP. NO. 5
54+28.75	62+97.00	868.25	868.25				5,192	1,367		1,264	73.8	9.3	547	5,461			TYPICAL NO. 5
62+97.00	63+57.00	60.00	60.00				359	96		90	5.2	0.6	39	387			TRANS. TYP. NO. 5 TO TYP. NO. 3
63+57.00	68+39.31	482.31	482.31				2,894	781		737	42.2	5.2	318	3,183			TYPICAL NO. 3
68+39.31	70+19.31	180.00	180.00				1,080	291		273	13.9	1.9	118	1,180			TRANS. TYP. NO. 3 TO TYP. NO. 6
70+19.31	93+68.36	2,349.05	2,349.05				14,094	3,777		3,538	157.2	25.1	1,527	15,292			TYPICAL NO. 6
93+68.36	95+48.36	180.00	180.00				1,080	291		273	13.9	1.9	118	1,180			TRANS. TYP. NO. 6 TO TYP. NO. 3
95+48.36	142+04.09	4,655.73	4,655.73				27,934	7,542		7,114	407.4	49.8	3,073	30,728			TYPICAL NO. 3
142+04.09	145+54.09	350.00	350.00				2,256	600		549	32.4	4.0	242	2,413			TRANS. TYP. NO. 3 TO TYP. NO. 7
145+54.09	151+02.75	548.66	548.66				3,780	993		882	53.6	6.7	395	3,945			TYPICAL NO. 7
151+02.75	151+72.75	70.00	70.00				498	130		115	7.0	0.9	51	508			TRANS. TYP. NO. 7 TO TYP. NO. 8
151+72.75	153+31.35	158.60	158.60				1,163	300		266	16.2	2.1	117	1,163			TYPICAL NO. 8
TOTAL		14,821.35	14,821.35	0.00	0.00	ADDITIONAL SURFACING	3,861	737	876	1,538	4,532	59.6	7.0	1,457	20,925	673	

\* BASED ON 2 APPLICATIONS

STATION		miles		gals		REMARKS
		SINUSOIDAL RUMBLE STRIPS	INTER-MITTENT	EMULSIFIED ASPHALT FOG SEAL #		
FROM	TO					
5+10.00	9+25.66	0.1		5		R.T. FROM B.O.P. TO E. RIVER RD.
5+10.00	90+25.11	1.6		95		L.T. FROM B.O.P. TO CEDAR BLUFFS RD.
15+18.53	99+86.64	1.6		94		R.T. SCALE SITE TO BLUE RD.
92+31.77	115+65.85	0.4		26		L.T. FROM CEDAR BLUFFS RD. TO WINEGLASS RD.
101+25.58	145+09.03	0.8		49		R.T. FROM BLUE RD. TO STRONG LN.
117+41.25	126+86.57	0.2		11		L.T. FROM WINEGLASS RD. TO SHAMROCK LN.
128+85.42	139+30.78	0.2		12		L.T. FROM SHAMROCK LN. TO GUTHRIE LN.
141+39.78	151+52.88	0.2		11		L.T. FROM GUTHRIE LN. TO MERRILL LN.
147+06.82	151+52.88	0.1		5		R.T. FROM STRONG LN. TO MERRILL LN.
SUBTOTAL		5.2		308		
TOTAL		5.2		~		

# FOR INFORMATION ONLY, INCLUDE IN THE COST OF RUMBLE STRIPS

PAVEMENT MARKINGS				
ITEM	UNIT	INTERIM APPLICATION #	FINAL APPLICATION	TOTAL
STRIPING - WHITE PAINT	gallon	202		202
STRIPING - YELLOW PAINT	gallon	270		270
WORDS & SYMBOLS - YELLOW PAINT	gallon	6		6
WORDS & SYMBOLS - WHITE PAINT	gallon	34		34
STRIPING - WHITE EPOXY	gallon		134	134
STRIPING - YELLOW EPOXY	gallon		180	180
WORDS & SYMBOLS - WHITE EPOXY	gallon		21	21
WORDS & SYMBOLS - YELLOW EPOXY	gallon		3	3
TEMPORARY STRIPING - WHITE PAINT	ln. ft.			800
TEMPORARY STRIPING - YELLOW PAINT	ln. ft.			37,485
FINAL SWEEP AND BROOM	cr. mile			2.8

# BASED ON 2 APPLICATIONS.

STATION		cubic yards		REMARKS
		EXC.	EMB. IN PLACE	
FROM	TO			
5+10	153+31.40	38,931	32,234	
		9,150	13,145	ADD. GRADING
44+80.00	63+57.00	~	5,976	TYP. NO'S 4 & 5 SUB EXC. MEASURED ON CADD
TOTAL		# 48,081	51,355	

# FOR INFORMATION ONLY  
\* - SUB EXC. INCL. IN MAINLINE  
NOTE: SEE SECTION 203 FOR PAYMENT OF EXCAVATION

STATION		cubic yards		REMARKS
		EXC.	EMB. IN PLACE	
FROM	TO			
44+80.00	63+57.00	9,050		TYP. NO'S. 4 & 5, MEASURED ON CADD
52+92.45	53+62.00	23		SUBSURFACE DRAIN OUTSIDE DIG OUT
63+57.00	68+08.20	274		SUBSURFACE DRAIN OUTSIDE DIG OUT
TOTAL		9,347		