

---

# MONTANA DEPARTMENT OF TRANSPORTATION STREAM MITIGATION MONITORING REPORT

---

*Spring Creek  
Flathead County, Montana*

*Project Completed: 2010  
Monitoring Report #2: December, 2014*



Prepared for:

**MONTANA**  
**MDT**★  
**DEPARTMENT OF TRANSPORTATION**  
2701 Prospect Ave  
Helena, MT 59620-1001

Prepared by:



**CONFLUENCE**  
PO Box 1133  
Bozeman, MT 59771-1133

# **MONTANA DEPARTMENT OF TRANSPORTATION**

## **STREAM MITIGATION MONITORING REPORT #2**

**YEAR 2014**

*Spring Creek  
Flathead County, Montana*

MDT Project Number: NH-MT 5-3(59) 109  
Control Number: 2038

USACE Permit: NWO-2009-01808-MTM

Prepared for:

**MONTANA DEPARTMENT OF TRANSPORTATION**  
2701 Prospect Ave  
Helena, MT 59620-1001

Prepared by:

**Confluence Consulting, Inc.**  
P.O. Box 1133  
Bozeman, MT 59771

December 2014

CCI Project No: MDT\_.007

## TABLE OF CONTENTS

1.0	Introduction .....	1
2.0	Site Location .....	2
3.0	Monitoring Methods.....	4
3.1.	Vegetation Inventories and Community Mapping .....	4
3.2.	Bank Erosion Inventory.....	4
3.3.	Channel Surveys .....	4
3.4.	Photo-Documentation .....	5
3.5.	Wildlife Documentation .....	5
4.0	Results .....	5
4.1.	Riparian and Stream bank Vegetation Inventory .....	5
4.2.	Stream Bank Vegetation Composition .....	6
4.3.	Noxious Weed Inventory.....	9
4.4.	Woody Plant Survival.....	9
4.5.	Bank Erosion Inventory.....	9
4.6.	Channel Form .....	9
4.7.	Wildlife Documentation .....	10
5.0	Comparison of Results to Performance Standards .....	11
5.1.	Riparian Buffer Success .....	11
5.2.	Vegetation Success .....	11
5.3.	Vegetation along Stream Banks .....	13
5.4.	Stream bank Stability Success .....	13
5.5.	Channel Form Success.....	13
6.0	Management and Design Recommendations .....	15
6.1.	Riparian and Floodplain Zones .....	15
6.2.	Willow Cutting and Riparian Plug Establishment .....	15
6.3.	Channel Planform .....	16
7.0	Literature Cited .....	16

## TABLES AND FIGURES

Figure 1. Project location of Spring Creek stream mitigation site.....	3
Figure 2. Alternative grading plan to increase floodplain and riparian areas.....	15
Figure 3. Spring Creek Site Map .....	Appendix A
Figure 4. Spring Creek Vegetation Communities .....	Appendix A
Table 1. Percent cover of vegetation transects at Spring Creek in 2013 and 2014. .....	6
Table 2. Comprehensive vegetative species list for the Spring Creek stream mitigation site in 2013 and 2014. ....	7
Table 3. Comprehensive list of plant species and accompanying stability index values found along Spring Creek in 2014 (stability score from Burton <i>et al.</i> , 2011).....	8
Table 4. Montana State listed noxious weed and regulated species observed in 2014 at the Spring Creek Stream Mitigation Site. ....	9
Table 5. Woody plant survival at the Spring Creek stream mitigation site in 2013 and 2014.....	9
Table 6. Spring Creek maximum depths and bankfull widths in 2013 and 2014.	10
Table 7. Wildlife species observed at the Spring Creek stream mitigation site in 2013 and 2014.....	11
Table 8. Monitoring results as compared to performance criteria for the Spring Creek mitigation site in 2014.....	12

## APPENDICES

Appendix A: Project Site Maps
Appendix B: Perpendicular Transect Plots and Longitudinal Profiles
Appendix C: Project Site Photos
Appendix D: Channel Construction Details

Cover Photo: Relocated segment of Spring Creek, 2014.

## 1.0 INTRODUCTION

As part of the construction of the Kalispell Bypass U.S. Highway 2 South, the Montana Department of Transportation (MDT) reconstructed a segment of Spring Creek upstream of the Ashley Creek Highway 93 North Bridge crossing on the west side of Kalispell, Montana. The following report presents results of the second year of post stream reconstruction monitoring and compares these results to performance standards outlined in the monitoring plan for the project. The Spring Creek channel relocation project was constructed in 2010; therefore, these results provide documentation of the site's condition four years following the project's completion.

The goal of the Spring Creek stream mitigation project is to provide compensatory mitigation for stream impacts associated with transportation projects including the Kalispell Bypass in the Missoula District. In order to accomplish this goal, the project's objective includes constructing 990 feet of new Spring Creek channel with the following design elements:

- Channel banks will generally be constructed with 0.5:1 side slopes
- Pool bottom widths generally 4 feet wide and top widths generally 7.5 feet wide
- Riffle bottom widths generally 5 feet wide and top widths generally 7.5 feet wide
- Floodplain width adjacent to the new stream channel to vary in width from 15.5 feet to 21 feet.
- Upland slopes varying from 2.2:1 to 6.5:1

These design elements were developed to create, enhance, restore, and maintain permanent, naturally self-sustaining, native, or native-like stream and riparian habitats along the newly constructed segment of Spring Creek. If successful, the project will protect the functional values of riparian lands, floodplains, wetlands, and uplands for the benefit of fish and wildlife habitat, water quality, floodwater retention, groundwater recharge, open space, aesthetic values, and environmental education.

Provisions outlined within the USACE permit include monitoring of the on and off-site stream mitigation areas for five years following channel construction to determine whether the site meets, or is trending toward a series of performance standards outlined in the mitigation plan for the site.

### Quantitative success criteria for the Spring Creek project:

1. **Riparian Buffer Success** will be achieved when:
  - a. Woody and riparian vegetation becomes established, and noxious weeds do not exceed 10% cover within the riparian buffer areas.
  - b. Any area within the creditable buffer area disturbed by the project construction must have at least 50% areal cover of non-noxious weed species by the end of the monitoring period.

2. **Vegetation Success** will be achieved when:
  - a. combined areal cover of riparian and stream bank vegetation communities is  $\geq 70\%$
  - b. Planted trees and shrubs will be considered successful where they exhibit 50% survival after 5 years.
3. **Vegetation along Stream banks** will be considered successful when banks are vegetated with a majority of deep-rooting riparian plant species having root stability indexes  $\geq 6$  (subject to 1.a and 1.b above).
4. **Stream bank Stability Success** will be achieved where; following restoration, less than 25% of bank length is unstable and classified as an eroding bank. For this purpose "eroding bank" will be defined as any bank greater than two feet in length that is more than 50% bare mineral soil and has no roots, surface vegetation, or other stabilizing structure (e.g. rock, woody debris) to inhibit erosion.

Qualitative success criteria for the Spring Creek project:

5. **Channel Form Success** will be achieved when the stream stabilizes, includes pools and riffles, allows for flood events to occupy the floodplain, and the habitat features such as riparian plant communities have successfully established along stream banks.

Additional monitoring requirements include:

6. **Photo Documenting** the success of restored stream channel and stream bank vegetation community development showing distinct positive changes from pre-construction to final monitoring year in comparison with the establishment reference reach.

Results of the second year monitoring of the Spring Creek project are summarized in Section 4 and compared to performance standards in Section 5. Section 6 provides management recommendations to maximize the potential for meeting all performance standards at this and other similar mitigation sites. Additional reporting requirements including a longitudinal stream profile, repeated survey results at four perpendicular transects, a planting schematic from the approved design, photo documentation of the project site, and maps indicating the endpoints of riparian belt transects, perpendicular transect surveys and locations of noxious weed infestations are included as Appendices to this report.

## **2.0 SITE LOCATION**

The project reach includes approximately 990 feet of reconstructed Spring Creek channel east of the U.S. Highway 93 ALT corridor. The project site is located in Section 13, Township 7 North, Range 22 West, in Flathead County, Montana (Figure 1).




Figure 1. Project location of Spring Creek stream mitigation site.

### **3.0 MONITORING METHODS**

Monitoring field crews visited the project site on August 19, 2014 while survey crews visited the site on July 30, 2014. The following data were collected at the Spring Creek stream mitigation site:

#### **3.1. Vegetation Inventories and Community Mapping**

Two riparian belt transects established during the first monitoring event in 2013 were re-surveyed to document areal percent cover of total vegetation, woody vegetation and noxious weeds. The riparian transect on the right (west) bank runs parallel to the channel for 223 feet, while the riparian transect on the left (east) bank is 296 feet long (Figure 3, Appendix A).

A vegetation inventory was conducted along both stream banks, and included documenting dominant species, percent cover of each species, and compiling a list of all species encountered within three feet of the active channel. The stream bank vegetation inventory included the entire 995-foot length of both banks (3 feet wide) within the project site. In 2013, plant species identified along the stream banks were assigned plant stability ratings based on Winward, 2000. In 2014, plant species identified along the stream banks were assigned plant stability ratings based on Burton *et al.*, 2011. This change was made per MDT request to use updated values for plant stability ratings.

The project site was visually inspected to document the presence of noxious weeds. All noxious weed infestations were mapped on aerial photographs, with species noted. Observations of isolated noxious weeds were noted in the species lists, but not mapped.

The project area was visually inspected to document woody vegetation plantings. The inspection included recording the total number of live and dead woody plantings observed. Dominant vegetation communities within the project area were mapped on aerial photographs to document vegetative establishment within both upland and riparian zones.

#### **3.2. Bank Erosion Inventory**

Both stream banks within the project reach were visually inspected to document eroding banks. Each eroding bank within the project reach was photo-documented. Data collected at each eroding bank included bank length and potential causes of bank erosion.

#### **3.3. Channel Surveys**

Four perpendicular transects (cross sections) were surveyed by licensed survey crews; two at riffles and two at pools. Locations of pool and riffle cross sections were selected based on the Spring Creek planform design sheet, which indicated where riffle and pool habitats were to be constructed. Endpoints of each transect were marked with a pin, flagging, or stake for locating during subsequent monitoring events. Photo-

documentation of each transect included photos taken facing upstream, downstream, left, and right from the channel centerline. In addition to the perpendicular transects, a longitudinal profile of the channel thalweg was surveyed to document bedform complexity and aquatic habitat conditions.

### **3.4. Photo-Documentation**

The project site was photographed from several locations to document vegetation establishment and stream bank conditions within the project site. Four locations for establishing permanent photo points were selected to document changes in the site over time. In addition, photos were taken at the endpoints and facing upstream, downstream, left and right from the center of the channel at each perpendicular transect. All permanent photo documentation sites were recorded on field maps with compass bearings noted to allow for repetition during subsequent monitoring years.

### **3.5. Wildlife Documentation**

Wildlife use of the project reach was documented by creating a list of all bird, mammal, and herpetile species observed during the site visit. Wildlife species were identified through visual observation, scat, tracks, and observation of nests, burrows, dens, feathers, etc.

## **4.0 RESULTS**

### **4.1. Riparian and Stream bank Vegetation Inventory**

Table 1 summarizes percent cover of total vegetation, woody vegetation, and noxious weeds for each riparian and stream bank transect. Subtotals for the combined riparian and combined stream bank inventories are provided, as well as an area-weighted total for riparian and stream bank zones. No bare ground was observed within any of the vegetation transects. In 2014, the total riparian and stream bank cover was 100%, and included 41% herbaceous cover and 59% woody coverage. Noxious weed coverage increased by 2% in 2014 to 5% cover.

No bare ground was observed within the entire project reach, and both the riparian and stream bank transects exhibited a diversity of herbaceous and woody vegetation species. Noxious weeds were sporadically found along both banks of the inventoried transects. Additional information about weed species observed is included in Section 4.3.

**Table 1. Percent cover of vegetation transects at Spring Creek in 2013 and 2014.**

Belt Transect	Length (ft)	Total % Vegetation Cover		% Woody Cover		% Noxious Weed Cover	
		2013	2014	2013	2014	2013	2014
Right (West) Riparian	223	100%	100%	35%	35%	2%	5%
Left (East) Riparian	296	100%	100%	57%	60%	2%	4%
<b>Riparian Subtotal</b>		100%	100%	47%	49%	2%	4%
Right (West) Streambank	995	100%	100%	38%	60%	6%	6%
Left (East) Streambank	995	100%	100%	100%	100%	4%	4%
<b>Streambank Subtotal</b>		100%	100%	69%	80%	5%	5%
<b>Area Weighted Total</b>		100%	100%	54%	59%	3%	5%

Dominant species recorded along the riparian and stream bank transects were combined with visual observations in other areas to develop a vegetation community map (Figure 4, Appendix A). The upper side slopes are dominated by wild rye (*Elymus spp.*), while the lower slopes and riparian zones are dominated by willows (*Salix spp.*), reed canary grass (*Phalaris arundinacea*), and sunflower (*Helianthus maximiliani*). A small patch of chokecherry (*Prunus virginiana*) and alder (*Alnus spp*) exists just north of the culvert outlet at the upstream extent of the project reach. As the planted shrubs mature and become larger over time, the corridor is expected to become more dominated by woody species.

Table 2 is a comprehensive list of vegetative species identified within the two belt transects, two stream bank transects, and other incidental plants observed on site. In 2014, 76 plant species were observed on site, an increase of 22 species from 2013. In 2014, 47% of the species observed on site were considered hydrophytic based on the National Wetland Plant List (NWPL) (Lichvar et al., 2014).

#### **4.2. Stream Bank Vegetation Composition**

In 2014, 39 plant species were observed along the stream banks, representing an increase by 11 species from 2013 (Table 3). Stability ratings were assigned to each species observed along the banks to help determine overall bank stability. Stability ratings (1-10 scale) indicate a plant's ability to resist erosive forces based on root characteristics (Winward 2000). Of the 39 species observed, 25 have stability indices provided by Burton et al., 2011, while the remaining 14 species do not. Scores for plants without stability indices are listed in Table 3 as N/A. Nine of the 25 species (36%) had stability indices of 6 or higher. The most prevalent species observed along the stream banks was reed canary grass (*Phalaris arundinacea*), which comprised >50% of the stream bank area and has an assigned stability index of 9. Three additional dominant species included pacific willow (*Salix lasiandra*), sandbar willow (*Salix exigua*), and Maximilian's sunflower (*Helianthus maximiliani*) covered a minimum of 40% of the stream banks and have stability indices of 7, 5, and N/A, respectively.

**Table 2. Comprehensive vegetative species list for the Spring Creek stream mitigation site in 2013 and 2014.**

Scientific Name	Common Name	WMVC Indicator Status*
<i>Agropyron cristatum</i>	Crested Wheatgrass	NL
<i>Agrostis gigantea</i>	Black Bent	FAC
<i>Algae, green</i>	Algae, green	NL
<i>Alnus incana</i>	Speckled Alder	FACW
<i>Alopecurus arundinaceus</i>	Creeping Meadow-Foxtail	FAC
<i>Alopecurus pratensis</i>	Field Meadow-Foxtail	FAC
<i>Artemisia biennis</i>	Biennial Wormwood	FACW
<b>Aster sp.</b>	<b>Aster</b>	<b>NL</b>
<i>Beckmannia syzigachne</i>	American Slough Grass	OBL
<i>Betula papyrifera</i>	Paper Birch	FAC
<b>Betula pumila</b>	<b>Bog Birch</b>	<b>OBL</b>
<i>Bromus inermis</i>	Smooth Brome	FAC
<b>Bromus tectorum</b>	<b>Cheatgrass</b>	<b>NL</b>
<i>Carduus nutans</i>	Nodding Plumeless-Thistle	UPL
<b>Carex stipata</b>	<b>Stalk-Grain Sedge</b>	<b>OBL</b>
<i>Centaurea stoebe</i>	Spotted Knapweed	NL
<i>Chenopodium album</i>	Lamb's-Quarters	FACU
<i>Cirsium arvense</i>	Canadian Thistle	FAC
<i>Cirsium vulgare</i>	Bull Thistle	FACU
<b>Clematis occidentalis</b>	<b>Purple Clematis</b>	<b>NL</b>
<i>Convolvulus arvensis</i>	Field Bindweed	NL
<i>Cornus alba</i>	Red Osier	FACW
<b>Cynoglossum officinale</b>	<b>Gypsy-Flower</b>	<b>FACU</b>
<b>Deschampsia cespitosa</b>	<b>Tufted Hairgrass</b>	<b>NL</b>
<b>Descurainia sophia</b>	<b>Herb Sophia</b>	<b>NL</b>
<i>Elymus canadensis</i>	Nodding Wild Rye	FAC
<b>Elymus cinereus</b>	<b>Great Basin Wildrye</b>	<b>NL</b>
<b>Elymus hispidus</b>	<b>Intermediate Wheatgrass</b>	<b>NL</b>
<i>Elymus repens</i>	Creeping Wild Rye	FAC
<i>Epilobium ciliatum</i>	Fringed Willowherb	FACW
<b>Festuca idahoensis</b>	<b>Bluebunch Fescue</b>	<b>FACU</b>
<i>Glyceria grandis</i>	American Manna Grass	OBL
<i>Glyceria striata</i>	Fowl Manna Grass	OBL
<i>Helianthus maximiliani</i>	Maximilian Sunflower	UPL
<i>Helianthus nuttallii</i>	Nuttall's Sunflower	FACW
<b>Hordeum jubatum</b>	<b>Fox-Tail Barley</b>	<b>FAC</b>
<b>Lactuca serriola</b>	<b>Prickly Lettuce</b>	<b>FACU</b>

Scientific Name	Common Name	WMVC Indicator Status*
<i>Lemna minor</i>	Common Duckweed	OBL
<i>Linaria vulgaris</i>	Butter-and-eggs	NL
<i>Lupinus arbustus</i>	Long-spur Lupine	NL
<b>Lupinus sp.</b>	<b>Lupine</b>	<b>NL</b>
<i>Medicago lupulina</i>	Black Medick	FACU
<i>Medicago sativa</i>	Alfalfa	UPL
<b>Melilotus albus</b>	<b>White Sweetclover</b>	<b>NL</b>
<i>Melilotus officinalis</i>	Yellow Sweet-Clover	FACU
<b>Mentha arvensis</b>	<b>American Wild Mint</b>	<b>FACW</b>
<b>Nasturtium officinale</b>	<b>Watercress</b>	<b>OBL</b>
<i>Onopordum acanthium</i>	Scotch Thistle	NL
<i>Pascopyrum smithii</i>	Western-Wheat Grass	FACU
<b>Persicaria amphibia</b>	<b>Water Smartweed</b>	<b>OBL</b>
<b>Persicaria sp.</b>	<b>Smartweed</b>	<b>NL</b>
<i>Phalaris arundinacea</i>	Reed Canary Grass	FACW
<i>Pinus ponderosa</i>	Ponderosa Pine	FACU
<b>Plantago major</b>	<b>Great Plantain</b>	<b>FAC</b>
<i>Poa palustris</i>	Fowl Blue Grass	FAC
<i>Poa pratensis</i>	Kentucky Blue Grass	FAC
<i>Populus angustifolia</i>	Narrow-Leaf Cottonwood	FACW
<i>Prunus virginiana</i>	Choke Cherry	FACU
<i>Pseudotsuga menziesii</i>	Douglas-Fir	FACU
<i>Rosa woodsii</i>	Woods' Rose	FACU
<i>Rumex crispus</i>	Curly Dock	FAC
<i>Salix bebbiana</i>	Gray Willow	FACW
<b>Salix drummondiana</b>	<b>Drummond's Willow</b>	<b>FACW</b>
<i>Salix exigua</i>	Narrow-Leaf Willow	FACW
<i>Salix lasiandra</i>	Pacific Willow	FACW
<i>Shepherdia argentea</i>	Silver Buffalo-Berry	FACU
<i>Silene vulgaris</i>	Maiden's-tears	NL
<i>Sonchus arvensis</i>	Field Sow-Thistle	FACU
<i>Symphoricarpos albus</i>	Common Snowberry	FACU
<i>Tanacetum vulgare</i>	Common Tansy	FACU
<b>Thlaspi arvense</b>	<b>Field Pennycress</b>	<b>UPL</b>
<b>Tragopogon dubius</b>	<b>Meadow Goat's-beard</b>	<b>NL</b>
<i>Trifolium repens</i>	White Clover	FAC
<i>Urtica dioica</i>	Stinging Nettle	FAC
<i>Verbascum thapsus</i>	Great Mullein	FACU
<i>Vicia americana</i>	American Purple Vetch	FAC

\*Based on 2014 NWPL (Lichvar *et al.*, 2014)  
New species identified in 2014 are **bolded**.

**Table 3. Comprehensive list of plant species and accompanying stability index values found along Spring Creek in 2014 (stability score from Burton *et al.*, 2011).**

Streambank Species	Left bank	Right bank	WMVC Indicator Status**	Stability Index
<i>Phalaris arundinacea</i> *	X	X	FACW	9
<i>Betula papyrifera</i>		X	OBL	8.5
<i>Carex stipata</i>	X		OBL	8.5
<i>Salix drummondiana</i>	X	X	FACW	8.5
<i>Cornus alba</i>	X	X	FACW	8
<i>Alnus incana</i>	X	X	FACW	7
<i>Salix lasiandra</i> *	X	X	FACW	7
<i>Alopecurus arundinaceus</i>	X		FAC	6
<i>Alopecurus pratensis</i>		X	FAC	6
<i>Deschampsia caespitosa</i>	X	X	FACW	5
<i>Glyceria striata</i>	X	X	OBL	5
<i>Pascopyrum smithii</i>	X	X	FACU	5
<i>Plantago major</i>		X	FAC	5
<i>Rosa woodsii</i>	X	X	FACU	5
<i>Salix exigua</i> *		X	FACW	5
<i>Vicia americana</i>	X	X	FAC	5
<i>Bromus inermis</i>		X	FAC	2
<i>Cirsium arvense</i>	X	X	FAC	2
<i>Epilobium ciliatum</i>	X	X	FACW	2
<i>Hordeum jubatum</i>	X		FAC	2
<i>Mentha arvensis</i>	X		FACW	2
<i>Nasturtium officinale</i>	X		OBL	2
<i>Onopordum acanthium</i>	X	X	NL	2
<i>Poa palustris</i>	X	X	FAC	2
<i>Rumex crispus</i>	X	X	FAC	2
<i>Beckmannia syzigachne</i>	X		OBL	N/A
<i>Carduus nutans</i>		X	UPL	N/A
<i>Convolvulus arvensis</i>		X	NL	N/A
<i>Descurainia sophia</i>		X	NL	N/A
<i>Helianthus maximiliani</i> *	X	X	UPL	N/A
<i>Lactuca serriola</i>		X	FACU	N/A
<i>Linaria vulgaris</i>		X	NL	N/A
<i>Medicago sativa</i>	X		UPL	N/A
<i>Persicaria amphibia</i>	X		OBL	N/A
<i>Persicaria sp.</i>	X		NL	N/A
<i>Prunus virginiana</i>	X		FACU	N/A
<i>Tanacetum vulgare</i>	X		FACU	N/A
<i>Tragopogon dubius</i>	X		NL	N/A

\*Dominant vegetation along Spring Creek banks

\*\*Based on 2014 NWPL (Lichvar *et al.*, 2014)

### 4.3. Noxious Weed Inventory

The Spring Creek field assessment identified the presence of six Montana state-listed noxious weeds and one state-regulated species (Table 4). Locations of all noxious weed species observed are shown on Figure 4 in Appendix A. As noted in Section 4.1, the percent cover of the site exhibiting weeds was 5%, and represents all weed species combined.

**Table 4. Montana State listed noxious weed and regulated species observed in 2014 at the Spring Creek Stream Mitigation Site.**

Category*	Scientific Name	Common Name
Priority 2B	<i>Centaurea stoebe</i>	Spotted Knapweed
	<i>Cirsium arvense</i>	Canadian Thistle
	<i>Convolvulus arvensis</i>	Field Bindweed
	<i>Cynoglossum officinale</i>	Gypsy-Flower
	<i>Linaria vulgaris</i>	Butter-and-eggs
	<i>Tanacetum vulgare</i>	Common Tansy
Priority 3 State Regulated	<i>Bromus tectorum</i>	Cheatgrass

\*Based on the MSU Extension Services' Noxious Weed List, 2013

### 4.4. Woody Plant Survival

Pacific willow, gray willow, coyote willow, black cottonwood, alder, snowberry, red osier dogwood, buffalo-berry, birch, and Wood's rose were observed throughout the site as planted woody vegetation species. Table 5 indicates the total number of plants inspected and the number of those surviving. Due to their relatively small size, the planted woody shrubs were difficult to find beneath the extremely dense stands of sunflower along both stream banks. Many additional shrubs likely exist along the planted corridor than are reported. Overall, 5% of the observed shrubs did not survive.

**Table 5. Woody plant survival at the Spring Creek stream mitigation site in 2013 and 2014.**

Year	Total Plants Inspected	Surviving Plants	Plant Survival Percentage
2013	600	596	99%
2014	377	360	95%

### 4.5. Bank Erosion Inventory

No eroding stream banks were observed at the Spring Creek stream mitigation site. All banks were well vegetated with no signs of bank sloughing or instability.

### 4.6. Channel Form

The formation of pool and riffle habitats within the project reach may be analyzed from the results of perpendicular transect and longitudinal profile surveys of the channel bed (Appendix B). The longitudinal profile along the thalweg of the channel indicates the

presence of nine pools varying in depth from 0.5 to 1.25 feet deeper than the riffles separating them. Design plans (Appendix D, Design Sheet 55 and 56) call for nine pools along the channel profile excavated 1.0 feet deeper than riffles. The longitudinal profile surveyed along the project reach verifies the channel displays a variety of riffle and pool habitats throughout its length.

Transect surveys were conducted at four locations including two pool and two riffle habitats as designated on the design plans. Maximum depth and bankfull widths for each transect are shown in Table 6, and survey results are illustrated in Appendix B. These results indicate the average pool depth is approximately 1.0 feet deeper than the average riffle depth at the surveyed transects. The relatively low variability in channel depth may be attributed to the planform geometry of the channel, which exhibits low sinuosity and very gently arced meander bends. The high radius of curvatures along designated pool sections likely will not generate deep pools, although based on the survey results, are creating slightly deeper and slower water habitat than in riffles.

**Table 6. Spring Creek maximum depths and bankfull widths in 2013 and 2014.**

Transect	Type	Max Depth (ft)		Bankfull Width (ft)	
		2013	2014	2013	2014
1	Pool	3.1	3.5	8.8	10.6
2	Riffle	2.6	2.2	9.1	10.8
3	Pool	2.5	2.7	9.1	8.6
4	Riffle	2.1	2.1	6.3	5.6
Average Riffles		2.4	2.1	7.7	8.2
Average Pools		2.8	3.1	9.0	9.6

The spring creek and urban runoff hydrology of this channel are also unlikely to generate deep pools over time. The hydrologic factors at play in Spring Creek generally do not result in flashy or snowmelt driven runoff events. As a result, natural development of deep pool features is unlikely to occur within the reconstructed section of Spring Creek.

Maximum depth surveyed at both riffles and pools in 2014 fell below the design depth of 2.7 and 3.7 feet, respectively, although the shallower pool depths have been affected by the location of the transects not occurring at the deepest part of the pool. Surveyed bankfull widths at both riffles and pools indicated a slightly wider channel than the 7.5 feet targeted in the design, although the channel does not appear to be actively widening.

#### **4.7. Wildlife Documentation**

Table 7 provides a comprehensive list of wildlife observed at the Spring Creek stream mitigation site. Species observed on site in 2014 included American robin, mallards, Ring-necked pheasant, and Sparrow spp. The low number of species observed may be

attributed to the relatively close proximity to the adjacent highway, human/dog use of the adjacent bike path, and lack of mature tree and shrub cover habitat.

**Table 7. Wildlife species observed at the Spring Creek stream mitigation site in 2013 and 2014.**

Common Name	Scientific Name
<b>Birds</b>	
American Robin	<i>Turdus migratorius</i>
Mallard	<i>Anas platyrhynchos</i>
Common Raven	<i>Corvus corax</i>
Ring-necked Pheasant	<i>Phasianus colchicus</i>
Song Sparrow	<i>Melospiza melodia</i>
Sparrow Sp.	<i>Passer sp.</i>
<b>Mammals</b>	
White-tailed Deer	<i>Odocoileus virginianus</i>

Species observed in 2014 are **bolded**.

## 5.0 COMPARISON OF RESULTS TO PERFORMANCE STANDARDS

Monitoring of the Spring Creek stream mitigation site is intended to document whether the reconstructed segment of the channel is meeting, or moving toward the performance standards outlined in the monitoring plan. The second year of monitoring suggests all six quantitative performance standards are being met four years after the project has been constructed (Table 8). Channel form success is considered a qualitative criterion, and is discussed in more detail in the following section. Additional reporting requirements including photo documentation of the project site, channel construction details, and a planting schematic have been included as appendices to this annual monitoring report.

### 5.1. Riparian Buffer Success

The project reach exhibits vigorous vegetation establishment within the designated riparian areas with no bare ground observed. The densely vegetated riparian zones were well established by a variety of woody and herbaceous species, and a total of 76 species were identified within the mitigation area. Overall, the project area has 95% cover by desirable, non-weed species. Approximately 5% of the area has been colonized by a variety of noxious weeds, which are identified in Section 4.3.

### 5.2. Vegetation Success

The combined, area-weighted percent cover of the riparian and stream banks within the project area was measured at 100%, as no bare ground was observed. The riparian areas and stream banks exhibited dense vegetative growth with a variety of shrubs, forbs, and herbaceous vegetation, indicating establishment exceeding the 70% coverage criteria.

**Table 8. Monitoring results as compared to performance criteria for the Spring Creek mitigation site in 2014.**

Type	Parameter	Performance Standard	Status	Site Meeting Performance Standard?
Quantitative Performance Criteria	Riparian Buffer Success	1a. Areas within creditable riparian buffer disturbed during construction must have 50% or greater aerial cover of non-noxious weed species by the end of the monitoring period	<b>95%</b> of riparian zones have revegetated with non-noxious species	<b>YES</b>
		1b. Noxious weeds do not exceed 10% cover within the riparian buffer areas.	<b>5%</b> of the project area exhibits noxious weeds	<b>YES</b>
	Vegetation Success	2a. Combined aerial cover of riparian and stream bank vegetation communities is at least 70%	Combined riparian and streambank vegetation cover is <b>100%</b>	<b>YES</b>
		2b. Planted trees and shrubs must exhibit 50% survival after 5 years	Planted shrub surveyes indicate <b>95%</b> of shrub survival*	<b>YES</b>
	Vegetation along Streambanks	3. Majority of plants on the river bank must have root stability indexes of at least 6	Dominant species present on stream banks has plant stability index of 9.	<b>YES</b>
	Streambank Stability Success	4. Less than 25% of bank length is unstable and classified as eroding bank.	<b>0%</b> of the banks within the project reach are eroding or unstable	<b>YES</b>
Qualitative Criteria	Channel Form	5. Will be achieved when the stream stabilizes, includes pools and riffles, allows for flood events to occupy the floodplain, and the habitat features such as riparian plant communities have successfully established along streambanks.	See Channel Form Narrative in Section 5.5	<b>YES</b>

\* Performance criteria has been met four years following construction. Additional monitoring is required to meet 5-year survival standard

Woody vegetation plantings indicated a survival rate of 95% four years following construction. The performance criteria states 50% of the woody plants installed must survive five years following construction; therefore, additional monitoring is necessary to meet this criterion. Woody plants remain relatively small but should provide increased percent cover of the site as they mature. Extremely dense vegetation growth within the riparian corridor made locating woody plantings difficult; however very few dead woody plantings were observed throughout the project site.

### **5.3. Vegetation along Stream Banks**

The most prevalent species observed along the banks was reed canary grass, which was observed growing along >50% of the stream banks. This species has a stability index of 9, and provides excellent resistance to bank erosion. Secondary dominant species included Pacific and sandbar willow. Combined, these species covered approximately 40% of the stream banks, and have root stability indices of 7 and 5 respectively.

Stream bank vegetation inventories along Spring Creek indicated 36% of the species having assigned root stability indices scored  $\geq 6$  (9 of 25). In 2013, 80% of the species having assigned root stability indices scored  $\geq 6$  (12 of 15). The disparity between these numbers is partially due to a new plant stability index used for the 2014 monitoring event (Burton et al., 2011). Four of the species identified on the stream banks (*Rosa woodsii*, *Salix exigua*, *Cirsium arvense*, and *Poa palustris*) have stability scores below 6 using the Burton scoring table; whereas, these plants had stability ratings  $\geq 6$  using the Winward scoring index. In addition, several new species occupying a relatively minor percent of the overall bank cover were observed in 2014 which have stability indices below 6.

Given the dominant species present along the banks of Spring Creek exhibit high scores using either of the stability indices, the performance criteria for vegetation along the stream banks is currently being met.

### **5.4. Stream bank Stability Success**

The stream bank inventory did not identify any stream segments with eroding or unstable banks. All banks were very well vegetated with many willow cuttings within five feet of the channel providing additional bank protection. As a result, the performance criterion for stream bank stability is currently being met.

### **5.5. Channel Form Success**

The reconstructed segment of Spring Creek appears to have stabilized following construction, as evidenced by a dense stand of riparian and stream bank vegetation, and lack of lateral or vertical erosion. No vertical head cuts or bank erosion was evident, and the channel does not appear to have migrated following construction.

The Spring Creek channel was designed to convey a capacity equivalent to the estimated 2-year discharge using regional regression equations. The estimated 2 year discharge is 50 cfs (MDT 2010). Discharges above 50 cfs are allowed to escape the

main channel and spread across the adjacent floodplain. The Spring Creek floodplain includes a 17.5-foot wide corridor with side slopes of 10% graded toward the channel.

Previous sections of this monitoring report provide data regarding the establishment of dense riparian and wetland vegetation along the stream banks and riparian zones adjacent to the reconstructed segment of Spring Creek. The stream banks have grown in with woody and herbaceous species that will provide additional habitat features in the form of woody debris and potentially undercut banks as vegetation continues to mature and coir rolls eventually decay.

The longitudinal profile surveyed along the length of the reconstructed channel indicates some degree of habitat variability, with a series of shallow pools providing an additional 0.5 to 1.25 feet of depth as compared to riffles. Nine pools can be identified on the profile, which corresponds to the number of pools proposed on the design plans. Riffle and pool transect re-surveys indicate pools are slightly deeper than riffles. The gently meandering planform and spring driven hydrology of this system likely will not generate particularly deep pools over time. However, surveys through pool habitats indicate some degree of habitat variability exists within the reconstructed channel segment.

The existence of riffles, shallow pools, and a dense riparian overstory provide relatively good habitat for fish that may migrate from Ashley Creek into Spring Creek. Although Spring Creek does not provide an abundance of slow, deep water habitat, the water depth (>1 foot) and velocities (<3 feet/second) observed during the monitoring visits may be suitable for spawning fish. Substrate composition was not documented as part of the monitoring at this site, but if small gravels are present, this reach of Spring Creek could be utilized for spawning fish. It should be noted the existing channel planform and habitat elements are a vast improvement from the former condition of the channel, which was highly incised and channelized, with banks consisting of discarded wood chips from the adjacent mill operation.

The combined results of channel form indicate the reconstructed segment of Spring Creek is stable and provides floodplain access during flood discharges greater than the estimated 2-year flood event discharge of 50 cfs. Evidence of pool and riffle habitats is provided by repeat surveys at pool and riffle transects, as well as the longitudinal profile through the project reach. Channel surveys indicate a constructed channel length of 986 feet.

The combination of quantitative and qualitative monitoring results from 2013 and 2014 suggests the Spring Creek mitigation site is successfully meeting its objective of constructing 990 feet of new channel that creates, enhances, restores, and maintains permanent, naturally self-sustaining, native, or native-like stream and riparian habitats. As a result, four years following the project's construction, the site is achieving its intended goal of providing compensatory mitigation for stream impacts associated with transportation projects including the Kalispell Bypass in the Missoula District.

## 6.0 MANAGEMENT AND DESIGN RECOMMENDATIONS

### 6.1. Riparian and Floodplain Zones

The reconstructed channel segment is designed with upland side slopes that transition to a narrow, 17.5-foot wide floodplain bench. Perpendicular transect survey results (Appendix B) illustrate floodplain slopes down to the channel which reduces the area available for overbank flooding to a narrow zone adjacent to the channel. This design configuration results in a relatively limited riparian/floodplain zone approximately three times wider than the active channel. Integrating a slightly steeper upland side slope design would provide for a wider, more functional floodplain and riparian zone by allowing the stream to access a larger, flat floodplain adjacent to the active channel (Figure 2). Constructing steeper side slopes and a wider floodplain area requires additional excavation; therefore a cost/benefit analysis of creating additional floodplain and wetland features, and the associated mitigation credits, is potentially worth consideration for future stream and riparian mitigation designs.




Figure 2. Alternative grading plan to increase floodplain and riparian areas.

### 6.2. Willow Cutting and Riparian Plug Establishment

The hydrology of Spring Creek is influenced by urban runoff, creating a difficult scenario for predicting typical discharges. During the site visit, Spring Creek was running nearly to the top of its banks, a notable level given the timing of the monitoring event (late August) and the lack of recent precipitation. Design plans called for installing willow cuttings and riparian plugs within the newly constructed stream banks. No willow stems were observed sprouting from within the coir logs and few sedges were observed growing on the inside bends of the pool features, although these features were under water during the site visit. Willow cuttings were very successful establishing just outside of the active channel along the graded floodplain. It is possible the willow cuttings and wetland plugs installed within the active channel did not survive due to long periods of inundation in these planting areas. Verification of vegetation survival in these areas could be conducted when the channel has less water and the banks are more exposed. Overall vegetative growth immediately adjacent to the channel provides excellent protection from bank scour and erosion, and planting techniques employed on this project should be considered for future, similar stream reconstruction plans.

### **6.3. Channel Planform**

The Spring Creek channel planform exhibits a very gently meandering pattern within a relatively narrow floodplain corridor. Channel planform design elements often include a comparison of meander radius of curvatures to bankfull width ratios ( $Rc/W$ ). Gently meandering streams exhibit high  $Rc/W$  ratios, while streams with high sinuosity and sharp bends exhibit low  $Rc/W$  ratios. Lower  $Rc/W$  ratios generally result in pronounced, deeper scour pools on the outside of meander bends, while higher  $Rc/W$  ratios typically result in more planar bed profiles with shallow and infrequent pools.

The Spring Creek design plans indicate meander radii ranging between 20 and 30 meters (66-98 feet), and a riffle bankfull top width of 2.0 meters (6.5 feet). These design parameters generate  $Rc/W$  ratios ranging from 10.1 to 15.0, which are considered high for meandering streams. Given the meander radii proposed in the channel planform design as compared to the bankfull width, pool features probably will not result following flood events. Additional habitat complexity elements could be generated in future projects by designing for lower  $Rc/W$  ratios, increased sinuosity, and wider floodplain corridors. It is acknowledged that each of these habitat improvement elements requires additional excavation (costs) to the overall project; therefore, a cost/benefit analysis is warranted prior to implementing such design considerations. It is also acknowledged that the design channel planform geometry of this segment of Spring Creek is vastly improved from the historic condition of the channel prior to channel reconstruction.

### **7.0 LITERATURE CITED**

- Burton, T.A., S.J. Smith, and E.R. Cowley. 2011. Riparian area management: Multiple indicator monitoring (MIM) of stream channels and streamside vegetation. Technical Reference 1737-23.BLM/OC/ST-10/003+1737. U.S. Department of the Interior, Bureau of Land Management, National Operations Center, Denver, CO. 155 pp.
- Montana Department of Transportation, 2008. Montana Wetland Assessment Method. Helena, Montana.
- Montana Department of Transportation, 2010. Kalispell Bypass MDT Project #NH-MT 5-3(59)109 FST, CN 2038 On-Site Stream Mitigation Plan, Flathead County, Montana.
- Winward, 2000. Monitoring the Vegetation Resources in Riparian Areas. Gen. Tech. Report RMRS-GTR.47. Ogden, UT: U.S. Department of Agriculture, Forest Service, Rocky Mountain Research Station. .

## **Appendix A**


---

### Project Site Maps

---

MDT Stream Mitigation Monitoring  
Spring Creek  
Flathead County, Montana

---



### Legend

-  Photo Points
-  Riparian and Perpendicular Transect Endpoints
-  Riparian Transects
-  Pool and Riffle Transects
-  Channel Thalweg
-  Major Station (100')
-  Minor Station (25')

### 2014 Monitoring Spring Creek


Figure 3

Date: 09/09/2014

X:/MDT\_.007/mains



Source: Esri, DigitalGlobe, GeoEye, i-cubed, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community



**Legend**

-  Project Boundary
-  Vegetation Community Boundary
-  *Cirsium arvense*
-  *Convolvulus arvensis*
-  *Cynoglossum officinale*
-  *Linaria vulgaris*
-  *Tanacetum vulgare*
-  *Centaurea stoebe*
-  1 Elymus Community
-  2 Salix/Helianthus Community
-  3 Salix/Phalaris Community
-  4 Prunus/Alnus Community

**2014 Monitoring Spring Creek**

Figure 4  
 Date: 09/22/2014  
 X:/MDT\_007/mains

## **Appendix B**

---


### Perpendicular Transect Plots and Longitudinal Profile

---


MDT Stream Mitigation Monitoring  
Spring Creek  
Flathead County, Montana

---

# Spring Creek Transect #1 - Pool




# Spring Creek Transect #2 - Riffle




◆ 2013 XS    — 2013 WS    ▲ 2014 XS    × 2014 WS

# Spring Creek Transect #3 - Pool




◆ 2013 XS    — 2013 WS    ▲ 2014 XS    × 2014 WS

# Spring Creek Transect #4 - Riffle



◆ 2013 XS    — 2013 WS    ▲ 2014 XS    × 2014 WS

# Spring Creek Longitudinal Profile



Channel Bed

## **Appendix C**

---

### Project Site Photos

---

MDT Stream Mitigation Monitoring  
Spring Creek  
Flathead County, Montana

---

## PHOTO INFORMATION

PROJECT NAME: Spring Creek Stream Mitigation Site

DATE: 2013 and 2014 Monitoring Events



**Photo Point 1.1—2013**  
**Description:** View looking north (upstream) at project area. **Compass:** 0 (North)



**Photo Point 1.1—2014**  
**Description:** View looking north (upstream) at project area. **Compass:** 0 (North)



**Photo Point 1.2—2013**  
**Description:** View looking south (downstream) at project area. **Compass:** 180 (South)



**Photo Point 1.2—2014**  
**Description:** View looking south (downstream) at project area. **Compass:** 180 (South)



**Photo Point 2—2013**  
**Description:** View looking north of project area from photo point 2. **Compass:** 0 (North)



**Photo Point 2—2014**  
**Description:** View looking north of project area from photo point 2. **Compass:** 0 (North)

**PHOTO INFORMATION**

PROJECT NAME: Spring Creek Stream Mitigation Site

DATE: 2013 and 2014 Monitoring Events



**Photo Point 3.1—2013**  
**Description:** View looking south from photo point 3  
**Compass:** 180 (South)



**Photo Point 3.1—2014**  
**Description:** View looking south from photo point 3  
**Compass:** 180 (South)



**Photo Point 3.2—2013**  
**Description:** Looking of upstream end of project area from photo point 3. **Compass:** 90 (East)



**Photo Point 3.2—2014**  
**Description:** Looking of upstream end of project area from photo point 3. **Compass:** 90 (East)



**Photo Point 4.1—2013**  
**Description:** Northward view of project area from photo point 4. **Compass:** 0 (North)



**Photo Point 4.1—2014**  
**Description:** Northward view of project area from photo point 4. **Compass:** 0 (North)

**PHOTO INFORMATION**

PROJECT NAME: Spring Creek Stream Mitigation Site

DATE: 2013 and 2014 Monitoring Events



**Photo Point 4.2—2013**  
**Description:** View east across the stream channel.  
**Compass:** 90 (East)



**Photo Point 4.2—2014**  
**Description:** View east across the stream channel.  
**Compass:** 90 (East)



**Photo Point 4.3—2013**  
**Description:** View looking downstream at project area.  
**Compass:** 180 (South)



**Photo Point 4.3—2014**  
**Description:** View looking downstream at project area.  
**Compass:** 180 (South)



**Photo 1—2013**  
**Description:** Culvert at upstream end of project area.  
**Compass:** 25 (North-Northeast)



**Photo 1—2014**  
**Description:** Culvert at upstream end of project area.  
**Compass:** 25 (North-Northeast)

**PHOTO INFORMATION**

PROJECT NAME: Spring Creek Stream Mitigation Site

DATE: 2013 and 2014 Monitoring Events



**Photo 2—2013**

**Description:** Hose in stream channel.

**Compass:** 130 (Southeast)



**Photo 2—2014**

**Description:** Hose in stream channel.

**Compass:** 130 (Southeast)



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T1 RIGHT: LOOKING EAST TO T1 LEFT



T1 LEFT: LOOKING WEST TO T1 RIGHT



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T1 RIGHT: LOOKING NORTHEAST UPSTREAM



T1 RIGHT: LOOKING SOUTH DOWNSTREAM



**PHOTOGRAPHIC INSPECTION INFORMATION**

Page 3 of 16

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T1: LOOKING NORTH UPSTREAM FROM MIDDLE OF CREEK



T1: LOOKING SOUTH DOWNSTREAM FROM MIDDLE OF CREEK



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T1 LEFT: LOOKING NORTH UPSTREAM



T1 LEFT: LOOKING SOUTH DOWNSTREAM



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T2 RIGHT: LOOKING EAST TO T2 LEFT



T2 LEFT: LOOKING WEST TO T2 RIGHT



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T2 RIGHT: LOOKING NORTH UPSTREAM



T2 RIGHT: LOOKING SOUTH DOWNSTREAM



**PHOTOGRAPHIC INSPECTION INFORMATION**

Page 7 of 16

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T2: LOOKING NORTH UPSTREAM FROM MIDDLE OF CREEK



T2: LOOKING SOUTH DOWNSTREAM FROM MIDDLE OF CREEK



**PHOTOGRAPHIC INSPECTION INFORMATION**

Page 8 of 16

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T2 LEFT: LOOKING NORTH UPSTREAM



T2 LEFT: LOOKING SOUTH DOWNSTREAM





**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T3 RIGHT: LOOKING NORTH UPSTREAM



T3 RIGHT: LOOKING SOUTH DOWNSTREAM



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T3: LOOKING NORTH UPSTREAM FROM MIDDLE OF CREEK



T3: LOOKING SOUTH DOWNSTREAM FROM MIDDLE OF CREEK



**PHOTOGRAPHIC INSPECTION INFORMATION**

Page 12 of 16

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T3 LEFT: LOOKING NORTH UPSTREAM



T3 LEFT: LOOKING SOUTH DOWNSTREAM



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T4 RIGHT: LOOKING EAST TO T4 LEFT



T4 LEFT: LOOKING WEST TO T4 RIGHT



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T4 RIGHT: LOOKING NORTHEAST UPSTREAM



T4 RIGHT: LOOKING SOUTH DOWNSTREAM



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T4: LOOKING NORTH UPSTREAM FROM MIDDLE OF CREEK



T4: LOOKING SOUTHWEST DOWNSTREAM FROM MIDDLE OF CREEK



**PHOTOGRAPHIC INSPECTION INFORMATION**

PROJECT NAME: 2014 MDT STREAM MITIGATION—SPRING CREEK

DATE: 7-30-14



T1 LEFT: LOOKING NORTH UPSTREAM



T1 LEFT: LOOKING SOUTHWEST DOWNSTREAM

## **Appendix D**

---

### Channel Construction Details

---

MDT Stream Mitigation Monitoring  
Spring Creek  
Flathead County, Montana

---

# DETAIL

## SPRING CREEK CHANNEL CHANGE

LEGEND  
 STREAM RIFFLE SECTION  
 STREAM POOL SECTION


**CENTERLINE COORDINATE TABLE NO. 1**

STATION	DESCRIPTION	N OR Y COORDINATE	E OR X COORDINATE	REMARKS
58119.36	POB	449 114.5861	240 795.0042	
58158.42	PC	449 152.3017	240 831.2578	BEGIN CHANNEL CHANGE
58162.53	PI	449 156.4550	240 832.3814	
58166.64	P2	449 160.6083	240 833.5050	
58170.75	PC	449 164.7616	240 834.6286	
58174.86	PI	449 168.9149	240 835.7522	
58178.97	P2	449 173.0682	240 836.8758	
58183.08	PC	449 177.2215	240 838.0000	
58187.19	PI	449 181.3748	240 839.1236	
58191.30	P2	449 185.5281	240 840.2472	
58195.41	PC	449 189.6814	240 841.3708	
58199.52	PI	449 193.8347	240 842.4944	
58203.63	P2	449 197.9880	240 843.6180	
58207.74	PC	449 202.1413	240 844.7416	
58211.85	PI	449 206.2946	240 845.8652	
58215.96	P2	449 210.4479	240 846.9888	
58220.07	PC	449 214.6012	240 848.1124	
58224.18	PI	449 218.7545	240 849.2360	
58228.29	P2	449 222.9078	240 850.3596	
58232.40	PC	449 227.0611	240 851.4832	
58236.51	PI	449 231.2144	240 852.6068	
58240.62	P2	449 235.3677	240 853.7304	
58244.73	PC	449 239.5210	240 854.8540	
58248.84	PI	449 243.6743	240 855.9776	
58252.95	P2	449 247.8276	240 857.1012	
58257.06	PC	449 251.9809	240 858.2248	
58261.17	PI	449 256.1342	240 859.3484	
58265.28	P2	449 260.2875	240 860.4720	
58269.39	PC	449 264.4408	240 861.5956	
58273.50	PI	449 268.5941	240 862.7192	
58277.61	P2	449 272.7474	240 863.8428	
58281.72	PC	449 276.9007	240 864.9664	
58285.83	PI	449 281.0540	240 866.0900	
58289.94	P2	449 285.2073	240 867.2136	
58294.05	PC	449 289.3606	240 868.3372	
58298.16	PI	449 293.5139	240 869.4608	
58302.27	P2	449 297.6672	240 870.5844	
58306.38	PC	449 301.8205	240 871.7080	
58310.49	PI	449 305.9738	240 872.8316	
58314.60	P2	449 310.1271	240 873.9552	
58318.71	PC	449 314.2804	240 875.0788	
58322.82	PI	449 318.4337	240 876.2024	
58326.93	P2	449 322.5870	240 877.3260	
58331.04	PC	449 326.7403	240 878.4496	
58335.15	PI	449 330.8936	240 879.5732	
58339.26	P2	449 335.0469	240 880.6968	
58343.37	PC	449 339.2002	240 881.8204	
58347.48	PI	449 343.3535	240 882.9440	
58351.59	P2	449 347.5068	240 884.0676	
58355.70	PC	449 351.6601	240 885.1912	
58359.81	PI	449 355.8134	240 886.3148	
58363.92	P2	449 359.9667	240 887.4384	
58368.03	PC	449 364.1200	240 888.5620	
58372.14	PI	449 368.2733	240 889.6856	
58376.25	P2	449 372.4266	240 890.8092	
58380.36	PC	449 376.5799	240 891.9328	
58384.47	PI	449 380.7332	240 893.0564	
58388.58	P2	449 384.8865	240 894.1800	
58392.69	PC	449 389.0398	240 895.3036	
58396.80	PI	449 393.1931	240 896.4272	
58400.91	P2	449 397.3464	240 897.5508	
58405.02	PC	449 401.5000	240 898.6744	
58409.13	PI	449 405.6533	240 899.7980	
58413.24	P2	449 409.8066	240 900.9216	
58417.35	PC	449 413.9600	240 902.0452	
58421.46	PI	449 418.1133	240 903.1688	
58425.57	P2	449 422.2666	240 904.2924	
58429.68	PC	449 426.4200	240 905.4160	
58433.79	PI	449 430.5733	240 906.5396	
58437.90	P2	449 434.7266	240 907.6632	
58442.01	PC	449 438.8800	240 908.7868	
58446.12	PI	449 443.0333	240 909.9104	
58450.23	P2	449 447.1866	240 911.0340	
58454.34	PC	449 451.3400	240 912.1576	
58458.45	PI	449 455.4933	240 913.2812	
58462.56	P2	449 459.6466	240 914.4048	
58466.67	PC	449 463.8000	240 915.5284	
58470.78	PI	449 467.9533	240 916.6520	
58474.89	P2	449 472.1066	240 917.7756	
58479.00	PC	449 476.2600	240 918.8992	
58483.11	PI	449 480.4133	240 920.0228	
58487.22	P2	449 484.5666	240 921.1464	
58491.33	PC	449 488.7200	240 922.2700	
58495.44	PI	449 492.8733	240 923.3936	
58499.55	P2	449 497.0266	240 924.5172	
58503.66	PC	449 501.1800	240 925.6408	
58507.77	PI	449 505.3333	240 926.7644	
58511.88	P2	449 509.4866	240 927.8880	
58515.99	PC	449 513.6400	240 929.0116	
58520.10	PI	449 517.7933	240 930.1352	
58524.21	P2	449 521.9466	240 931.2588	
58528.32	PC	449 526.1000	240 932.3824	
58532.43	PI	449 530.2533	240 933.5060	
58536.54	P2	449 534.4066	240 934.6296	
58540.65	PC	449 538.5600	240 935.7532	
58544.76	PI	449 542.7133	240 936.8768	
58548.87	P2	449 546.8666	240 938.0004	
58552.98	PC	449 551.0200	240 939.1240	
58557.09	PI	449 555.1733	240 940.2476	
58561.20	P2	449 559.3266	240 941.3712	
58565.31	PC	449 563.4800	240 942.4948	
58569.42	PI	449 567.6333	240 943.6184	
58573.53	P2	449 571.7866	240 944.7420	
58577.64	PC	449 575.9400	240 945.8656	
58581.75	PI	449 580.0933	240 946.9892	
58585.86	P2	449 584.2466	240 948.1128	
58590.00	PC	449 588.4000	240 949.2364	
58594.11	PI	449 592.5533	240 950.3600	
58598.22	P2	449 596.7066	240 951.4836	
58602.33	PC	449 600.8600	240 952.6072	
58606.44	PI	449 605.0133	240 953.7308	
58610.55	P2	449 609.1666	240 954.8544	
58614.66	PC	449 613.3200	240 955.9780	
58618.77	PI	449 617.4733	240 957.1016	
58622.88	P2	449 621.6266	240 958.2252	
58627.00	PC	449 625.7800	240 959.3488	
58631.11	PI	449 629.9333	240 960.4724	
58635.22	P2	449 634.0866	240 961.5960	
58639.33	PC	449 638.2400	240 962.7196	
58643.44	PI	449 642.3933	240 963.8432	
58647.55	P2	449 646.5466	240 964.9668	
58651.66	PC	449 650.7000	240 966.0904	
58655.77	PI	449 654.8533	240 967.2140	
58659.88	P2	449 659.0066	240 968.3376	
58664.00	PC	449 663.1600	240 969.4612	
58668.11	PI	449 667.3133	240 970.5848	
58672.22	P2	449 671.4666	240 971.7084	
58676.33	PC	449 675.6200	240 972.8320	
58680.44	PI	449 679.7733	240 973.9556	
58684.55	P2	449 683.9266	240 975.0792	
58688.66	PC	449 688.0800	240 976.2028	
58692.77	PI	449 692.2333	240 977.3264	
58696.88	P2	449 696.3866	240 978.4500	
58701.00	PC	449 700.5400	240 979.5736	
58705.11	PI	449 704.6933	240 980.6972	
58709.22	P2	449 708.8466	240 981.8208	
58713.33	PC	449 713.0000	240 982.9444	
58717.44	PI	449 717.1533	240 984.0680	
58721.55	P2	449 721.3066	240 985.1916	
58725.66	PC	449 725.4600	240 986.3152	
58729.77	PI	449 729.6133	240 987.4388	
58733.88	P2	449 733.7666	240 988.5624	
58738.00	PC	449 737.9200	240 989.6860	
58742.11	PI	449 742.0733	240 990.8096	
58746.22	P2	449 746.2266	240 991.9332	
58750.33	PC	449 750.3800	240 993.0568	
58754.44	PI	449 754.5333	240 994.1804	
58758.55	P2	449 758.6866	240 995.3040	
58762.66	PC	449 762.8400	240 996.4276	
58766.77	PI	449 766.9933	240 997.5512	
58770.88	P2	449 771.1466	240 998.6748	
58775.00	PC	449 775.3000	240 999.7984	
58779.11	PI	449 779.4533	240 1000.9220	
58783.22	P2	449 783.6066	240 1002.0456	
58787.33	PC	449 787.7600	240 1003.1692	
58791.44	PI	449 791.9133	240 1004.2928	
58795.55	P2	449 796.0666	240 1005.4164	
58800.00	PC	449 800.2200	240 1006.5400	
58804.11	PI	449 804.3733	240 1007.6636	
58808.22	P2	449 808.5266	240 1008.7872	
58812.33	PC	449 812.6800	240 1009.9108	
58816.44	PI	449 816.8333	240 1011.0344	
58820.55	P2	449 820.9866	240 1012.1580	
58824.66	PC	449 825.1400	240 1013.2816	
58828.77	PI	449 829.2933	240 1014.4052	
58832.88	P2	449 833.4466	240 1015.5288	
58837.00	PC	449 837.6000	240 1016.6524	
58841.11	PI	449 841.7533	240 1017.7760	
58845.22	P2	449 845.9066	240 1018.8996	
58849.33	PC	449 850.0600	240 1020.0232	
58853.44	PI	449 854.2133	240 1021.1468	
58857.55	P2	449 858.3666	240 1022.2704	
58861.66	PC	449 862.5200	240 1023.3940	
58865.77	PI	449 866.6733	240 1024.5176	
58870.00	P2	449 870.8266	240 1025.6412	
58874.11	PC	449 874.9800	240 1026.7648	
58878.22	PI	449 879.1333	240 1027.8884	
58882.33	P2	449 883.2866	240 1029.0120	
58886.44	PC	449 887.4400	240 1030.1356	
58890.55	PI	449 891.5933	240 1031.2592	
58894.66	P2	449 895.7466	240 1032.3828	
58898.77	PC	449 899.9000	240 1033.5064	
58902.88	PI	449 904.0533	240 1034.6300	
58907.00	P2	449 908.2066	240 1035.7536	
58911.11	PC	449 912.3600	240 1036.8772	
58915.22	PI	449 916.5133	240 1038.0008	
58919.33	P2	449 920.6666	240 1039.1244	
58923.44	PC	449 924.8200	240 1040.2480	
58927.55	PI	449 928.9733	240 1041.3716	
58931.66	P2	449 933.1266	240 1042.4952	
58935.77	PC	449 937.2800	240 1043.6188	
58939.88	PI	449 941.4333	240 1044.7424	
58944.00	P2	449 945.5866	240 1045.8660	
58948.11	PC	449 949.7400	240 1046.9896	

STATE	PROJECT NUMBER	SHEET NO
MONTANA	ARRA 151921	56
CSP - 0.999470385		

# DETAIL

## SPRING CREEK CHANNEL CHANGE POOL SECTION




■ GULL SLOPES, LEFT  
 60+982 TO 60+987: 1:1  
 60+987 TO 61+21: 3:1 TO 6:1

■ GULL SLOPES, RIGHT  
 58+44 TO 58+45: 4:1  
 58+45 TO 58+46: 2:1  
 58+46 TO 58+47: 2:1  
 58+47 TO 58+48: 2:1  
 58+48 TO 58+49: 2:1  
 58+49 TO 58+50: 2:1  
 58+50 TO 58+51: 2:1  
 58+51 TO 58+52: 2:1  
 58+52 TO 58+53: 2:1  
 58+53 TO 58+54: 2:1  
 58+54 TO 58+55: 2:1  
 58+55 TO 58+56: 2:1  
 58+56 TO 58+57: 2:1  
 58+57 TO 58+58: 2:1  
 58+58 TO 58+59: 2:1  
 58+59 TO 58+60: 2:1  
 58+60 TO 58+61: 2:1  
 58+61 TO 58+62: 2:1  
 58+62 TO 58+63: 2:1  
 58+63 TO 58+64: 2:1  
 58+64 TO 58+65: 2:1  
 58+65 TO 58+66: 2:1  
 58+66 TO 58+67: 2:1  
 58+67 TO 58+68: 2:1  
 58+68 TO 58+69: 2:1  
 58+69 TO 58+70: 2:1  
 58+70 TO 58+71: 2:1  
 58+71 TO 58+72: 2:1  
 58+72 TO 58+73: 2:1  
 58+73 TO 58+74: 2:1  
 58+74 TO 58+75: 2:1  
 58+75 TO 58+76: 2:1  
 58+76 TO 58+77: 2:1  
 58+77 TO 58+78: 2:1  
 58+78 TO 58+79: 2:1  
 58+79 TO 58+80: 2:1  
 58+80 TO 58+81: 2:1  
 58+81 TO 58+82: 2:1  
 58+82 TO 58+83: 2:1  
 58+83 TO 58+84: 2:1  
 58+84 TO 58+85: 2:1  
 58+85 TO 58+86: 2:1  
 58+86 TO 58+87: 2:1  
 58+87 TO 58+88: 2:1  
 58+88 TO 58+89: 2:1  
 58+89 TO 58+90: 2:1  
 58+90 TO 58+91: 2:1  
 58+91 TO 58+92: 2:1  
 58+92 TO 58+93: 2:1  
 58+93 TO 58+94: 2:1  
 58+94 TO 58+95: 2:1  
 58+95 TO 58+96: 2:1  
 58+96 TO 58+97: 2:1  
 58+97 TO 58+98: 2:1  
 58+98 TO 58+99: 2:1  
 58+99 TO 59+00: 2:1  
 59+00 TO 59+01: 2:1  
 59+01 TO 59+02: 2:1  
 59+02 TO 59+03: 2:1  
 59+03 TO 59+04: 2:1  
 59+04 TO 59+05: 2:1  
 59+05 TO 59+06: 2:1  
 59+06 TO 59+07: 2:1  
 59+07 TO 59+08: 2:1  
 59+08 TO 59+09: 2:1  
 59+09 TO 59+10: 2:1  
 59+10 TO 59+11: 2:1  
 59+11 TO 59+12: 2:1  
 59+12 TO 59+13: 2:1  
 59+13 TO 59+14: 2:1  
 59+14 TO 59+15: 2:1  
 59+15 TO 59+16: 2:1  
 59+16 TO 59+17: 2:1  
 59+17 TO 59+18: 2:1  
 59+18 TO 59+19: 2:1  
 59+19 TO 59+20: 2:1  
 59+20 TO 59+21: 2:1  
 59+21 TO 59+22: 2:1  
 59+22 TO 59+23: 2:1  
 59+23 TO 59+24: 2:1  
 59+24 TO 59+25: 2:1  
 59+25 TO 59+26: 2:1  
 59+26 TO 59+27: 2:1  
 59+27 TO 59+28: 2:1  
 59+28 TO 59+29: 2:1  
 59+29 TO 59+30: 2:1  
 59+30 TO 59+31: 2:1  
 59+31 TO 59+32: 2:1  
 59+32 TO 59+33: 2:1  
 59+33 TO 59+34: 2:1  
 59+34 TO 59+35: 2:1  
 59+35 TO 59+36: 2:1  
 59+36 TO 59+37: 2:1  
 59+37 TO 59+38: 2:1  
 59+38 TO 59+39: 2:1  
 59+39 TO 59+40: 2:1  
 59+40 TO 59+41: 2:1  
 59+41 TO 59+42: 2:1  
 59+42 TO 59+43: 2:1  
 59+43 TO 59+44: 2:1  
 59+44 TO 59+45: 2:1  
 59+45 TO 59+46: 2:1  
 59+46 TO 59+47: 2:1  
 59+47 TO 59+48: 2:1  
 59+48 TO 59+49: 2:1  
 59+49 TO 59+50: 2:1  
 59+50 TO 59+51: 2:1  
 59+51 TO 59+52: 2:1  
 59+52 TO 59+53: 2:1  
 59+53 TO 59+54: 2:1  
 59+54 TO 59+55: 2:1  
 59+55 TO 59+56: 2:1  
 59+56 TO 59+57: 2:1  
 59+57 TO 59+58: 2:1  
 59+58 TO 59+59: 2:1  
 59+59 TO 60+00: 2:1  
 60+00 TO 60+01: 2:1  
 60+01 TO 60+02: 2:1  
 60+02 TO 60+03: 2:1  
 60+03 TO 60+04: 2:1  
 60+04 TO 60+05: 2:1  
 60+05 TO 60+06: 2:1  
 60+06 TO 60+07: 2:1  
 60+07 TO 60+08: 2:1  
 60+08 TO 60+09: 2:1  
 60+09 TO 60+10: 2:1  
 60+10 TO 60+11: 2:1  
 60+11 TO 60+12: 2:1  
 60+12 TO 60+13: 2:1  
 60+13 TO 60+14: 2:1  
 60+14 TO 60+15: 2:1  
 60+15 TO 60+16: 2:1  
 60+16 TO 60+17: 2:1  
 60+17 TO 60+18: 2:1  
 60+18 TO 60+19: 2:1  
 60+19 TO 60+20: 2:1  
 60+20 TO 60+21: 2:1  
 60+21 TO 60+22: 2:1  
 60+22 TO 60+23: 2:1  
 60+23 TO 60+24: 2:1  
 60+24 TO 60+25: 2:1  
 60+25 TO 60+26: 2:1  
 60+26 TO 60+27: 2:1  
 60+27 TO 60+28: 2:1  
 60+28 TO 60+29: 2:1  
 60+29 TO 60+30: 2:1  
 60+30 TO 60+31: 2:1  
 60+31 TO 60+32: 2:1  
 60+32 TO 60+33: 2:1  
 60+33 TO 60+34: 2:1  
 60+34 TO 60+35: 2:1  
 60+35 TO 60+36: 2:1  
 60+36 TO 60+37: 2:1  
 60+37 TO 60+38: 2:1  
 60+38 TO 60+39: 2:1  
 60+39 TO 60+40: 2:1  
 60+40 TO 60+41: 2:1  
 60+41 TO 60+42: 2:1  
 60+42 TO 60+43: 2:1  
 60+43 TO 60+44: 2:1  
 60+44 TO 60+45: 2:1  
 60+45 TO 60+46: 2:1  
 60+46 TO 60+47: 2:1  
 60+47 TO 60+48: 2:1  
 60+48 TO 60+49: 2:1  
 60+49 TO 60+50: 2:1  
 60+50 TO 60+51: 2:1  
 60+51 TO 60+52: 2:1  
 60+52 TO 60+53: 2:1  
 60+53 TO 60+54: 2:1  
 60+54 TO 60+55: 2:1  
 60+55 TO 60+56: 2:1  
 60+56 TO 60+57: 2:1  
 60+57 TO 60+58: 2:1  
 60+58 TO 60+59: 2:1  
 60+59 TO 60+60: 2:1  
 60+60 TO 60+61: 2:1  
 60+61 TO 60+62: 2:1  
 60+62 TO 60+63: 2:1  
 60+63 TO 60+64: 2:1  
 60+64 TO 60+65: 2:1  
 60+65 TO 60+66: 2:1  
 60+66 TO 60+67: 2:1  
 60+67 TO 60+68: 2:1  
 60+68 TO 60+69: 2:1  
 60+69 TO 60+70: 2:1  
 60+70 TO 60+71: 2:1  
 60+71 TO 60+72: 2:1  
 60+72 TO 60+73: 2:1  
 60+73 TO 60+74: 2:1  
 60+74 TO 60+75: 2:1  
 60+75 TO 60+76: 2:1  
 60+76 TO 60+77: 2:1  
 60+77 TO 60+78: 2:1  
 60+78 TO 60+79: 2:1  
 60+79 TO 60+80: 2:1  
 60+80 TO 60+81: 2:1  
 60+81 TO 60+82: 2:1  
 60+82 TO 60+83: 2:1  
 60+83 TO 60+84: 2:1  
 60+84 TO 60+85: 2:1  
 60+85 TO 60+86: 2:1  
 60+86 TO 60+87: 2:1  
 60+87 TO 60+88: 2:1  
 60+88 TO 60+89: 2:1  
 60+89 TO 60+90: 2:1  
 60+90 TO 60+91: 2:1  
 60+91 TO 60+92: 2:1  
 60+92 TO 60+93: 2:1  
 60+93 TO 60+94: 2:1  
 60+94 TO 60+95: 2:1  
 60+95 TO 60+96: 2:1  
 60+96 TO 60+97: 2:1  
 60+97 TO 60+98: 2:1  
 60+98 TO 60+99: 2:1  
 60+99 TO 60+100: 2:1

NOTE: SEE VEGETATION PLANS FOR SEEDING & PLANTINGS

## SPRING CREEK CHANNEL CHANGE RIFFLE SECTION



NOTE: SEE VEGETATION PLANS FOR SEEDING & PLANTINGS

KBP - FOYS LAKE RD TO US 2  
 SPRING CREEK CHANNEL CHANGE  
 POOL SECTION  
 RIFFLE SECTION

NO SCALE




DATE	BY	REVISION
10/2/2009	HEAVY	REVISED
11/18/2009	CHIEF	CHECKED
11/18/2009	DESIGN	DRAWN
11/18/2009	DESIGN	APPROVED
11/18/2009	DESIGN	REVISED

STATE PROJECT NUMBER SHEET NO.  
 MONTANA ARRA 151922 VA

CSF - 0.999470385

**DETAIL**  
 ASHLEY CREEK NORTH & SPRING CREEK  
 VEGETATION PLAN



LEGEND

	AREA 4 UPLAND SEED MIX
	AREA 5 RIPARIAN SEED MIX
	PROPOSED SHRUB PLANTING
	COR ROLLS
	PROPOSED TREE PLANTING

KBP - FOYS LAKE RD TO US 2  
 ASHLEY CREEK NORTH & SPRING CREEK  
 VEGETATION PLAN

SCALE 1:250

NOTE: THIS PLAN IS A GRAPHIC REPRESENTATION OF THE SECTIONS AND PLANT LISTS FOR MORE DETAILED ZONAL PLACEMENT.



DESIGNER	DATE
DRAWN	
APPROVED	
REVISED	
INITIALS	DATE



# DETAIL

## ASHLEY CREEK NORTH & SPRING CREEK VEGETATION SUMMARY & DETAILS

- CHANNEL PLANTING SEQUENCE**
1. PLACE COIR ROLL AS PER COIR ROLLS DETAIL IN ROADWAY PLANS AND SPECIAL PROVISIONS.
  2. INSTALL PLANTS BETWEEN THE DATES OF OCTOBER 1 AND NOVEMBER 15 OR APRIL 30 AND JUNE 1 PROVIDED THE GROUND IS NOT FROZEN.
  3. PLANT RIPARIAN PLUGS AS PER INSTALLING DETAIL AND SPECIAL PROVISIONS.
  4. PLANT CUTTINGS AS PER INSTALLING DETAIL AND SPECIAL PROVISIONS.
  5. INSTALL JUTE NETTING ON SLOPES GREATER THAN 3:1 AS PER SPECIAL PROVISIONS.
  6. SEED UPLAND AREA 4 AND RIPARIAN AREA 5 AS PER SEEDING SPECIAL PROVISIONS.
  7. APPLY TOP DRESSING AND FERTILIZER AS PER SPECIAL PROVISIONS.
  8. APPLY WEED FREE ORGANIC COMPOST MULCH AS PER SPECIAL PROVISIONS.


ASHLEY CREEK NORTH & SPRING CREEK CHANNEL CHANGE PLANT LIST			
ZONE A UPLAND			
TYPE	BOTANICAL NAME	COMMON NAME	SIZE
TREES			
BP	BETULA PAPERIFERA	PAPER BIRCH	4 10' BAB
PP	PRUNUS PONDEROSA	PLUM	3 7' BAB
PM	PIEDMONT PINE	PIEDMONT PINE	8 6' BAB
ZONE B TRANSITIONAL			
TYPE	BOTANICAL NAME	COMMON NAME	SIZE
SHRUBS			
AG	AMELANCHIER ALNIFOLIA	SASKATOON SERVICEBERRY	100 1 CAL.
AD	ARTEMISIA CANADENSIS	ROCKY MOUNTAIN ARTEMISIA	243 1 CAL.
RO	ROGOSA ROSA	ROSE	243 1 CAL.
CA	CANADIAN BUFFALO BERRY	CANADIAN BUFFALO BERRY	41 1 CAL.
SP	SPIRAEAE ALBIS	SPIRAEA	156 1 CAL.
ZONE C SEASONALLY FLOODED			
TYPE	BOTANICAL NAME	COMMON NAME	SIZE
TREES			
BD	BETULA OCCIDENTALIS	WATER BIRCH	11 15 CAL.
ZONE D SEMI-PERMANENTLY FLOODED			
TYPE	BOTANICAL NAME	COMMON NAME	SIZE
SHRUBS			
AT	ARTEMISIA TENIFOLIA	ROCKY MOUNTAIN ARTEMISIA	43 5 GAL.
TR	TRIN-LEAF ALDER	TRIN-LEAF ALDER	38 5 GAL.
SD	SALIX BICOLOR	WOODS ROSE	38 5 GAL.
SB	SALIX BEBBIANA	BEBB WILLOW	38 5 GAL.
SD	SALIX DRUMMONDIANA	DRUMMOND WILLOW	33 5 GAL.
COIR ROLL STAKING			
TYPE	BOTANICAL NAME	COMMON NAME	SIZE
SP	SALIX BICOLOR	WOODS ROSE	350 CUTTINGS
SD	SALIX DRUMMONDIANA	DRUMMOND WILLOW	350 CUTTINGS
COIR ROLL LAYERING			
TYPE	BOTANICAL NAME	COMMON NAME	SIZE
SP	SALIX BICOLOR	WOODS ROSE	1500 CUTTINGS
SD	SALIX DRUMMONDIANA	DRUMMOND WILLOW	1500 CUTTINGS
STREAMBANK PLUGS			
TYPE	BOTANICAL NAME	COMMON NAME	SIZE
GR	GRASS	GRASS	288 PLUGS
NE	NEBRASKA SEDGE	NEBRASKA SEDGE	288 PLUGS
CA	CAREX	CAREX	288 PLUGS
VE	VEGETATION	VEGETATION	288 PLUGS
LS	LOOSE STRAW	LOOSE STRAW	123 PLUGS

\* FOR INFORMATION ONLY. INCLUDE ALL COSTS AND MATERIALS ASSOCIATED WITH THE INSTALLATION OF THIS ITEM IN THE LUMP SUM BID PRICE FOR "VEGETATION".

JUTE NETTING *	
STATION	Square meters
FROM 56+19.58	6372
TO 63+72	6372
TOTAL	12744


\* FOR INFORMATION ONLY. INCLUDE ALL COSTS AND MATERIALS ASSOCIATED WITH THE INSTALLATION OF THIS ITEM IN THE LUMP SUM BID PRICE FOR "VEGETATION".

DESIGNER		INITIALS	DATE
DRAWN			
CHECKED			
APPROVED			
REVISION			



ZONE D COIR BUNDLES WITH WILLOW CUTTINGS AND LAYERING SCALE: NOT TO SCALE

- HARVESTING AND INSTALLATION NOTES:**
1. HARVEST AND PLANT CUTTINGS DURING OPTIMUM SEASON.
  2. USE HEALTHY STRAIGHT AND LIVE WOOD AT LEAST 1 YEAR OLD.
  3. MAKE CLEAN CUTS AND DO NOT DAMAGE CUTTINGS OR SPLIT ENDS.
  4. BRIEFLY SOAK CUTTINGS IN WATER AND ROOTING HORMONE PRIOR TO INSTALLATION.
  5. BIODEGRADABLE BUNDLES CUTTINGS TOGETHER AND BIND WITH BINDER.
  6. INSTALL WILLOW CUTTING AND WILLOW BUNDLE LAYERING.
  7. PLANT BUNDLES AND WILLOW BUNDLES SHALL EXTEND INTO EXPECTED MOISTURE SOIL ZONES.
  8. LIVE WILLOW CUTTING SMALL HOLES IN COIR ROLLS AND INSERT BUNDLES INTO SOIL BETWEEN COIR ROLLS.
  9. INSERT BUNDLES INTO SOIL BETWEEN COIR ROLLS.



ZONE D RIPARIAN PLUG PLANTING FOR INSIDE BAND OF SPRING CREEK MOLES SCALE: NOT TO SCALE

SPACING

KBP - FOYS LAKE RD TO US 2  
ASHLEY CREEK NORTH & SPRING CREEK VEGETATION SUMMARY & DETAILS

NO SCALE



REVISED BY	10/6/2009
CHECKED BY	14:28:02 AM
DATE	02/18/09