MONTANA DEPARTMENT OF TRANSPORTATION
WETLAND MITIGATION MONITORING REPORT: YEAR 2006

Kleinschmidt Creek
Ovando, Montana

Prepared for:

MONTANA DEPARTMENT OF TRANSPORTATION
2701 Prospect Ave
Helena, MT 59620-1001

Prepared by:

POST, BUCKLEY, SCHUH, & JERNIGAN
P.O. Box 239
Helena, MT 59624

December 2006

Project No: B43054.00 - 0112

MONTANA DEPARTMENT OF TRANSPORTATION

WETLAND MITIGATION MONITORING REPORT:

YEAR 2006

Kleinschmidt Creek
Ovando, Montana

Prepared for:

MONTANA DEPARTMENT OF TRANSPORTATION
2701 Prospect Ave
Helena, MT 59620-1001

Prepared by:

POST, BUCKLEY, SCHUH & JERNIGAN
P.O. Box 239
Helena, MT 59624

December 2006

B43054.00 - 0112

"MDT attempts to provide accommodations for any known disability that may interfere with a person participating in any service, program, or activity of the Department of Transportation. Alternative accessible formats of this information will be provided upon request. For further information, call 406-444-7228 or TTY (800-335-7592) or by calling Montana Relay at 711."

PBS&J

TABLE OF CONTENTS

TABLES

FIGURES

CHARTS

APPENDICES

1.0 INTRODUCTION

This report documents the 2006 (fifth year) monitoring results at the Kleinschmidt Creek Wetland Mitigation Site. The site was developed to mitigate wetland impacts associated with two Montana Department of Transportation (MDT) projects, Clearwater Junction North and Helmville Junction, and to serve as a reserve for future MDT projects in the watershed. Kleinschmidt Creek is located in Powell County within the Upper Clark Fork River Basin (watershed #2). The mitigation site is located approximately six miles east of Ovando, Montana and is directly adjacent to MT Highway 200 (**Figure 1**). Elevations of the site range from 4,200 ft. at the eastern boundary to 4,180 ft. at the western boundary. Land and Water Consulting (LWC) conducted the baseline wetland delineation for the Kleinschmidt Creek proposed mitigation site in the summer of 1999. A U.S. Fish and Wildlife Service contractor conducted the baseline functional assessments for the site in 1998.

The approximate site boundary is illustrated on **Figure 2** in **Appendix A**. The project is located on property owned by Thomas Rue within a 47-acre perpetual wetland conservation easement. Kleinschmidt Creek flows west until eventually draining into the North Fork of the Blackfoot River. The perennial creek is spring fed, which provides the primary hydrology source. Local groundwater systems serve as a secondary hydrology source, flowing through the deep alluvial substrate contained along Kleinschmidt Flats and eventually discharging along the Kleinschmidt Creek corridor outside and within the easement area.

Construction at the Kleinschmidt Creek Mitigation Site was completed during the summer of 2001. The overall goals of this project were the restoration, creation, and enhancement (high and low intensity) of heavily grazed and degraded creek/wetlands. Primary restoration objectives included channel reconstruction and fish habitat enhancement on approximately 5,000 ft of Kleinschmidt Creek and the creation of additional wetland areas along the spring fed corridor. Project objectives and task details are included in the following list:

Restoration

- Narrowing and deepening the existing manipulated stream channel, restoring the portion narrowed as wetland.
- Conversion of degraded channel/open water into wetland on approximately 6 acres.
- Planting woody vegetation at a density of 500 stems per acre in portions of the site.
- Eliminating the existing stock water channel under the highway.

Creation

- Converting approximately 1.19 acres of upland area to wetland / shallow open water by adjusting the surface elevation.
- Planting woody vegetation at a density of 500 stems per acre along the perimeter of the shallow open water areas.

High Intensity Enhancement

- Planting woody vegetation on approximately 8.05 acres of existing degraded wetlands at a density of 1,500 stems per acre.

FIGURE 1. PROJECT LOCATION
Kleinschmidt
Mitigation Site





800 0 800 1600 FEET

1: 24,000

PROJECT #: 110174
DATE: FEB 2004
LOCATION:
PROJECT MANAGER: J. BERGLUND
DRAWN BY: B. STEINEBACH

LAND & WATER CONSULTING, INC.

1120 CEDAR PO BOX 8254 MISSOULA, MT 59807

Low Intensity Enhancement

- Planting woody vegetation on the remaining 3.43 acres of existing degraded wetlands at a density of 500 stems per acre (clumped).

The site was designed to mitigate for specific wetland functions impacted by MDT roadway projects, including: storm water retention, roadway runoff filtration, sediment and nutrient retention, water quality, groundwater recharge, and wildlife habitat.

Mitigation credit goals and credit ratios approved by the Corps of Engineers (COE) (Steinle 2001) are contained in **Table 1**.

Table 1: ***Mitigation credit goals and credit ratios for the Kleinschmidt Creek Wetland Mitigation Site.***

Project Component	Total Estimated Acres	Credit Ratio	Credit Acres
Restoration	6.0	1:1	6.0
Creation	1.19	1:1	1.19
High-Intensity Enhancement	8.05	1:2	4.02
Low-Intensity Enhancement	3.43	1:3	1.14
75-Foot Upland Buffer Preservation	12.69	1:4	3.17
Total	**31.36**	**--**	**15.52**

The Kleinschmidt Creek site is monitored once per year to document wetland and other biological attributes. The monitoring area is illustrated in **Figure 2** in **Appendix A**.

2.0 METHODS

2.1 Monitoring Dates and Activities

The site was visited on August 16th (mid-season) of 2006. Monitoring activities were conducted on both the "upstream" (top half of **Figures 2** and **3** in **Appendix A**) and "downstream" (bottom half of **Figures 2** and **3** in **Appendix A**) mitigation sections. The mid-season visit was conducted to document vegetation, soil, and hydrologic conditions used to map jurisdictional wetlands. All information contained on the Wetland Mitigation Site Monitoring Form (**Appendix B**) was collected at this time. Activities and information conducted/collected included: wetland delineation; wetland/open water aquatic habitat boundary mapping; vegetation community mapping; vegetation transect; soils data; hydrology data; bird and general wildlife use; macroinvertebrate sampling; GPS data points; and functional assessment.

2.2 Hydrology

Wetland hydrology indicators were recorded during the mid-season visit using procedures outlined in the COE 1987 Wetland Delineation Manual (Environmental Laboratory 1987). Hydrology data were recorded on COE Routine Wetland Delineation Data Forms (**Appendix B**). Additional hydrologic data were recorded on the Wetland Mitigation Site Monitoring Form (**Appendix B**). No groundwater monitoring wells were installed at the site.

Channel cross sections established on January 8, 2002 were re-sampled on December 1, 2006 (**Appendix A**).

2.3 Vegetation

General dominant species-based vegetation community types (e.g., *Carex/Phalaris*) were delineated on an aerial photograph during the mid-season visit. Standardized community mapping was not employed as many of these systems are geared towards climax vegetation and do not reflect yearly changes. Estimated percent cover of the dominant species in each community type was listed on the Wetland Mitigation Site Monitoring Form (**Appendix B**).

A 10-foot wide belt transect was established during the mid-season monitoring event to represent the range of current vegetation conditions. Percent cover was estimated for each vegetative species within each successive vegetative community encountered within the "belt" using the following values: T (few plants); P (1-5%); 1 (5-15%); 2 (15-25%); 3 (25-35%); 4 (35-45%); 5 (45-55%) and so on to 9 (85-95%). The transect location is illustrated on **Figure 2** in **Appendix A**. The transect is used to evaluate changes over time, especially the establishment and increase of hydrophytic vegetation. The transect location was marked on the aerial photo and all data were recorded on the mitigation site monitoring form. Transect endpoint locations were recorded with the GPS unit in 2002. A photo was taken from both ends of the transect looking along the transect path.

A comprehensive plant species list for the site was compiled and was updated as new species were encountered. Ultimately, observations from past years will be compared with new data to document vegetation changes over time. Revegetation enhancements were implemented in the spring of 2002.

Planting survival ratings and stem counts were conducted during the 2003 - 2006 monitoring seasons. Live planting totals within each mitigation type were counted using a belt transect method. The larger mitigation areas such as the restoration and high intensity enhancement zones were evaluated with more transects. One meter-wide belt transects of varying lengths were used to evaluate plantings throughout the site. The lengths of transects were based on the mitigation type being evaluated. Areas along the channel were walked in segments based on the length of the meanders and distance across wetland pads.

2.4 Soils

Soils were evaluated during the mid-season site visit using the hydric soils determination procedures outlined in the COE 1987 Wetland Delineation Manual. Soil data were recorded for each wetland determination point on the COE Routine Wetland Delineation Data Forms (**Appendix B**). The most current terminology used by NRCS was used to describe hydric soils (USDA 1998).

2.5 Wetland Delineation

Wetland delineation was conducted during the mid-season visit according to the 1987 COE Wetland Delineation Manual. Wetland and upland areas within the monitoring area were investigated for the presence of wetland hydrology, hydrophytic vegetation and hydric soils. The information was recorded on COE Routine Wetland Delineation Data Forms (**Appendix B**). The

wetland/upland boundary was originally delineated on the aerial photo during the 2002 monitoring and recorded with a resource grade GPS unit using the procedures outlined in **Appendix E**. Modifications to these boundaries in 2006 were accomplished by hand-mapping onto the 2005 aerial photograph. The wetland/upland boundary in combination with the wetland/open water boundary was used to calculate the final wetland acreage.

2.6 Mammals, Reptiles, and Amphibians

Mammal, reptile, and amphibian species observations and other positive indicators of use, such as vocalizations, were recorded on the Wetland Mitigation Monitoring Form during the mid-season visit. Indirect use indicators, including tracks; scat; burrows; eggshells; skins; bones; etc., were also recorded. These observations were recorded as the observer traversed the site while conducting other required activities. Direct sampling methods, such as snap traps, live traps, and pitfall traps, were not implemented. A comprehensive species list for the entire site was compiled (**Appendix B**).

2.7 Birds

Bird observations were recorded during the mid-season visit on the Wetland Mitigation Monitoring Site Form (**Appendix B**). No formal protocol, census plot, spot mapping, point count, or strip transect were conducted. Observations were recorded incidental to other monitoring activities and were categorized by species, activity code, and general habitat association.

2.8 Macroinvertebrates

Macroinvertebrate samples were collected during the mid-season site visit at two locations. Samples were collected along Kleinschmidt Creek and the created pond on the upstream sections (**Figure 2** in **Appendix A**). The Macroinvertebrate Sampling Protocol was used (**Appendix F**). Samples were preserved as outlined in the sampling procedure and sent to Rhithron Associates, Inc. in Missoula, Montana for analysis (**Appendix F**).

2.9 Functional Assessment

A functional assessment form was completed using the 1999 MDT Montana Wetland Assessment Method (Berglund 1999) (**Appendix B**). Field data necessary for this assessment were collected during the mid-season visit.

2.10 Photographs

The July 14, 2006 aerial photograph was used for **Figures 2** and **3** (**Appendix A**). Photographs were taken illustrating current land uses surrounding the site, the upland buffer, the monitored area and the vegetation transects. Each photograph point location was recorded with a resource grade GPS in 2002. The location of photo points was mapped onto **Figure 2** in **Appendix A**. All photographs were taken using a digital camera during the 2003 to 2006 visits.

2.11 GPS Data

During the 2002 monitoring season, point data were collected with a resource grade GPS unit at the vegetation transect beginning and ending locations and at all photograph locations. Wetland boundaries were also recorded with a resource grade GPS unit in 2002, but were modified via hand mapping onto aerial photographs in 2006. Procedures used for GPS mapping and aerial photography referencing are included in **Appendix E**.

2.12 Maintenance Needs

Observations were made of existing structures and of erosion/sediment problems to identify maintenance needs. This did not constitute an engineering-level structural inspection, but rather a cursory examination. Current or future potential problems were documented on the monitoring form.

3.0 RESULTS

3.1 Hydrology

The main source of hydrology for this site is groundwater flowing from numerous springs that feed Kleinschmidt Creek, a perennial flowing stream that eventually drains into the North Fork of the Blackfoot River. Kleinschmidt Creek does not experience a large peak flow, which results from snowmelt. The spring fed source of hydrology at this site is augmented by the persistent movement of groundwater across the glacial outwash materials of Kleinschmidt Flats. Higher water flows are usually observed at Kleinschmidt Creek during mid summer after the groundwater levels have been recharged from snowmelt, stream flow and irrigation diversion (DNRC 1999).

The newly constructed channel consisting of rock bottom occurred on 1.75 acres within the mitigation site (**Figure 3** in **Appendix A**). Depths of the perennial creek varied, ranging from 0.5 ft in the straight segments to 2 - 5 ft deep around the bends and meanders. All other wetlands were inundated or saturated during the mid-season visit.

Channel cross sections established on January 8, 2002 were re-sampled on December 1, 2006 and the results are presented on **Figure 5** in **Appendix A**. Banks have remained stable since construction and lateral channel migration has not been observed. As Kleinschmidt Creek is a spring creek with a stable hydrologic regime, major channel adjustments were not anticipated and have not been observed to date.

3.2 Vegetation

Seventy-seven plant species were identified at the site and are listed in **Table 2**. The majority of these species are herbaceous, occurring in saturated wetland meadow complexes and the constructed wetland pads along the reconstructed channel. These wet meadows are seasonally inundated from a ground water-fed hydrology source. A few small groups of mature Pacific willow (*Salix lasiandra*) are present and are limited in distribution to near the heads of the springs. Also, a few random Bebbs willow (*Salix bebbiana*) and shrubby potentilla

Table 2: ***2002 - 2006 vegetation species list at the Kleinschmidt Creek Wetland Mitigation Site.***

Scientific Name	Common Name	Region 9 (Northwest) Wetland Indicator
Achillea millefolium	common yarrow	FACU
Agrostis alba	redtop	FAC+
Agrostis exarata	spike bentgrass	FACW
Agropyron cristatum	crested wheatgrass	--
Agropyron repens	quack grass	FACU
Agropyron smithii	western wheatgrass	FACU
Allium brevistylum	short-style onion	--
Alnus incana	thin leaved alder	FACW
Beckmannia syzigachne	American sloughgrass	OBL
Betula glandulosa	birch	OBL
Bidens cernua	nodding beggars-ticks	FACW+
Bromus inermis	smooth brome	--
Bromus tectorum	cheatgrass	--
Calamagrostis canadensis	bluejoint reedgrass	FACW+
Carex aquatilis	water sedge	OBL
Carex lanuginosa	wooly sedge	OBL
Carex crawei	Crawe sedge	FACW
Carex flava	yellow sedge	OBL
Carex nebrascensis	Nebraska sedge	OBL
Carduus nutans	musk thistle	--
Carex utriculata	beaked sedge	OBL
Carex simulata	short-beaked sedge	OBL
Centaurea maculosa	spotted knapweed	--
Chenopodium album	lambsquarter	FAC
Chrysanthemum leucanthemum	oxeye daisy	--
Cirsium arvense	Canada thistle	FACU+
Cynoglossum officinale	hounds tongue	--
Deschampsia cespitosa	tufted hairgrass	FACW
Eleocharis palustris	creeping spike rush	OBL
Epilobium ciliatum	hairy willow-herb	FACW+
Equisetum arvense	field horsetail	FAC
Equisetum hyemale	scouring rush	FACW
Eriophorum viridicarinatum	green-keeled cottongrass	OBL
Geum macrophyllum	big leafed avens	OBL
Glyceria elata	tall mannagrass	FACW+
Glyceria striata	fowl mannagrass	OBL
Habenaria dilatata	bog orchid	--
Hyoscyamus niger	black henbane	--
Juncus balticus	Baltic rush	FACW
Juncus ensifolius	three-stamen rush	FACW
Juncus mertensianus	Merten's rush	OBL
Juncus nodosus	tuberous rush	OBL
Linaria vulgaris	butter and eggs	--
Lychnis alba	white campion	--
Medicago sativa	alfalfa	--
Melilotus officinalis	yellow sweet clover	FACU
Mentha arvensis	field mint	FAC
Mimulus guttatus	common monkey-flower	OBL
Najas flexilis	wavy water nymph	OBL
Pedicularis groenlandica	elephant’s-head lousewort	OBL
Phalaris arundinacea	reed canarygrass	FACW

Table 1 (continued): ***2002 - 2006 vegetation species list at the Kleinschmidt Creek Wetland Mitigation Site.***

Scientific Name	Common Name	Region 9 (Northwest) Wetland Indicator
Phleum pratense	Timothy	FACU
Plantago spp.	plaintain	--
Poa pratensis	Kentucky bluegrass	FACU+
Polygonum amphibium	water smartweed	OBL
Potentilla anserina	silverweed	OBL
Potentilla fruticosa	shrubby potentilla	FAC-
Ranunculus spp.	buttercup	--
Ranunculus aquatilis var. hispidulus	whitewater buttercup	OBL
Rumex crispus	curly dock	FACW
Sagittaria latifolia	broadleaf arrowhead	OBL
Salix bebbiana	Bebb's willow	FACW
Salix boothii	Booths willow	OBL
Salix drummondiana	Drummond willow	FACW
Salix geyeriana	Geyer willow	FACW+
Salix lasiandra	pacific willow	FACW+
Scirpus acutus	hardstem bulrush	OBL
Scirpus spp.	bulrush	--
Sisymbrium altissimum	tall tumble mustard	FACU-
Sisyrinchium angustifolium	blue-eyed grass	FACW-
Solidago missouriensis	Missouri goldenrod	--
Taraxacum officinale	common dandelion	FACU
Thlaspi arvense	pennycress	NI
Triglochin maritimum	seaside arrowgrass	OBL
Trifolium pratense	red clover	FACU
Typha latifolia	common cattail	OBL
Veronica americana	American speedwell	OBL

[1] **Bolded** species indicate those documented in the analysis area for the first time in 2006.

(*Potentilla fruticosa*) occur throughout some of the wet meadow complexes, but for the most part are very limited in distribution due to the historic livestock grazing.

Nine wetland and four upland community types were identified and mapped at the mitigation site (**Figure 3** in **Appendix A**). The nine wetland community types include Type 3: *Phleum/Agrostis*, Type 4: *Juncus/Carex*, Type 5: *Phalaris/Agrostis*, Type 6: *Juncus/Agrostis*, Type 7: *Carex/Juncus*, Type 9: *Salix*, Type 10: *Salix/Alnus*, Type 12: *Phalaris/Typha* and Type 13: *Ranunculus/Juncus.* The four upland community types include Type 1: *Medicago/Centaurea*, Type 2: *Phleum/Melilotus* and Type 8: *Centaurea/Carduus* and Type 11: *Bromus/Phleum.* Plant species observed within each of these communities are listed on the **COE Forms** (**Appendix B**).

Wetland types 4, 9, and 10 were present before reconstruction of the channel. Pre-construction wetland delineation mapped the majority of the site as emergent wetlands. Type 4 is a remnant wetland with heavy past alterations due to livestock grazing. Type 4 occurs in saturated to shallow water conditions. Vegetation is dominated by Baltic rush (*Juncus balticus*) and Nebraska sedge (*Carex nebrascensis*). During the 2005 monitoring, Crawe sedge (*Carex crawei*), rated S2 by the Montana Natural Heritage Program, and green-keeled cottongrass (*Eriophorum viridicarinatum*), formerly rated as S3, were identified in this type. Type 9 consists of a small

group of several mature Pacific willows found near the heads of the larger springs located near the east end of the site. Type 10 is located along the upper most reaches of the mitigation site; vegetation is dominated by Bebbs willow and thin leaved alder (*Alnus incana*) with a herbaceous layer of wetter grass species such as reed canarygrass (*Phalaris arundinacea*) and redtop (*Agrostis alba*). The remaining wetland types were created during the channel reconstruction and wetland creation. Community Type 3: *Phleum/Agrostis*, formerly located in the upstream section of the project around the shallow water fringes of the excavated wetland, was replaced by Community Type 12 during 2005. Community Type 12 is dominated by reed canarygrass, cattails and aquatic vegetation. Community Type 5 is located within the reconstructed channel and adjacent created wetland pads. Type 5 includes the vegetation along the streambanks that were lined with transplanted wetland sod from within the site. Streambank vegetation is dominated by the transplanted Baltic rush and Nebraska sedge that was removed from within Community Type 4. The streambank and adjacent wetlands were sprigged with several willow species and also planted with variety of 10T cubic inch seedlings (**Appendix G**).

The remaining area of Type 5 includes the created wetland pads dominated by reed canarygrass, dagger-leaved rush (*Juncus ensifolius*) and redtop. During the 2002 monitoring these created wetlands had minor distributions of some invasive species such as lambs quarter (*Chenopodium album*), white campion (*Lychnis alba*), spotted knapweed (*Centaurea maculosa*) and Canada thistle (*Cirsium arvense*). Observations during the 2006 season showed little evidence of these invasive species being present. It is possible that extended late season inundation and high groundwater table ultimately drowned out the invasive species and also was a more suitable water regime for the development of wetland species that now occupy these niches. The site is dominated by the aggressive reed canarygrass. The potential exists for this species to eventually dominate the entire wetland pads and ultimately decrease the high diversity of wetland grasses and forbs present on the site.

Community Type 6 is located around the fringe of excavated wetland on the lower, downstream section of the mitigation site. Vegetation surrounding the excavated wetland fringe is dominated by dagger leaf rush, redtop and nodding beggars-ticks (*Bidens cernua*). Community Type 13 was added during the 2005 monitoring. Areas considered as open water within the smaller excavated wetland were mapped as shallow water with emergent and aquatic bed vegetation types. The shallow waters are dominated by whitewater buttercup (*Ranunculus aquatilis var. hispidulus*) and other aquatic vegetation. The remaining wetland Community Type 7, which also is located exclusively within the downstream reach of the mitigation site, is dominated by Nebraska sedge and dagger leaf rush.

Extensive revegetation efforts to re-establish woody plant species were implemented during 2001 and 2002 seasons. Revegetation included planting of 10T cubic inch seedlings and sprigging of willows in community types 2, 3, 4, 5, 6, 7 and 12. Larger, more mature shrubs were transplanted along the channel banks in Community 5. Refer to **Sections 3.9** and **3.10** and **Appendix G** for specific details on revegetation.

Pasture crops and non-native grass species mainly dominate adjacent upland vegetation communities. Type 1 consists of an alfalfa field with a minor infestation of spotted knapweed. Alfalfa is still being cultivated and hayed for livestock feed. Type 2 is located within the upstream section of the mitigation project adjacent to Type 1 and excavated wetlands. This community type on the south and eastern fringes of the excavated wetlands consists of mostly upland species, but also was planted with a variety of woody-stemmed plants (**Appendix G**).

Type 8 is an upland community type located in the downstream section near the western end of the mitigation site. Type 8 is located along two cut slopes of an old rail grade that historically crossed this lower section of the mitigation site. These dry slopes are outside the saturated zone of the wetland area and are dominated by several aggressive invasive and noxious weed species. Type 8 is dominated by spotted knapweed and musk thistle (*Carduus nutans*). Type 8 populations of musk thistle continue to expand per year, and no evidence of weed control was observed within this area. The remaining upland community, Type 11, covers the majority of the upland areas. Type 11 is dominated by mostly non-native grasses used for livestock grazing. Type 11 is found on the outer fringes of the wetland corridor in both the upstream and downstream sections.

Several Category 1 Noxious weeds were observed throughout the Kleinschmidt Creek Mitigation Site. These plants include spotted knapweed, Canada thistle, hounds tongue (*Cynoglossum officinale*) and Oxeye daisy (*Chrysanthemum leucanthemum*). Other invasive or non-native species include common dandelion (*Taraxacum officinale*), lambsquarter, clasping pepper-grass (*Lepidium perfoliatum*), butter and eggs (*Linaria vulgaris*), black henbane (*Hyoscyamus niger*), musk thistle, pennycress (*Thlaspi arvense*), tall tumbleweed mustard (*Sisymbrium altissimum*) and quackgrass (*Agropyron repens*).

Vegetation transect results are detailed in the attached data forms and are graphically summarized in **Charts 1** and **2**. A tabular transect summary is presented in **Table 3**.

Table 3: ***Transect 1 data summary for 2002 – 2006.***

Monitoring Year	2002-2003	2004	2005	2006
Transect Length (feet)	222	222	222	222
# Vegetation Community Transitions along Transect	4	4	4	4
# Vegetation Communities along Transect	4	4	4	4
# Hydrophytic Vegetation Communities along Transect	3	3	3	3
Total Vegetative Species	25	23	22	22
Total Hydrophytic Species	17	17	18	17
Total Upland Species	8	6	4	5
Estimated % Total Vegetative Cover	95	95	88	86
% Transect Length Comprised of Hydrophytic Vegetation Communities	93	93	93	93
% Transect Length Comprised of Upland Vegetation Communities	7	7	7	7
% Transect Length Comprised of Unvegetated Open Water	0	0	0	0
% Transect Length Comprised of Bare Substrate	0	0	0	0

Chart 1: ***Transect maps showing vegetation types from the start of transect (0 feet) to the end of transect (222 feet) for each year monitored.***



Chart 2: ***Length of vegetation communities along Transect 1 for each year monitored.***



3.3 Soils

The soils located at the Kleinschmidt Creek site are mapped as Tetonview Loam and Perma Gravelly Loam (NRCS 2004). Tetonview Loam is listed on the Powell County Hydric Soils list and covers a majority of the mitigation site. These soils have a 0 to 4 percent slope and are classified as a stream terrace type landform with alluvial parent materials. The majority of the site was mapped as the Tetonview loam, which includes all of the upstream sections and a portion of the downstream sections. The remaining downstream section includes Perma Gravelly Loam. These soils have 8 to 15 percent slopes and are classified as an alluvial fan type landform with parent materials consisting of alluvium. Perma Gravelly loam is considered somewhat excessively drained. Soil profiles examined during monitoring visits revealed similar soil types to those mapped in this area. Wetland soils observed during monitoring and documented on the COE Routine Wetland Delineation Data Form were mostly peat, loams, or clays with very low chromas (1 or 2). Mottles were present in one profile. Soil profiles in the grass and sedge-dominated areas mostly consisted of deep A horizons of peat or mucky mineral textured materials with an underlying clay layer.

3.4 Wetland Delineation

Delineated wetland boundaries are illustrated on **Figure 3** in **Appendix A**. Completed wetland delineation forms are included in **Appendix B**. Soils, vegetation, and hydrology are discussed in preceding sections. The 1999 pre-construction wetland delineation documented 13.78 acres of wetland and 7.59 acres of over-excavated open water channel on the mitigation site (**Table 4**; **Figure 4** in **Appendix A**). Wetland conditions identified in 1999 and from 2002 to 2006 monitoring are presented in **Table4**.

Table 4: ***Wetland conditions within the Kleinschmidt Creek Wetland Mitigation Site.***

Condition	2006 (acre)	2005 (acre)	2004 (acre)	2002-2003 (acre)	Pre-Project 1999 (acre)
Gross Wetland Area	25.41	25.25	25.25	25.99	21.38
Open Water Area	2.41	2.43	2.72	2.6	7.59
Net Wetland Area	**23.00**	**22.82**	**22.53**	**23.30**	**13.78**

Approximately 23 wetland acres and 2.41 restored channel/open water acres are currently within the monitoring area (**Figure 3** in **Appendix A**). The pre-construction wetland delineation reported 13.78 wetland and 7.59 over-excavated open water channel acres. The net increase in gross wetland acres for 2006 was 23 – 13.78 = 9.22 acres, while the open water of 7.59 (degraded channel) acres decreased to 2.41 acres, consisting of restored sinuous stream channel (1.75 acres) and portions of one excavated shallow wetland (0.66 acre).

Differences between pre-and post-project net wetlands were due to the decrease in degraded channel/open-water, active restoration of wetlands, addition of two excavated shallow wetland areas that were created in upland areas, and “passive”, or incidental, wetland restoration. Incidental wetland restoration occurred outside of enhancement areas within portions of intended upland buffer areas.

3.5 Wildlife

Wildlife species and evidence of wildlife, observed on the site during the 2002 to 2006 monitoring visits are listed in **Table 5**. Specific evidence observed, as well as activity codes pertaining to birds, is provided on the completed **Monitoring Form** in **Appendix B**.

Table 5: ***2002-2006 fish and wildlife species observed at the Kleinschmidt Creek Wetland Mitigation Site.***

FISH
Westslope Cutthroat Trout (*Oncorhynchus clarki lewisi*)
Brook Trout (*Salvelinus fontinalis*)[1]
Brown Trout (*Salmo trutta linnaeus*) [1]
Bull Trout (*Salvelinus confluentus*)
Rainbow (*Oncorhynchus mykiss*)
Sculpins (*Cottus* spp.)[1]
AMPHIBIANS
Spotted Frog (*Rana luteiventris*)
REPTILES
None
BIRDS
American Dipper (*Cinclus mexicanus*)[2]
American Crow (*Corvus brachyrhynchos*)
Bald Eagle (*Haliaeetus leucocephalus*)[2]
Brewers Blackbird (*Euphagus cyanocephalus*)
Bluebird (*Sialia mexicana*)
Bufflehead (*Bucephala albeola*)[2]
Canada Goose (*Branta canadensis*)
Grasshopper Sparrow (*Ammodramus savannarum*)[2]
Killdeer (*Charadrius vociferus*)
Mallard (*Anas platyrhynchos*)
Red-tailed hawk (*Buteo jamaicensis*)
Savannah Sparrow (*Passerculus sandwichensis*)[2]
Solitary Sandpiper (*Tringa solitaria*)[2]
Sparrows (*Spizella* spp.)
Tree swallow (*Tachycineta bicolor*)
Yellow-headed blackbird (*Xanthocephalus xanthocephalus*)
MAMMALS
Coyote (*Canis latrans*)
Deer (*Odocoileus sp.*)
Elk (*Cervus elaphus*)

Bolded species were observed during 2006 monitoring.
[1] Species identified in 2006 by Montana Fish Wildlife & Parks Blackfoot Tributary Fisheries Survey.
[2] Observed by MDT in 2006.

This site provides habitat for a variety of wildlife species, although this was not necessarily reflected in the 2002 - 2006 monitoring data. Indications of one mammal, one amphibian, and two bird species were noted at the mitigation site during the 2006 site visits, with additional observations by MDT staff (**Table 5**). Deer frequent the site and occasionally the property owner has observed elk on the site. Deer are thought to be partially responsible for browse

disturbance to planted woody vegetation, although livestock broke into a portion of the site in 2004.

The newly constructed channel offers habitat for three types of fish species. These species include low numbers of brook trout, brown trout and sculpins (FWP 2006). Final survey results not yet available. The Montana Department of Fish, Wildlife and Parks conducted pre-project and post-project surveys during 1998, 2000, 2003, 2004, and 2006.

3.6 Macroinvertebrates

Complete 2006 results from the macroinvertebrate sampling locations (**Figure 2** in **Appendix A**) are presented in **Appendix F**. Two points were sampled at this mitigation site during 2006. The two 2006 sampling locations are along the creek and pond on the upstream section of the site. There was a decline in the stream bioassessment score between the years 2004 and 2006; however, the reason for this decline is not clear. In this pring-fed system, the banks and bed are extremely stable through the site (e.g., no sediment concerns), indicating that the decline may be related to an unidentified upstream water quality problem. The following macroinvertebrate analysis was provided by Rhithron Associates, Inc. (Bollman 2006).

Shallow Open Water – 2006
Bioassessment index scores remained relatively stable between 2005 and 2006, despite a loss of taxa richness. POET taxa richness was high in each year of the study. Assemblage sensitivity as measured by the biotic index value indicated good water quality at this site. A single mayfly taxon (Callibaetis sp.) was collected, but it was abundant. The dominant taxon was the amphipod Hyalella sp., which suggests that senescent macrophytes provided both habitat and an energy source for invertebrates here. Sub-optimal conditions are indicated.

Stream - 2006
Both lentic and lotic flow conditions were evident at the stream site; many taxa collected here were rheophilic. The Montana DEQ bioassessment index for Valley and Foothill Prairie streams indicates severe impairment at this site. Metric indicators of water quality gave conflicting results, although no mayfly taxa were collected, the biotic index value was low. Midges, especially Tanytarsus sp. and Orthocladius sp. dominated the sample. These taxa suggest the presence of filamentous algae.

Chart 3: ***Bioassessment scores for Kleinschmidt Creek Wetland Mitigation Site.***



3.7 Functional Assessment

Functional Assessment Forms were completed for wetlands in 2006 (**Appendix B**). The two assessment areas (AAs) evaluated at Kleinschmidt Creek were separated into channel corridor/wetlands (23.86 acres) and excavated wetlands (1.55 acres) and rated as Category II (high value) and Category III (moderate value), respectively.

The channel corridor/wetland area received moderate to high ratings for threatened and endangered (T&E) species habitat, Montana Natural Heritage Program (MTNHP) species habitat, surface water storage, production export/food chain support and groundwater discharge/recharge. The variable for T&E species habitat rated moderate due to documented secondary bull trout (*Salvelinus confluentus*) habitat in the project area (FWP 2003). The variable for MTNHP species habitat rated high due to the identification in 2005 of an S2 plant species, Crawe sedge. A formerly-listed S3 species, green-keeled cottongrass, was also noted. Also contributing to this higher rating was the presence of secondary habitat for westslope cutthroat trout (*Oncorhynchus clarki lewisi*) based on Montana Fish, Wildlife & Parks (MFWP) surveys in 2003. The surface water storage variable rated high due to the acre-feet of water contained within the channel and adjacent wetlands. The site received a high sediment/shoreline stabilization rating due to the dominant percent cover of sedges and rushes with deep binding roots along the channel. Willow sprigged along the banks will also develop into larger, more robust shrubs with extensive deep binding roots systems.

The Category III rating for excavated wetlands was primarily due to low ratings for T&E species habitat and MHNP species habitat, and uniqueness. General wildlife habitat, sediment/shoreline stabilization, sediment/nutrient removal and production export rated as moderate. Other factors contributing to this score were high ratings for surface water storage and groundwater discharge/recharge.

Based on functional assessment results (**Table 6**), approximately 212 functional units occur at the Kleinschmidt Creek mitigation site. Baseline functional assessment results are also provided in **Table 6** for general comparative purposes. However, it should be noted that direct comparison between the baseline and 2002 - 2006 functional assessments is not possible as they were completed using different versions of the MDT functional assessment methods. The baseline assessment was completed using the 1997 version, while the 2002 - 2006 assessments were conducted using the most current (1999) version. Nonetheless, functional units appear to have generally doubled at the site since construction.

3.8 Photographs

Representative photographs were taken from photo-points and transect ends (**Appendix C**).

3.9 Revegetation

Upon completion of the new channel, adjacent wetlands, and excavated wetlands, revegetation efforts were conducted to enhance riparian habitat throughout the mitigation site. Approximately 6,000 willow cuttings were sprigged and 12,800 10 cubic inch container woody shrub/tree seedlings were planted throughout the entire site in the varying mitigation work areas. Planting quantities and locations were based on a stem per acre requirement for each type of mitigation work. **Table 7** describes the type of mitigation work and stems per acre requirement.

Table 6: ***Summary of 1998 (baseline) and 2002 to 2006 wetland function/value ratings and functional points at the Kleinschmidt Creek Wetland Mitigation Project.***[1]

Function and Value Parameters from the 1999 MDT Montana Wetland Assessment Method[1]	1998 Channel & Wetlands Lower Section (MDT/USFWS[3])	1998 Channel & Wetlands Upper Section (MDT/USFWS[3])	2002 - 2003 Channel & Wetlands (LWC[3])	2002 – 2003 Ponds (LWC[3])	2004 Channel & Wetlands (LWC[3])	2004 Ponds (LWC[3])	2005 Channel & Wetlands (LWC[3])	2005 Ponds (LWC[3])	2006 Channel & Wetlands[2] (PBS&J[3])	2006 Ponds[2] (PBS&J[3])
Listed/Proposed T&E Species Habitat	Low (0.2)	Low (0.2)	Mod (0.8)	Low (0.2)	Mod (0.8)	Low (0.2)	Mod (0.8)	Low (0.5)	Mod (0.8)	Low (0.5)
MTNHP Species Habitat	Low (0.1)	Low (0.1)	Mod (0.7)	Low (0.1)	Mod (0.7)	Low (0.1)	High (1.0)	Low (0.1)	High (1.0)	Low (0.1)
General Wildlife Habitat	Mod (0.5)	Mod (0.5)	Mod (0.7)	Mod (0.7)	Mod (0.7)	Mod (0.7)	Mod (0.7)	Mod (0.7)	Mod (0.7)	Mod (0.7)
General Fish/Aquatic Habitat	Low (0.2)	Low (0.2)	Mod (0.7)	NA	Mod (0.7)	NA	Mod (0.7)	NA	Mod (0.7)	NA
Flood Attenuation	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Short and Long Term Surface Water Storage	Mod (0.5)	Mod (0.5)	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)
Sediment, Nutrient, Toxicant Removal	Mod (0.5)	High (1.0)	High (0.9)	Mod (0.7)	High (0.9)	Mod (0.7)	High (0.9)	Mod (0.7)	High (0.9)	Mod (0.7)
Sediment/Shoreline Stabilization	Mod (0.4)	Mod (0.4)	High (1.0)	Mod (0.7)	High (1.0)	Mod (0.7)	High (1.0)	Mod (0.7)	High (1.0)	Mod (0.7)
Production Export/Food Chain Support	High (0.8)	High (0.8)	High (0.8)	Mod (0.7)	High (0.8)	Mod (0.6)	High (0.8)	Mod (0.7)	High (0.8)	Mod (0.7)
Groundwater Discharge/Recharge	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)	High (1.0)
Uniqueness	Low (0.2)	Low (0.2)	Low (0.3)	Low (0.2)	Low (0.3)	Low (0.3)	Low (0.3)	Low (0.3)	Low (0.3)	Low (0.3)
Recreation/Education Potential	Low (0.1)	Low (0.1)	Low (0.3)	Low (0.3)	Low (0.3)	Low (0.3)	Low (0.3)	Low (0.3)	Low (0.3)	Low (0.3)
Actual Points/Possible Points	4.5/11	5/11	8.2/11	5.6/10	8.2/11	5.6/10	8.5/11	6.0/10	8.5/11	6.0/10
% of Possible Score Achieved	41%	45%	75%	56%	75%	56%	77%	60%	77%	60%
Overall Category	III	III	II	III	II	III	II	III	II	III
Total Acreage of Assessed Wetlands and Open Water within Easement (acre)	**10.40**	**12.90**	**24.35**	**1.64**	**23.70**	**1.55**	**23.70**	**1.55**	**23.86**	**1.55**
Functional Units (acreage x actual points) (fu)	**46.8**	**64.5**	**199.67**	**9.18**	**194.34**	**8.68**	**201.45**	**9.3**	**202.81**	**9.3**
Total Functional Units At Site (fu)	**111.30**		**208.85**		**203.02**		**210.75**		**212.11**	
Total Functional Unit "Increase"[1] (fu)	**NA**		**97.55**		**91.72**		**99.45**		**100.81**	

[1] The baseline assessment was performed using the 1997 MDT Assessment Method. Several parameters were substantially revised in the 1999 MDT Assessment Method, which was used to evaluate 2002 - 2006 monitoring conditions. Thus, direct comparison of pre- and post-project functions is not possible; although, some general trends can be noted.
[2] See completed 2006 MDT functional assessment forms **Appendix B** for further detail.
[3] Assessment completed as indicated by Montana Department of Transportation (MDT), U.S. Fish & Wildlife Service (USFWS), or Post, Buckley, Schuh, and Jernigan (PBSJ), formally Land & Water Consulting (LWC).

Table 7: ***Type of mitigation work and required stems per acre for the Kleinschmidt Creek Wetland Mitigation Site.***

Type of Mitigation Work	Planting Area	Required Stems per Acre for Credit[1]
Restoration	Channel, streambank, and wetland pads	500
Creation	Fringes around shallow open water	500[2]
High-intensity enhancement	Emergent wetlands	1,000
Low-intensity enhancement	Emergent wetlands	500

[1] As presented in LWC (2001) and confirmed in Steinle (2001); [2] Not specifically stated as success criterion in LWC (2001).

Twelve species were planted at this mitigation site (**Table 8**). Species selection was based on observation of similar wetlands in the Ovando area and species historically known to occur in this region. Refer to **Appendix G** for a list of species and their associated quantities.

Table 8: ***Planted species at Kleinschmidt Creek Wetland Mitigation Site.***

Common Name	Scientific Name
aspen	*Populus tremuloides*
alder	*Alnus incana*
black cottonwood	*Populus trichocarpa*
dogwood	*Cornus stolonifera*
bog birch	*Betula glandulosa*
Booths willow	*Salix boothii*
yellow willow	*Salix lutea*
Geyer willow	*Salix geyeriana*
Bebb willow	*Salix bebbiana*
Drummonds willow	*Salix drummondiana*
hawthorn	*Crataegus douglasii*
woods rose	*Rosa woodsii*

3.10 Woody Species Survival and Performance Success

Results from the belt transects were calculated using extrapolated stem densities. The results from the belt transect evaluations for each mitigation type are presented in **Table 9**. The "percent of 1 acre" figures listed in **Table 9** are based on a combined total for all transects walked for each mitigation type. **Table 9** also lists the area sampled (square feet) for each type and the total number of actual stems counted within the transects. Individual species survival is not listed; counts are based on the number of live stems present within each mitigation type.

Table 9: ***Stem density count for each mitigation type for the Kleinschmidt Creek Wetland Mitigation Site.***

Year	Creation (perimeter)			Restoration (throughout)			High Intensity Enhancement (throughout)			Low Intensity Enhancement (throughout)		
	Sq. Ft.	% of Acre	# of Stems	Sq. Ft.	% of Acre	# of Stems	Sq. Ft.	% of Acre	# of Stems	Sq. Ft.	% of Acre	# of Stems
2006	3,396	8	109	6,395	15	212	3,168	7	153	1,040	2	46
2005	2,495	6	108	3,614	8	256	3,218	7	254	426	1	21
2004	2,610	6	173	4,396	10	343	4,623	10.61	221	0	0	0
2002-2003	1,554	3.57	58	5,900	13.55	311	6,079	13.95	354	792	1.82	48

During 2003, a small number of transects were evaluated in the low intensity area due to lack of available woody vegetation to evaluate. These areas had been planted during the initial revegetation efforts, but were later disturbed by intensive livestock grazing. During the 2004 monitoring, no woody plants were observed in this low intensity area, and the results represent these findings. During the 2006 monitoring a few woody plants were located. The low intensity site still lacks significant amounts of woody plants, except for a few larger transplanted shrubs.

Ultimately, the cover of woody species throughout the site can be estimated based on transect data. **Table 10** lists the estimated number of stems per acre based purely on the extrapolation of sampled transect count data to the larger treatment areas. These figures likely over-estimate stem density as planting locations and densities were often concentrated (clumped), rather than uniformly distributed across the various treatment areas. Woody plantings were distributed in clumps of varying size, and in some instances were planted at a higher density in locations that were more accessible. Areas such as the restored pads were covered with an even distribution of clump plantings across the entire area. Plantings in the high intensity enhancement areas were more sporadic and concentrated in locations with bare ground or areas with scalped sod.

Preliminary results for 2006 show a decreased stem density for all the mitigation areas, except the low intensity zones. Stem density numbers varied between monitoring years for several reasons, including variability in transect locations and increased sampling area for the creation, restoration and low intensity zones.

Table 10: ***Extrapolated woody stem densities for each mitigation zone at the Kleinschmidt Wetland Mitigation Site.***

Mitigation Zone	2003 Estimated Density Per Acre	2004 Estimated Density Per Acre	2005 Estimated Density Per Acre	2006 Estimated Density Per Acre	Target Stem Density Per Acre
Creation	1,625	2,883	1,800	1,363	500 (along perimeter)
Restoration	2,295	3,430	3,200	1,413	500 (throughout)
High Intensity Enhancement	2,537	2,083	3,629	2,185	1,000 (throughout)
Low Intensity Enhancement	2,637	0	2,100	2,300	500 (throughout)

Current methods for stem density calculation are likely over-estimating actual stem densities at the site. However, as these estimates are currently three times greater than the performance requirements in creation and restoration areas and two times greater than the performance requirement in the high-intensity enhancement areas, the 2006 stem densities are likely still meeting the target density agreed to by the Army Corps of Engineers (LWC 2001) for all categories except low intensity enhancement. The estimated stem count for the low-intensity area is likely exaggerated. Woody stems counted in this area were recorded from a single location that most likely received less grazing pressure than the other areas of the low-intensity enhancement area.

3.11 Maintenance Needs/Recommendations

Although the landowner treated weeds near upper excavated shallow open water area and other areas in 2004, several noxious weeds are present including Canada thistle, hounds tongue, oxeye daisy and spotted knapweed, which should be controlled. The continued spread of noxious weeds within the dry portion of upland areas within the mitigation area was recorded with an increase in knapweed along the lower section of the project in Community Type 11.

To achieve credit in the low intensity sections, the areas impacted by livestock grazing should be revegetated with woody plants. Areas outside the perimeter of the excavated wetlands, which are currently dominated by mostly invasive species, could be treated via mechanical and cultural weed control activities to control invasive species. These include mowing or hand whipping of taller weed species and seeding of bare ground with an appropriate mix suited for the hydrological regime. Mechanical weed control would be recommended due to the woody vegetation already installed in this area. Areas where aggressive reed canarygrass is encroaching on planted woody species could be mechanically controlled to limit disturbance to plantings. Heavy browse from local wildlife has been observed across the entire site. Control measures such as chemical browse repellants should be considered to avoid further browse damage or eventual mortality to shrub and tree species.

A new jackleg fence was installed at the site in 2004. Bird boxes installed by MDT at the site were in good condition.

3.12 Current Credit Summary

As of 2006, approximately 23 acres of wetland and 2.41 acres of open water (restored stream channel/portions of excavated wetlands) occur at the Kleinschmidt Creek mitigation site. This represents an approximate increase of 9.22 wetland acres and a 5.18-acre decrease of over-excavated, straightened open water channel as compared to baseline conditions. Open water on the site is currently comprised of 1.75 acres of restored sinuous channel and 0.66 acre of excavated shallow water as a component of wetland creation. Functional units at the site have essentially doubled to over 212 since project construction.

Table 11 summarizes the maximum credit that could be assigned to the site as of 2006. Target mitigation credit ratios and acres were agreed upon prior to site construction, with the exception of incidental wetland restoration within proposed upland buffer areas, for which no performance standards or ratios were discussed. As these areas are restoring naturally within the easement, a 1:1 credit ratio was assumed.

Table 11: ***Maximum 2006 credit for the Kleinschmidt Creek Wetland Mitigation Site.***

Mitigation Type	Current Acres	Ratio	Current Maximum Credit Acres	Target Credit Acres	Comments
Designed Restoration	6.0	1:1	6.0	6.0	Does not include 1.75 acres of open water stream channel. Extrapolated stem density (1,413) is exceeding performance standard (500).
Designed Creation	1.19	1:1	1.19	1.19	Includes 0.66 acre of designed shallow open water. Extrapolated stem density along upland / wetland border (1,363) is exceeding assumed performance standard (500).
Designed High-Intensity Enhancement	8.05	1:2	4.02	4.02	Extrapolated stem density (2,185) is exceeding performance standard (1,000)
Designed Low-Intensity Enhancement	3.43	1:3	0.0	1.14	Plantings were destroyed by grazing. Actual stem density (46) is not meeting performance standard (500). No credit likely at this time. Recommend re-planting this area if credit is desired.
Incidental Restoration	4.99	1:1	4.99	0.0	4.99 acres of intended 12.69-acre upland buffer within easement reverted to emergent wetland. 1:1 ratio is assumed and has not been verified with the Corps of Engineers.
Designed Upland Buffer	7.7	4:1	1.93	3.17	4.99 acres of intended 12.69-acre upland buffer reverted to wetland.
Grand Total	**31.36**	**--**	**18.13**	**15.52**	**117% of goal**

4.0 REFERENCES

Berglund, J. 1999. *MDT Montana Wetland Assessment Method*. May 25th. Prepared for Montana Department of Transportation and Morrison-Maierle, Inc., Helena, MT. Prepared by Western EcoTech. Helena, Montana. 18 pp.

Bollman, W. 2006. MDT Mitigated Wetland Monitoring Project – Aquatic Invertebrate Monitoring Summary 2001-2006. Rhithron Associates Inc. Missoula, MT.

Carlson, J. 2001. Program Zoologist, Montana Natural Heritage Program, Helena, MT. Conversation in April.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deepwater habitats of the United States. FWS/OBS-79/31. US Fish and Wildlife Service. Washington, D.C.

Environmental Laboratory. 1987. *Corps of Engineers Wetlands Delineation Manual*. US Army Corps of Engineers. Washington, DC.

Hitchcock, C. and A. Cronquist. 1973. Flora of the Pacific Northwest. University of Washington Press. Seattle. 730p.

Land and Water Consulting, Inc. (LWC). 2001. Performance Standards and Proposed Wetland Credits for Kleinschmidt Creek Mitigation Project. Missoula, Montana.

Montana Department of Fish Wildlife and Parks (MFWP). 2003. Kleinschmidt Creek Fish Survey.

Montana Department of Natural Resources and Conservation (DNRC). 1999. North Fork Blackfoot River Hydrologic Analysis. Helena, Montana.

Natural Resources Conservation Service (NRCS). 1998. *Field Indicators of Hydric Soils in the United States*, Version 4. G. Hurt, P. Whited and R. Pringle (eds.). USDA, NRCS, Fort Worth, TX.

Natural Resources Conservation Service (NRCS). 2004. *Powell County Soil Survey, Montana.* Downloaded from internet 2/15/2004. http://www.nris.state.mt.us/nrcs/soils/datapage.html

Ralph, C.J., Geupel, G.R., Pyle, P., Martin, T.E., and D.F. DeSante. 1993. *Handbook of field methods for monitoring landbirds*. Gen. Tech. Rep. PSW-GTR-144. Albany, CA: Pacific Southwest Research Station, Forest Service, U.S. Dept. of Agriculture. 41 p.

Steinle, A. 2001. Letter to Paul Callahan, Land & Water Consulting, Inc., Missoula, MT to Allen Steinle, U.S. Army Corps of Engineers, Helena Regulatory Office, Helena, MT. October 30th. Letter addresses crediting and performance criteria at the Kleinschmidt Creek mitigation site.

Urban, L. 2001. Wetland Mitigation Specialist, Montana Department of Transportation. March meeting. Helena, Montana.

Urban, L. 2002. Wetland Mitigation Specialist, Montana Department of Transportation. January meeting. Helena, Montana.

Appendix A

FIGURES 2, 3, 4, & 5

MDT Wetland Mitigation Monitoring
Kleinschmidt Creek
Montana

Figure 2 - 2006 Monitoring Activity Locations



PROJECT NAME
MDT Kleinschmidt Creek Wetland Mitigation
DRAWING TITLE
2006 Monitoring Activity Locations

DRAWN: LL
PROJ MGR: JB
CHECKED:
APPVD:
PROJ NO: B43054.112
LOCATION:
SCALE: 1"=200'
FILE NAME: L:\330054.112\Kleinschmidt\dwg\MDT2006redo.dwg

PBSJ
1120 Cedar
Missoula, MT 59802

FIGURE
2 OF
REV -
Dec/20/2006

Figure 3 - 2006 Mapped Site Features

Vegetation Community Types:

1. Medicago/Centaurea
2. Phleum/Melilotus
3. Phleum/Agrostis
4. Juncus/Carex
5. Phalaris/Agrostis
6. Juncus/Agrostis
7. Carex/Juncus
8. Centaurea/Carduus
9. Salix
10. Salix/Alnus
11. Bromus/Phleum
12. Phalarus/Typha
13. Ranunculus/Juncus

LEGEND:

- Easement Area Limits
- Monitoring Area Limits (where different from easement)
- Wetland Limits
- Open Water Limits
- Vegetation Community Limits

Base Photograph Date: July 14, 2006

Wetland Areas: No Change	
Gross Wetland	25.41 Acres
Creek Open Water	1.75 Acres
Pond Open Water	0.66 Acres
Net Wetland	23.00 Acres

EASEMENT AREA LIMITS

MONITORING AREA LIMITS

OW

SEE LOWER RIGHT

SCALE 1"= 200ft

MONITORING AREA LIMITS

SEE UPPER LEFT

BARN

SCALE 1"= 200ft

PROJECT NAME
MDT Kleinschmidt Creek Wetland Mitigation

DRAWING TITLE
2006 Mapped Site Features

PROJ NO:	B43054.112
LOCATION:	
SCALE:	1"=200'
FILE NAME:	L:\3300\54.112\Kleinschmidt\dwg\MDT2006redc.dwg
DRAWN:	LL
PROJ MGR:	J.Berglund
CHECKED:	GH
APPVD:	JB

PBSJ
1120 Cedar
Missoula, MT 59802

FIGURE 3 OF 3

REV -

Dec/20/2006

Figure 4 Pre-Developed Wetlands



PROJECT NAME: MDT Kleinschmidt Creek Wetland Mitigation
DRAWING TITLE: Pre-Developed Wetlands

PROJ NO. 330654.18
FILE NAME: MDT2006ESE
SCALE: NOTED
LOCATION:
DRAWN: RA
CHECKED: JB
APPVD: GH
PROJ MGR: JB

LAND & WATER CONSULTING, INC.
P.O. BOX 8254
Missoula, MT 59807

FIGURE F4
REV: -
DATE: 6-24-0

Figure 5- Channel Cross Sections



CROSS SECTION 1



CROSS SECTION 2



CROSS SECTION 3

Existing Surface 1-08-02
Existing Surface 12-01-06



CROSS SECTION 4



CROSS SECTION 5

PROJECT NAME: MDT Kleinschmidt Creek Wetland Mitigation
DRAWING TITLE: Channel Cross Sections
DRAWN: RAA
PROJ MGR: JB
CHECKED:
APP'D:
PROJ NO: B43054.112
LOCATION:
SCALE: 1"=25ft
FILE NAME: L:\3300054.112\Kleinschmidt\dwg\MDT2006.dwg
A division of PBS
LAND & WATER CONSULTING
P.O. BOX 8254
Missoula, MT 59807
FIGURE
5
OF
REV -
Dec/08/2006

Appendix B

2006 WETLAND MITIGATION SITE MONITORING FORM
2006 BIRD SURVEY FORM
2006 COE WETLAND DELINEATION FORMS
2006 FUNCTIONAL ASSESSMENT FORM

MDT Wetland Mitigation Monitoring
Kleinschmidt Creek
Montana

LWC / MDT WETLAND MITIGATION SITE MONITORING FORM

Project Name: Kleinschmidt Creek Project Number: 33054.00 0112 Assessment Date: 8/16/06
Location: SE. of Ovando MDT District: Upper Clark Fork Milepost:__
Legal description: T 14 N R 11 W Section 5 & 8 Time of Day: Morning to Afternoon
Weather Conditions: overcast Person(s) conducting the assessment: G. Howard
Initial Evaluation Date: 9/03/02 Visit #: 5 Monitoring Year: 5
Size of evaluation area: 36 acres Land use surrounding wetland: Agriculture

HYDROLOGY

Surface Water Source: Hydrology source is spring feed, perennial Kleinschmidt Creek.
Inundation**:** Present x Absent____ Average depths: 2.5 ft Range of depths: 0-5 ft
Assessment area under inundation: 30 %
Depth at emergent vegetation-open water boundary: 0.6 ft (excavated wetlands)
If assessment area is not inundated are the soils saturated w/in 12" of surface**:** Yes x No
Other evidence of hydrology on site (drift lines, erosion, stained vegetation etc.): Large area of saturated wet-meadow for later part of summer months. Hydrology influenced by groundwater.

Groundwater
Monitoring wells: Present_____ Absent x
Record depth of water below ground surface

Well #	Depth	Well #	Depth	Well #	Depth

Additional Activities Checklist:
x Map emergent vegetation-open water boundary on air photo
x Observe extent of surface water during each site visit and look for evidence of past surface water elevations (drift lines, erosion, vegetation staining etc.)
___GPS survey groundwater monitoring wells locations if present

COMMENTS/PROBLEMS: Similar site conditions observed during 2005 mid-summer visit. Inundation presents at both the created pads and excavated wetlands. The lower sections of the project have several large populations of noxious weeds including spotted knapweed, Canada thistle, musk thistle and oxeye daisy. The upper section has an increase in Canada thistle. One new species identified during 2006 monitoring, refer to vegetation list.

VEGETATION COMMUNITIES

Community No.: 1 Community Title (main species): Medicago/Centaurea

Dominant Species	% Cover	Dominant Species	% Cover
Medicago sativa	60		
Centaurea maculosa	10		
Phleum pretense	10		

COMMENTS/PROBLEMS: Upland area adjacent to created pond # 2, vegetation dominated by mainly alfalfa, timothy and spotted knapweed. Transect # 1 begins at the boundary between the upland field and created wetland slopes.

Community No.: 2 Community Title (main species): Phleum/Melilotus

Dominant Species	% Cover	Dominant Species	% Cover
Phleum pratense	30	Plantings	P
Centaurea maculosa	P	*Poa pratensis*	T
Carduus nutans	T	*Trifolium spp.*	P
Melilotus officinalis	30	*Phalaris arundinacea*	T
Chrysanthemum leucanthemum	10	*Cirsium arvense*	P
Linaria vulgare	T	*Agropyron smithii*	P

COMMENTS/PROBLEMS: Slopes adjacent to pond # 2. Area mostly dominated by *Phleum pratense* and *Melilotus officinalis*. The remaining species are mostly invasive and include several state listed noxious weeds such as *Centaurea maculosa*, *Cirsium arvense* and *Chrysanthemum leucanthemum*. Native grasses seeded during construction have established a minor presence.

Community No.: 3 Community Title (main species): Phleum/Agrostis

Dominant Species	% Cover	Dominant Species	% Cover
Phalaris arundinacea	10		
Phleum pratense	10		
Agrostis alba	10		

COMMENTS/PROBLEMS: Emergent vegetation growing along the west side of excavated wetland. Transect # 1 bisects the west side of excavated wetland. During the 2005 mapping CT# 3 was changed to CT # 12 and removed from the Figure 3.

VEGETATION COMMUNITIES (continued)

Community No.: 4 Community Title (main species): Juncus/Carex

Dominant Species	% Cover	Dominant Species	% Cover
Juncus balticus	30	*Solidago missouriensis*	T
Carex nebrascensis	20	*Trifolium spp.*	P
Agrostis alba	10	*Phleum pratense*	10
Phalaris arundinacea	10	*Epilobium ciliatum*	P
Glyceria elata	P	*Carex utriculata*	P

COMMENTS/PROBLEMS: Wet meadow dominated by wetland grass species. Areas located along outer edges of constructed wetland pads along creek.

Community No.: 5 Community Title (main species): Phalaris/Agrostis

Dominant Species	% Cover	Dominant Species	% Cover
Phalaris arundinacea	50	*Carex nebrascensis*	10
Juncus ensifolius	10	*Epilobium ciliatum*	P
Agrostis alba	30	*Typha latifolia*	T
Deschampsia cespitosa	P	*Carex utriculata*	P
Mimulus guttatus	P	*Plantings*	T
Carex lanuginosa	P		

COMMENTS/PROBLEMS: Wetlands adjacent to creek. Areas inundated during monitoring visit.

Community No.: 6 Community Title (main species): Juncus/Agrostis

Dominant Species	% Cover	Dominant Species	% Cover
Phalaris arundinacea	20	*Agropyron repens*	P
Trifolium pratense	10	*Bidens cernua*	20
Agrostis alba	20	*Juncus ensifolius*	30
Typha latifolia	P		
Melilotus officinalis	P		

COMMENTS/PROBLEMS: Excavated wetland located on the lower section of Kleinschmidt Creek project area. Emergent type vegetation dominates excavated wetland and fringes. During the 2005 mapping CT # 13 was added in place of the shallow open water category.

VEGETATION COMMUNITIES (continued)

Community No.: 7 Community Title (main species): Carex/Juncus

Dominant Species	% Cover	Dominant Species	% Cover
Juncus ensifolius	20	*Potentilla anserina*	T
Agrostis alba	10		
Carex nebrascensis	40		
Cirsium arvense	T		
Poa pratensis	10		

COMMENTS/PROBLEMS: Area of emergent vegetation located below house and barn on lower section. Area heavily grazed in past.

Community No.: 8 Community Title (main species): Centaurea/Carduus

Dominant Species	% Cover	Dominant Species	% Cover
Carduus nutans	40	*Bromus inermis*	P
Hyoscyamus niger	P	*Cirsium arvense*	10
Centaurea maculosa	20	*Cynoglossum officinale*	P
Agropyron repens	P	*Linaria vulgare*	P
Medicago sativa	T	*Agropyron cristatum*	T

COMMENTS/PROBLEMS: Area near the bottom of the lowest section adjacent to old railroad grade. Upland area dominated by invasive species; *Carduus nutans, Centaurea maculosa* and *Cirsium arvense*.

Community No.: 9 Community Title (main species): Salix

Dominant Species	% Cover	Dominant Species	% Cover
Salix lasiandra	70		
Phleum pratense	10		
Bromus inermis	10		

COMMENTS/PROBLEMS: Small group of several mature pacific willows located near springs.

Community No.: 10 Community Title (main species): Salix/Alnus

Dominant Species	% Cover	Dominant Species	% Cover
Salix bebbiana	30		
Alnus incana	10		
Phalaris arundinacea	30		
Agrostis alba	20		

COMMENTS/PROBLEMS: Small group of several Bebbs willow and alder located near the beginning of the upstream section. Understory dominated by herbaceous species.

Community No.: 11 Community Title (main species): Bromus/Phleum

Dominant Species	% Cover	Dominant Species	% Cover
Agropyron repens	20	*Centaurea maculosa*	30
Phleum pratense	10		
Bromus inermis	20		
Sisymbrium altissimum	P		
Potentilla fruticosa	10		

COMMENTS/PROBLEMS: Upland areas dominated by grass species. Increase in noxious weed cover values recorded during 2006 monitoring.

Community No.: 12 Community Title (main species): Phalaris/Typha

Dominant Species	% Cover	Dominant Species	% Cover
Phalaris arundinacea	30	Aquatic vegetation	20
Phleum pratense	P	*Juncus ensifolius*	P
Agrostis alba	20	*Carex lanuginosa*	T
Typha latifolia	20		
Eleocharis palustris	P		

COMMENTS/PROBLEMS: Emergent vegetation growing along the west side of excavated wetland. Transect # 1 bisects the west side of excavated wetland. Some areas mapped as OW in 2004 are now considered as emergent and aquatic bed vegetation types.

Community No.: 13 Community Title (main species): Ranunculus/Juncus

Dominant Species	% Cover	Dominant Species	% Cover
Phalaris arundinacea	20	*Carex lanuginosa*	P
Trifolium pratense	P	*Bidens cernua*	10
Agrostis alba	30	*Juncus ensifolius*	30
Typha latifolia	P	*Ranunculus aquatilis var. hispidulus*	70
Melilotus officinalis	T	*Carex nebrascensis*	P
Sagittaria latifolia	P		

COMMENTS/PROBLEMS: Excavated wetland located on the lower section of Kleinschmidt Creek project area. Emergent and aquatic type vegetation dominates wetland and fringes. Increase in aquatic vegetation cover value. New species identified within this area including broadleaf arrowhead (*Sagittaria latifolia*).

Community No.: Community Title (main species):

Dominant Species	% Cover	Dominant Species	% Cover

COMMENTS/PROBLEMS:

COMPREHENSIVE VEGETATION LIST

Species	Vegetation Community Number(s)	Species	Vegetation Community Number(s)
Achillea millefolium	2,11	*Juncus balticus*	4
Agrostis alba	3,4,5,6,7,10,11	*Juncus ensifolius*	5,6,7
Agrostis exarata	5	*Juncus mertensianus*	4,5,6,7
Agropyron cristatum	8	*Juncus nodosus*	4,5,7
Agropyron repens	6,8	*Linaria vulgaris*	4
Agropyron smithii	5	*Lychnis alba*	5
Allium brevistylum	4,5,7	*Medicago sativa*	1
Alnus incana	10	*Melilotus officinalis*	2,6,8
Beckmannia syzigachne	5	*Mentha arvensis*	4,5
Betula glandulosa	5,7	*Mimulus guttatus*	5
Bidens cernua	5	*Najas flexilis*	12, 13
Bromus inermis	8,9,11	*Pedicularis groenlandica*	4,5,7
Bromus tectorum	1	*Phalaris arundinacea*	2,3,4,5,6,10
Calamagrostis canadensis	4,5	*Phleum pratense*	1,2,3,4,9,11
Carduus nutans	2,8	*Plantago spp.*	5
Carex aquatilis	4,7	*Poa pratensis*	2,7
Carex crawei	4,7	*Polygonum amphibium*	5,6
Carex flava	4,5,7	*Potentilla anserina*	7
Carex lanuginosa	4,5,7	*Potentilla fruticosa*	4
Carex nebrascensis	4,5,7	*Ranunculus spp.*	5
Carex utriculata	4,5	*Ranunculus aquatilis var. hispidulus*	6
Carex simulata	4,5,7	*Rumex crispus*	2,5,7
Centaurea maculosa	1,2,8	*Sagittaria latifolia*	13
Chenopodium album	5	*Salix bebbiana*	4,5,7,10
Chrysanthemum leucanthemum	2	*Salix boothii*	2,3,4,5,6,7
Cirsium arvense	7	*Salix drummondiana*	2,3,4,5,6,7
Cynoglossum officinale	8	*Salix geyeriana*	2,3,4,5,6,7
Deschampsia cespitosa	5	*Salix lasiandra*	9
Eleocharis palustris	4,5,6,7	*Scirpus acutus*	12,13
Epilobium ciliatum	4,5	*Sisymbrium altissimum*	11
Equisetum arvense	3,4,5,6,7	*Sisyrinchium angustifolium*	4,5,7
Equisetum hyemale	5	*Solidago missouriensis*	4
Eriophorum viridicarinatum	4,7	*Taraxacum officinale*	1,2,4,5,7,11
Geum macrophyllum	4,5,7	*Thlaspi arvense*	1,2,4,5,7,11
Glyceria elata	4	*Triglochin maritimum*	4,5
Glyceria striata	4,5,7	*Trifolium pratense*	2,4,6
Habenaria dilatata	4,5	*Typha latifolia*	5,6
Hyoscyamus niger	8	*Veronica americana*	5,6,7

COMMENTS/PROBLEMS: One new plant was identified in 2006: broadleaf arrowhead (*Sagittaria latifolia).*

PLANTED WOODY VEGETATION SURVIVAL

Pond #	Species	Number Originally Planted	Number Observed	Mortality Causes

COMMENTS/PROBLEMS: Due to the large number of woody plants installed at this mitigation site only stem density was counted. Survival for each species was not calculated. Refer to the revegetation section of report (Section 3.9) for survival data and summaries.

WILDLIFE

BIRDS

(Attach Bird Survey Field Forms)

Were man made nesting structures installed? Yes x No___Type: Boxes How many? 12 Are the nesting structures being utilized? Yes x No____ Do the nesting structures need repairs? Yes___ No x

MAMMALS AND HERPTILES

Species	Number Observed	Indirect indication of use			
		Tracks	Scat	Burrows	Other
Deer		X	X		
Coyote			X		
Elk					X
Spotted Frog	1				
Striped Skunk	1				

Additional Activities Checklist:

__X_ Macroinvertebrate sampling (if required)

COMMENTS/PROBLEMS: Macroinvertebrates sample were collected at two locations. These include the creek and pond along upper section during 2006.

PHOTOGRAPHS

Using a camera with a 50 mm lenses and color film take photographs of the following permanent reference points listed in the checklist below. Record the direction of the photograph using a compass. (The first time at each site establish a permanent reference point by setting a ½ inch rebar or fencepost extending 2-3' above ground, survey the location with a resource grade GPS and mark the location on the air photo.)
Checklist:

_X_ One photo for each of the 4 cardinal directions surrounding wetland
_X_ At least one photo showing upland use surrounding wetland – if more than one upland use exists, take additional photos
_X_ At least one photo showing buffer surrounding wetland
_X_ One photo from each end of vegetation transect showing transect

Location	Photo Frame #	Photograph Description	Compass Reading
1	1	Looking north along transect.	0 ^{o}
1	2	Looking west across upland pasture.	270 ^{o}
2	3	Looking east across pond.	90 ^{o}
2	4	Looking south at transect	180 ^{o}
3	5-9	Panoramic looking west to east, upper section of site.	270 ^{o} - 90 ^{o}
4	10	Looking north along end of transect.	0 ^{o}
5	11	Panoramic looking south at transect end.	180 ^{o}
6	12-13	Looking west across upper end of site	270 ^{o}
7	14	Looking northwest across created wetland pond on lower section.	270 ^{o}
8	15	Looking northwest along channel.	270 ^{o}
9	16	Looking southeast along channel.	135 ^{o}
9	17	Looking northwest along channel.	315 ^{o}
10	18-19	Looking northwest upland areas.	315 ^{o}
11	20-21	Looking northwest at emergent wetlands and channel.	315 ^{o}
11	22-23	Looking southeast along channel.	135 ^{o}

COMMENTS/PROBLEMS:

_____
_____
_____
_____

GPS SURVEYING

Using a resource grade GPS survey the items on the checklist below. Collect at least 3 location points with the GPS unit set at 5 second recording rate. Record file numbers fore site in designated GPS field notebook

Checklist:

_x_ Jurisdictional wetland boundary
_x_ 4-6 landmarks recognizable on the air photo
_x_ Start and end points of vegetation transect(s)
_x_ Photo reference points
___ Groundwater monitoring well locations

COMMENTS/PROBLEMS:

_____
_____

WETLAND DELINEATION

(Attach Corps of Engineers delineation forms)

At each site conduct the items on the checklist below:
_x_ Delineate wetlands according to the 1987 Army Corps manual.
_x_ Delineate wetland-upland boundary on the air photo
___ Survey wetland-upland boundary with a resource grade GPS survey

COMMENTS/PROBLEMS: _____

FUNCTIONAL ASSESSMENT

(Complete and attach full MDT Montana Wetland Assessment Method field forms; also attach abbreviated field forms, if used)

COMMENTS/PROBLEMS:

MAINTENANCE

Were man-made nesting structures installed at this site? YES _x_ NO____
If yes, do they need to be repaired? YES____ NO_x_
If yes, describe problems below and indicate if any actions were taken to remedy the problems.

Were man-made structures build or installed to impound water or control water flow into or out of the wetland? YES____ NO _x_
If yes, are the structures working properly and in good working order? YES____ NO___
If no, describe the problems below.

COMMENTS/PROBLEMS: _____

MDT WETLAND MONITORING – VEGETATION TRANSECT

Site: Kleinschmidt Creek Date: 8/16/06 Examiner: G. Howard Transect # 1

Approx. transect length: 222ft. Compass Direction from Start (Upland): 0°

Vegetation type 1:	Medicago/Centaurea	
Length of transect in this type:	15	feet
Species:		Cover:
Phleum pratense		40
Poa pratensis		20
Agropyron repens		P
Agrostis alba		P
Phalaris arundinacea		P
Medicago sativa		P
Alnus incana (Planted)		T
Centaurea maculosa		T
Total Vegetative Cover:		80%

Vegetation type 2:	Phalaris/Typha	
Length of transect in this type:	57	feet
Species:		Cover:
Phleum pratense		P
Agrostis alba		10
Typha latifolia		20
Epilobium ciliatum		T
Juncus ensifolius		P
Salix boothii (Planted)		P
Phalaris arundinacea		30
Eleocharis palustris		P
Alnus incana (Planted)		T
Salix geyeriana (Sprigged)		T
Total Vegetative Cover:		70%

Vegetation type 3:	Juncus/Carex	
Length of transect in this type:	60	feet
Species:		Cover:
Phalaris arundinacea		30
Juncus balticus		30
Poa pratensis		P
Carex nebrascensis		20
Triglochin maritimum		T
Juncus ensifolius		P
Equisetum hyemale		T
Phleum pratense		P
Agrostis alba		10
Carex utriculata		P
Total Vegetative Cover:		95%

Vegetation type 4:	Phalaris/Agrostis	
Length of transect in this type:	90	feet
Species:		Cover:
Phalaris arundinacea		30
Agrostis alba		40
Phleum pratense		P
Beckmannia syzigachne		T
Plantings		P
Carex nebrascensis		P
Deschampsia cespitosa		T
Juncus ensifolius		20
Carex lanuginosa		P
Carex utriculata		10
Total Vegetative Cover:		100%

MDT WETLAND MONITORING – VEGETATION TRANSECT (back of form)

Cover Estimate		**Indicator Class:**	**Source:**
+ = <1%	3 = 11-20%	+ = Obligate	P = Planted
1 = 1-5%	4 = 21-50%	- = Facultative/Wet	V = Volunteer
2 = 6-10%	5 = >50%	0 = Facultative	

Percent of perimeter _____ % developing wetland vegetation – excluding dam/berm structures.

Establish transects perpendicular to the shoreline (or saturated perimeter). The transect should begin in the upland area. Permanently mark this location with a standard metal fencepost. Extend the imaginary transect line towards the center of the wetland, ending at the 3 food depth (in open water), or at a point where water depths or saturation are maximized. Mark this location with another metal fencepost.

Estimate cover within a 10 ft wide "belt" along the transect length. At a minimum, establish a transect at the windward and leeward sides of the wetland. Remember that the purpose of this sampling is to monitor, not inventory, representative portions of the wetland site.

Notes:

3

BIRD SURVEY – FIELD DATA SHEET

Page__1_of_1__
Date: 8/16/06

SITE: Kleinschmidt Creek

Survey Time: 9:00-4:00

Bird Species	#	Behavior	Habitat	Bird Species	#	Behavior	Habitat
Mallard	1	F	OW				
Yellow-headed blackbird	2	L	WM				

Notes:

Behavior: BP – one of a breeding pair; BD – breeding display; F – foraging; FO – flyover; L – loafing; N – nesting

Habitat: AB – aquatic bed; FO – forested; I – island; MA – marsh; MF – mud flat; OW – open water; SS – scrub/shrub; UP – upland buffer; WM – wet meadow, US – unconsolidated shoreline

DATA FORM

ROUTINE WETLAND DETERMINATION

(1987 COE Wetlands Delineation Manual)

Project/Site: Kleinschmidt Creek	Date: 08/16/06
Applicant/Owner: MDT	County: Powell
Investigator: Greg Howard	State: MT

Do Normal Circumstances exist on the site:	x	Yes	____	No
Is the site significantly disturbed (Atypical Situation)?	____	Yes	____	No
Is the area a potential Problem Area?	____	Yes	____	No
(If needed, explain on reverse.)				

Community ID: Upland
Transect ID: 1
Plot ID: 1

VEGETATION

	Dominant Plant Species	Stratum	Indicator		Dominant Plant Species	Stratum	Indicator
1	*Phleum pratense*	H	FACU	9			
2	*Medicago sativa*	H	--	10			
3	*Centaurea maculosa*	H	--	11			
4	*Agropyron repens*	H	FACU	12			
5	*Agrostis alba*	H	FAC+	13			
6	*Poa pratensis*	H	FACU+	14			
7				15			
8				16			

Percent of Dominant Species that are OBL, FACW, or FAC (excluding FAC-). 1/6 = 17%

Area dominated by upland vegetation.

HYDROLOGY

____ Recorded Data (Describe in Remarks):
- ____ Stream, Lake, or Tide Gauge
- ____ Aerial Photographs
- ____ Other

X No Recorded Data Available

Field Observations:

Depth of Surface Water: ____ - ____ (in.)

Depth to Free Water in Pit: ____ - ____ (in.)

Depth to Saturated Soil: ____ - ____ (in.)

Wetland Hydrology Indicators:

Primary Indicators:
- ____ Inundated
- ____ Saturated in Upper 12 Inches
- ____ Water Marks
- ____ Drift Lines
- ____ Sediment Deposits
- ____ Drainage Patterns in Wetlands

Secondary Indicators (2 or more required):
- ____ Oxidized Root Channels in Upper 12 Inches
- ____ Water-Stained Leaves
- ____ Local Soil Survey Data
- ____ FAC-Neutral Test
- ____ Other (Explain in Remarks)

Remarks:
No hydrology indicators present.

SOILS

Map Unit Name (Series and Phase): Tetonview Loam
Drainage Class: Poorly-drained
Taxonomy (Subgroup): _____
Field Observations
Confirm Mapped Type? _____ Yes X No

Profile Description:

Depth inches	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0 – 10+	A	10 YR 2/1	--	--	Loam

Hydric Soil Indicators:

_____	Histosol	_____	Concretions
_____	Histic Epipedon	_____	High Organic Content in surface Layer in Sandy Soils
_____	Sulfidic Odor	_____	Organic Streaking in Sandy Soils
_____	Aquic Moisture Regime	_____	Listed on Local Hydric Soils List
_____	Reducing Conditions	_____	Listed on National Hydric Soils List
X	Gleyed or Low-Chroma Colors	_____	Other (Explain in Remarks)

Soil pit located in area of upland. Low-chroma colors present, but no direct evidence of hydric influence.

WETLAND DETERMINATION

Hydrophytic Vegetation Present? _____ Yes X No
Wetland Hydrology Present? _____ Yes X No
Hydric Soils Present? _____ Yes X No

Is this Sampling Point Within a Wetland? _____ Yes X No

Remarks:
Sampling point considered within an upland area.

Approved by HQUSACE 2/92

DATA FORM

ROUTINE WETLAND DETERMINATION

(1987 COE Wetlands Delineation Manual)

Project/Site: Kleinschmidt Creek	Date: 08/16/06
Applicant/Owner: MDT	County: Powell
Investigator: Greg Howard	State: MT

Do Normal Circumstances exist on the site:	X	Yes		No
Is the site significantly disturbed (Atypical Situation)?		Yes		No
Is the area a potential Problem Area?:		Yes		No
(If needed, explain on reverse.)				

Community ID: Emergent

Transect ID: 1

Plot ID: 2

VEGETATION

	Dominant Plant Species	Stratum	Indicator		Dominant Plant Species	Stratum	Indicator
1	*Phleum pratense*	H	FACU	9			
2	*Agrostis alba*	H	FAC+	10			
3	*Typha latifolia*	H	OBL	11			
4	*Phalaris arundinacea*	H	FACW	12			
5	*Salix boothii*	S	OBL	13			
6			--	14			
7				15			
8				16			

Percent of Dominant Species that are OBL, FACW, or FAC (excluding FAC-). 5/5= 100%

Area dominated by hydrophytic vegetation.

HYDROLOGY

Recorded Data (Describe in Remarks):

- ____ Stream, Lake, or Tide Gauge
- ____ Aerial Photographs
- ____ Other
- X No Recorded Data Available

Field Observations:

- Depth of Surface Water: 3 (in.)
- Depth to Free Water in Pit: ____ (in.)
- Depth to Saturated Soil: 0 (in.)

Wetland Hydrology Indicators:

Primary Indicators:

- X Inundated
- X Saturated in Upper 12 Inches
- ____ Water Marks
- ____ Drift Lines
- ____ Sediment Deposits
- ____ Drainage Patterns in Wetlands

Secondary Indicators (2 or more required):

- ____ Oxidized Root Channels in Upper 12 Inches
- ____ Water-Stained Leaves
- ____ Local Soil Survey Data
- ____ FAC-Neutral Test
- ____ Other (Explain in Remarks)

Remarks:

Hydrology indicator present with inundation and soils saturated to ground surface.

SOILS

Map Unit Name (Series and Phase): Tetonview Loam

Taxonomy (Subgroup): _____

Drainage Class: Poorly-drained

Field Observations

Confirm Mapped Type? _____ Yes X No

Profile Description:

Depth inches	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0 – 2	A	10 YR 2/1	--	--	Mucky mineral
2 – 12+	B	Gley 1 7Y / Gley 1 10Y			Sandy Clay

Hydric Soil Indicators:

_____	Histosol	_____	Concretions
_____	Histic Epipedon	_____	High Organic Content in surface Layer in Sandy Soils
_____	Sulfidic Odor	_____	Organic Streaking in Sandy Soils
_____	Aquic Moisture Regime	_____	Listed on Local Hydric Soils List
_____	Reducing Conditions	_____	Listed on National Hydric Soils List
X	Gleyed or Low-Chroma Colors	_____	Other (Explain in Remarks)

Hydric soils present with low-chroma colors.

WETLAND DETERMINATION

Hydrophytic Vegetation Present? X Yes _____ No

Wetland Hydrology Present? X Yes _____ No

Hydric Soils Present? X Yes _____ No

Is this Sampling Point Within a Wetland? X Yes _____ No

Remarks:

Sampling point is considered within a wetland. Wetland area consisting of an emergent vegetation type around the excavated wetlands fringe.

Approved by HQUSACE 2/92

ROUTINE WETLAND DETERMINATION
(1987 COE Wetlands Delineation Manual)

Project/Site: Kleinschmidt Creek	Date: 08/16/06
Applicant/Owner: MDT	County: Powell
Investigator: Greg Howard	State: MT

Do Normal Circumstances exist on the site:	X	Yes	___	No
Is the site significantly disturbed (Atypical Situation)?	___	Yes	___	No
Is the area a potential Problem Area?:	___	Yes	___	No
(If needed, explain on reverse.)				

Community ID: Emergent
Transect ID: 1
Plot ID: 3

VEGETATION

	Dominant Plant Species	Stratum	Indicator		Dominant Plant Species	Stratum	Indicator
1	*Carex nebrascensis*	H	OBL	9			
2	*Phalaris arundinacea*	H	FACW	10			
3	*Carex utriculata*	H	OBL	11			
4	*Juncus ensifolius*	H	FACW	12			
5	*Phleum pratense*	H	FACU	13			
6	*Juncus balticus*	H	FACW	14			
7	*Triglochin maritimum*	H	OBL	15			
8				16			

Percent of Dominant Species that are OBL, FACW, or FAC (excluding FAC-). 6/7 = 86%

Area dominated hydrophytic vegetation.

HYDROLOGY

___ Recorded Data (Describe in Remarks):
___ Stream, Lake, or Tide Gauge
___ Aerial Photographs
___ Other
X No Recorded Data Available

Field Observations:

Depth of Surface Water: ___ (in.)

Depth to Free Water in Pit: 0 (in.)

Depth to Saturated Soil: 0 (in.)

Wetland Hydrology Indicators:
Primary Indicators:
___ Inundated
X Saturated in Upper 12 Inches
___ Water Marks
___ Drift Lines
___ Sediment Deposits
___ Drainage Patterns in Wetlands
Secondary Indicators (2 or more required):
___ Oxidized Root Channels in Upper 12 Inches
___ Water-Stained Leaves
___ Local Soil Survey Data
___ FAC-Neutral Test
___ Other (Explain in Remarks)

Remarks:
Hydrology indicator present with free water in the sampling pit to the top.

SOILS

Map Unit Name (Series and Phase): Tetonview Loam

Drainage Class: Poorly-drained

Taxonomy (Subgroup): _____

Field Observations

Confirm Mapped Type? ____ Yes __X__ No

Profile Description:

Depth inches	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0 – 10+	B	10 YR 2/1	--	--	Loam with large cobbles

Hydric Soil Indicators:

____	Histosol	____	Concretions
____	Histic Epipedon	____	High Organic Content in surface Layer in Sandy Soils
____	Sulfidic Odor	____	Organic Streaking in Sandy Soils
____	Aquic Moisture Regime	____	Listed on Local Hydric Soils List
____	Reducing Conditions	____	Listed on National Hydric Soils List
X	Gleyed or Low-Chroma Colors	____	Other (Explain in Remarks)

Hydric soil indicator present with low-chroma colors.

WETLAND DETERMINATION

Hydrophytic Vegetation Present? X Yes ____ No

Wetland Hydrology Present? X Yes ____ No

Hydric Soils Present? X Yes ____ No

Is this Sampling Point Within a Wetland? X Yes ____ No

Remarks:

Sampling point considered within a wetland.

Approved by HQUSACE 2/92

ROUTINE WETLAND DETERMINATION
(1987 COE Wetlands Delineation Manual)

Project/Site: Kleinschmidt Creek	Date: 08/16/06
Applicant/Owner: MDT	County: Powell
Investigator: Greg Howard	State: MT

Do Normal Circumstances exist on the site:	X	Yes	___	No
Is the site significantly disturbed (Atypical Situation)?	___	Yes	___	No
Is the area a potential Problem Area?:	___	Yes	___	No
(If needed, explain on reverse.)				

Community ID: Emergent
Transect ID: 1
Plot ID: 4

VEGETATION

	Dominant Plant Species	Stratum	Indicator		Dominant Plant Species	Stratum	Indicator
1	*Carex nebrascensis*	H	OBL	9			
2	*Phalaris arundinacea*	H	FACW	10			
3	*Agrostis alba*	H	FAC+	11			
4	*Juncus ensifolius*	H	FACW	12			
5	*Phleum pratense*	H	FAC	13			
6	*Polygonum amphibium*	H	OBL	14			
7	*Deschampsia cespitosa*	H	FACW	15			
8				16			

Percent of Dominant Species that are OBL, FACW, or FAC (excluding FAC-). 7/7 = 100%

Area dominated by hydrophytic vegetation.

HYDROLOGY

___ Recorded Data (Describe in Remarks):
- ___ Stream, Lake, or Tide Gauge
- ___ Aerial Photographs
- ___ Other

X No Recorded Data Available

Field Observations:

Depth of Surface Water: 1 (in.)

Depth to Free Water in Pit: -- (in.)

Depth to Saturated Soil: 0 (in.)

Wetland Hydrology Indicators:

Primary Indicators:
- X Inundated
- X Saturated in Upper 12 Inches
- ___ Water Marks
- ___ Drift Lines
- ___ Sediment Deposits
- ___ Drainage Patterns in Wetlands

Secondary Indicators (2 or more required):
- ___ Oxidized Root Channels in Upper 12 Inches
- ___ Water-Stained Leaves
- ___ Local Soil Survey Data
- ___ FAC-Neutral Test
- ___ Other (Explain in Remarks)

Remarks:
Hydrology indicator present with inundation and soils saturated to the ground surface.

SOILS

Map Unit Name (Series and Phase): Tetonview Loam

Drainage Class: Poorly-drained

Taxonomy (Subgroup): _____

Field Observations

Confirm Mapped Type? _____ Yes __X__ No

Profile Description:

Depth inches	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0 – 12+	A	10 YR 2/1	--	--	Sandy loam with cobbles and gravels

Hydric Soil Indicators:

_____	Histosol	_____	Concretions
_____	Histic Epipedon	_____	High Organic Content in surface Layer in Sandy Soils
_____	Sulfidic Odor	_____	Organic Streaking in Sandy Soils
_____	Aquic Moisture Regime	_____	Listed on Local Hydric Soils List
_____	Reducing Conditions	_____	Listed on National Hydric Soils List
__X__	Gleyed or Low-Chroma Colors	_____	Other (Explain in Remarks)

Hydric soil indicator present with low-chroma colors.

WETLAND DETERMINATION

Hydrophytic Vegetation Present? __X__ Yes _____ No

Wetland Hydrology Present? __X__ Yes _____ No

Hydric Soils Present? __X__ Yes _____ No

Is this Sampling Point Within a Wetland? __X__ Yes _____ No

Remarks:

Sampling point considered within a wetland. Wetland area consisting of emergent type vegetation.

Approved by HQUSACE 2/92

MDT MONTANA WETLAND ASSESSMENT FORM (revised May 25, 1999)

1. Project Name: Kleinschmidt Creek **2. Project #:** 33054.00 0112 **Control #:** AA 1

3. Evaluation Date: 8/16/2006 **4. Evaluator(s):** G.Howard **5. Wetland / Site #(s):** Channel and adjacent wetlands

6. Wetland Location(s) i. T: 14 N **R:** 11 E **S:** 5 & 8 **T:** __ N **R:** __ E **S:** _____

ii. Approx. Stationing / Mileposts: _____

iii. Watershed: 2 - Upper Clark Fork **GPS Reference No. (if applies):** _____

Other Location Information: _____

7. A. Evaluating Agency MDT

8. Wetland Size (total acres): 23.86 (visually estimated)
_____ (measured, e.g. GPS)

B. Purpose of Evaluation:

- ☐ Wetlands potentially affected by MDT project
- ☐ Mitigation wetlands; pre-construction
- ☒ Mitigation wetlands; post-construction
- ☐ Other

9. Assessment Area (total acres): 23.86 (visually estimated)
_____ (measured, e.g. GPS)

Comments: _____

10. CLASSIFICATION OF WETLAND AND AQUATIC HABITATS IN AA

HGM CLASS [1]	SYSTEM [2]	SUBSYSTEM [2]	CLASS [2]	WATER REGIME [2]	MODIFIER [2]	% OF AA
Riverine	Riverine	Upper Perennial	Unconsolidated Bottom	Permanently Flooded	Excavated	20
Riverine	Palustrine	---	Emergent Wetland	Semipermanently Flooded	Excavated	80
---	---	---	---	---	---	
---	---	---	---	---	---	

[1] = Smith et al. 1995. [2] = Cowardin et al. 1979.

Comments: _____

11. ESTIMATED RELATIVE ABUNDANCE (of similarly classified sites within the same Major Montana Watershed Basin)
Common **Comments:** _____

12. GENERAL CONDITION OF AA

i. Regarding Disturbance: (Use matrix below to select appropriate response.)

Conditions Within AA	Predominant Conditions Adjacent (within 500 Feet) To AA		
	Land managed in predominantly natural state; is not grazed, hayed, logged, or otherwise converted; does not contain roads or buildings.	Land not cultivated, but moderately grazed or hayed or selectively logged or has been subject to minor clearing; contains few roads or buildings.	Land cultivated or heavily grazed or logged; subject to substantial fill placement, grading, clearing, or hydrological alteration; high road or building density.
AA occurs and is managed in predominantly a natural state; is not grazed, hayed, logged, or otherwise converted; does not contain roads or occupied buildings.	---	---	---
AA not cultivated, but moderately grazed or hayed or selectively logged or has been subject to relatively minor clearing, or fill placement, or hydrological alteration; contains few roads or buildings.	---	moderate disturbance	---
AA cultivated or heavily grazed or logged; subject to relatively substantial fill placement, grading, clearing, or hydrological alteration; high road or building density.	---	---	---

Comments: (types of disturbance, intensity, season, etc.) Livestock grazing and hay production.

ii. Prominent weedy, alien, & introduced species: Spotted knapweed, Canada thistle, oxeye daisy, black henbane, pennycress, musk thistle, and butter & eggs.

iii. Briefly describe AA and surrounding land use / habitat: AA is a riparian corridor with spring fed Kleinschmidt creek and adjacent wetlands. Surrounding land use includes livestock grazing and hay fields. AA located along HWY 200, 5 miles E. of Ovando.

13. STRUCTURAL DIVERSITY (Based on 'Class' column of #10 above.)

Number of 'Cowardin' Vegetated Classes Present in AA	≥3 Vegetated Classes or ≥ 2 if one class is forested	2 Vegetated Classes or 1 if forested	≤ 1 Vegetated Class
Select Rating	---	---	Low

Comments: _____

14A. HABITAT FOR FEDERALLY LISTED OR PROPOSED THREATENED OR ENDANGERED PLANTS AND ANIMALS

i. AA is Documented (D) or Suspected (S) to contain (check box):

Primary or Critical habitat **(list species)**	☐ D ☐ S	_____
Secondary habitat **(list species)**	☒ D ☐ S	Bull trout
Incidental habitat **(list species)**	☒ D ☐ S	Bald eagle
No usable habitat	☐ D ☒ S	Grizzly bear, Lynx

ii. Rating (Based on the strongest habitat chosen in 14A(i) above, find the corresponding rating of High (H), Moderate (M), or Low (L) for this function.

Highest Habitat Level	doc/primary	sus/primary	doc/secondary	sus/secondary	doc/incidental	sus/incidental	none
Functional Point & Rating	---	---	.8 (M)	---	---	---	---

If documented, list the source (e.g., observations, records, etc.)**:** FWP

14B. HABITAT FOR PLANTS AND ANIMALS RATED AS S1, S2, OR S3 BY THE MONTANA NATURAL HERITAGE PROGRAM.
Do not include species listed in 14A(i).

i. AA is Documented (D) or Suspected (S) to contain (check box):

Primary or Critical habitat **(list species)**	☒ D ☐ S	Crawe sedge (S2) & green-keeled cottongrass (S3)
Secondary habitat **(list species)**	☒ D ☐ S	Westslope cutthroat trout
Incidental habitat **(list species)**	☐ D ☒ S	Common loon
No usable habitat	☐ D ☒ S	Missoual phlox

ii. Rating: Based on the strongest habitat chosen in 14B(i) above, find the corresponding rating of High (H), Moderate (M), or Low (L) for this function.

Highest Habitat Level	doc/primary	sus/primary	doc/secondary	sus/secondary	doc/incidental	sus/incidental	none
Functional Point & Rating	1(H)	---	---	---	---	---	---

If documented, list the source (e.g., observations, records, etc.)**:** FWP & plants identified at the site during 2005

14C. GENERAL WILDLIFE HABITAT RATING

i. Evidence of overall wildlife use in the AA: Check either substantial, moderate, or low.

☐ **Substantial** (based on any of the following)
- ☐ observations of abundant wildlife #s or high species diversity (during any period)
- ☐ abundant wildlife sign such as scat, tracks, nest structures, game trails, etc.
- ☐ presence of extremely limiting habitat features not available in the surrounding area
- ☐ interviews with local biologists with knowledge of the AA

☐ **Low** (based on any of the following)
- ☐ few or no wildlife observations during peak use periods
- ☐ little to no wildlife sign
- ☐ sparse adjacent upland food sources
- ☐ interviews with local biologists with knowledge of AA

☒ **Moderate** (based on any of the following)
- ☒ observations of scattered wildlife groups or individuals or relatively few species during peak periods
- ☒ common occurrence of wildlife sign such as scat, tracks, nest structures, game trails, etc.
- ☒ adequate adjacent upland food sources
- ☐ interviews with local biologists with knowledge of the AA

ii. Wildlife Habitat Features: Working from top to bottom, select the AA attribute to determine the exceptional (E), high (H), moderate (M), or low (L) rating. Structural diversity is from 13. For class cover to be considered evenly distributed, vegetated classes must be within 20% of each other in terms of their percent composition in the AA (see 10). Duration of Surface Water: P/P = permanent/perennial; S/I = seasonal/intermittent; T/E = temporary/ephemeral; A= absent.

Structural Diversity (from 13)	☐**High**								☐**Moderate**								☒**Low**			
Class Cover Distribution (all vegetated classes)	☐**Even**				☐**Uneven**				☐**Even**				☐**Uneven**				☒**Even**			
Duration of Surface Water in ≥ 10% of AA	**P/P**	**S/I**	**T/E**	**A**	**P/P**	**S/I**	**T/E**	**A**	**P/P**	**S/I**	**T/E**	**A**	**P/P**	**S/I**	**T/E**	**A**	**P/P**	**S/I**	**T/E**	**A**
Low disturbance at AA (see 12)	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Moderate disturbance at AA (see 12)	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	H	--	--	--
High disturbance at AA (see 12)	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

iii. Rating: Use 14C(i) and 14C(ii) above and the matrix below to arrive at the functional point and rating of exceptional (E), high (H), moderate (M), or low (L) for this function.

Evidence of Wildlife Use from 14C(i)	**Wildlife Habitat Features Rating** from 14C(ii)			
	☐ **Exceptional**	☒ **High**	☐ **Moderate**	☐ **Low**
Substantial	--	--	--	--
Moderate	--	.7 (M)	--	--
Low	--	--	--	--

Comments: _____

14D. GENERAL FISH / AQUATIC HABITAT RATING ☐ **NA** (proceed to 14E)

If the AA is not or was not historically used by fish due to lack of habitat or excessive gradient, then check the NA box above.
Assess if the AA is used by fish or the existing situation is "correctable" such that the AA could be used by fish [*e.g.* fish use is precluded by perched culvert or other barrier, etc.]. If fish use occurs in the AA but is not desired from a resource management perspective (*e.g.* fish use within an irrigation canal], then Habitat Quality [14D(i)] below should be marked as "Low", applied accordingly in 14D(ii) below, and noted in the comments.

i. Habitat Quality: Pick the appropriate AA attributes in matrix to determine the quality rating of exceptional (E), high (H), moderate (M), or low (L).

Duration of Surface Water in AA	☒**Permanent/Perennial**			☐**Seasonal / Intermittent**			☐**Temporary / Ephemeral**		
Cover - % of waterbody in AA containing cover objects (*e.g.* submerged logs, large rocks & boulders, overhanging banks, floating-leaved vegetation)	**>25%**	**10-25%**	**<10%**	**>25%**	**10-25%**	**<10%**	**>25%**	**10-25%**	**<10%**
Shading - >75% of streambank or shoreline of AA contains riparian or wetland scrub-shrub or forested communities	--	--	--	--	--	--	--	--	--
Shading – 50 to 75% of streambank or shoreline of AA contains riparian or wetland scrub-shrub or forested communities.	--	--	--	--	--	--	--	--	--
Shading - < 50% of streambank or shoreline of AA contains riparian or wetland scrub-shrub or forested communities.	--	M	--	--	--	--	--	--	--

ii. Modified Habitat Quality: Is fish use of the AA precluded or significantly reduced by a culvert, dike, other man-made structure or activity **or** is the waterbody included on the 'MDEQ list of waterbodies in need of TMDL development' with 'Probable Impaired Uses' listed as cold or warm water fishery or aquatic life support**?**
☐ **Y** ☐ **N** If yes, reduce the rating from 14D(i) by one level and check the modified habitat quality rating: ☐ E ☐ H ☐ M ☐ L

iii. Rating: Use the conclusions from 14D(i) and 14D(ii) above and the matrix below to arrive at the functional point and rating of exceptional (E), high (H), moderate (M), or low (L).

Types of Fish Known or Suspected within AA	**Modified Habitat Quality** from 14D(ii)			
	☐ **Exceptional**	☐ **High**	☒ **Moderate**	☐ **Low**
Native game fish	--	--	.7 (M)	--
Introduced game fish	--	--	--	--
Non-game fish	--	--	--	--
No fish	--	--	--	--

Comments: _____

14E. FLOOD ATTENUATION ☒ **NA** (proceed to 14G)

Applies only to wetlands subject to flooding via in-channel or overbank flow. If wetlands in AA do not flood from in-channel or overbank flow, then check NA.

i. Rating: Working from top to bottom, mark the appropriate attributes to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.

Estimated wetland area in AA subject to periodic flooding	☐ **≥ 10 acres**			☐ **<10, >2 acres**			☐ **≤2 acres**		
% of flooded wetland classified as forested, scrub/shrub, or both	**75%**	**25-75%**	**<25%**	**75%**	**25-75%**	**<25%**	**75%**	**25-75%**	**<25%**
AA contains **no outlet or restricted outlet**	--	--	--	--	--	--	--	--	--
AA contains **unrestricted outlet**	--	--	--	--	--	--	--	--	--

ii. Are residences, businesses, or other features which may be significantly damaged by floods located within 0.5 miles downstream of the AA? (check)
☐**Y** ☐**N** **Comments:** _____

14F. SHORT AND LONG TERM SURFACE WATER STORAGE ☐ **NA** (proceed to 14G)

Applies to wetlands that flood or pond from overbank or in-channel flow, precipitation, upland surface flow, or groundwater flow.
If no wetlands in the AA are subject to flooding or ponding, then check NA above.

i. Rating: Working from top to bottom, use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.
P/P = permanent/perennial; S/I = seasonal/intermittent; T/E = temporary/ephemeral.

Estimated maximum acre feet of water contained in wetlands within the AA that are subject to periodic flooding or ponding**.**	☒ **>5 acre feet**			☐ **<5, >1 acre feet**			☐ **≤1 acre foot**		
Duration of surface water at wetlands within the AA	**P/P**	**S/I**	**T/E**	**P/P**	**S/I**	**T/E**	**P/P**	**S/I**	**T/E**
Wetlands in AA flood or pond **≥ 5 out of 10 years**	1 (H)	--	--	--	--	--	--	--	--
Wetlands in AA flood or pond **< 5 out of 10 years**	--	--	--	--	--	--	--	--	--

Comments: _____

14G. SEDIMENT/NUTRIENT/TOXICANT RETENTION AND REMOVAL ☐ **NA** (proceed to 14H)

Applies to wetlands with the potential to receive excess sediments, nutrients, or toxicants through influx of surface or ground water or direct input.
If no wetlands in the AA are subject to such input, check NA above.

i. Rating Working from top to bottom, use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.

Sediment, Nutrient, and Toxicant Input Levels Within AA	AA receives or surrounding land use has potential to deliver low to moderate levels of sediments, nutrients, or compounds such that other functions are not substantially impaired. Minor sedimentation, sources of nutrients or toxicants, or signs of eutrophication present.				Waterbody on MDEQ list of waterbodies in need of TMDL development for "probable causes" related to sediment, nutrients, or toxicants **or** AA receives or surrounding land use has potential to deliver high levels of sediments, nutrients, or compounds such that other functions are substantially impaired. Major sedimentation, sources of nutrients or toxicants, or signs of eutrophication present.			
% cover of wetland vegetation in AA	☒ **≥ 70%**		☐ **< 70%**		☐ **≥ 70%**		☐ **< 70%**	
Evidence of flooding or ponding in AA	☒ **Yes**	☐ **No**	☐ **Yes**	☐ **No**	☐ **Yes**	☐ **No**	☐ **Yes**	☐ **No**
AA contains **no or restricted outlet**	--	--	--	--	--	--	--	--
AA contains **unrestricted outlet**	.9 (H)	--	--	--	--	--	--	--

Comments: _____

14H. SEDIMENT/SHORELINE STABILIZATION ☐ **NA** (proceed to 14I)

Applies only if AA occurs on or within the banks of a river, stream, or other natural or man-made drainage, or on the shoreline of a standing water body that is subject to wave action. If this does not apply, then check NA above.

i. Rating: Working from top to bottom, use the matrix below to arrive at the functional point and rating exceptional (E), high (H), moderate (M), or low (L) for this function.

% Cover of wetland streambank or shoreline by species with deep, binding rootmasses.	Duration of Surface Water Adjacent to Rooted Vegetation		
	☐ Permanent / Perennial	☐ Seasonal / Intermittent	☐ Temporary / Ephemeral
≥ 65 %	1 (H)	--	--
35-64 %	--	--	--
< 35 %	--	--	--

Comments: Sedges, rushes and willows along shoreline.

14I. PRODUCTION EXPORT / FOOD CHAIN SUPPORT

i. Rating: Working from top to bottom, use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function. **A** = acreage of vegetated component in the AA. **B** = structural diversity rating from #13. **C** = Yes (Y) or No (N) as to whether or not the AA contains a surface or subsurface outlet. **P/P** = permanent/perennial; **S/I** = seasonal/intermittent; **T/E/A**= temporary/ephemeral/absent.

A	☒ Vegetated component >5 acres						☐ Vegetated component 1-5 acres						☐ Vegetated component <1 acre					
B	☐ High		☐ Moderate		☒ Low		☐ High		☐ Moderate		☐ Low		☐ High		☐ Moderate		☐ Low	
C	☐Y	☐N	☐Y	☐N	☒Y	☐N	☐Y	☐N	☐Y	☐N	☐Y	☐N	☐Y	☐N	☐Y	☐N	☐Y	☐N
P/P	--	--	--	--	.8H	--	--	--	--	--	--	--	--	--	--	--	--	--
S/I	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
T/E/A	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Comments: _____

14J. GROUNDWATER DISCHARGE / RECHARGE (DR) (Check the indicators in i & ii below that apply to the AA.)

i. ☒ **Discharge Indicators**

- ☒ Springs are known or observed.
- ☒ Vegetation growing during dormant season / drought.
- ☒ Wetland occurs at the toe of a natural slope.
- ☒ Seeps are present at the wetland edge.
- ☒ AA permanently flooded during drought periods.
- ☒ Wetland contains an outlet, but no inlet.
- ☐ Other _____

ii. ☐ **Recharge Indicators**

- ☐ Permeable substrate presents without underlying impeding layer.
- ☐ Wetland contains inlet but not outlet.
- ☐ Other _____

iii. Rating: Use information from 14J(i) and 14J(ii) above and the table below to arrive at the functional point and rating of high (H) or low (L) for this function.

Criteria	Functional Point and Rating
AA has known Discharge/Recharge area or one or more indicators of D/R present	1 (H)
No Discharge/Recharge indicators present	--
Available Discharge/Recharge information inadequate to rate AA D/R potential	--

Comments: _____

14K. UNIQUENESS

i. Rating: Working from top to bottom, use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.

Replacement Potential	AA contains fen, bog, warm springs or mature (>80 yr-old) forested wetland or plant association listed as "S1" by the MTNHP.			AA does not contain previously cited rare types and structural diversity (#13) is high or contains plant association listed as "S2" by the MTNHP.			AA does not contain previously cited rare types or associations and structural diversity (#13) is low-moderate.		
Estimated Relative Abundance from 11	☐rare	☐common	☐abundant	☐rare	☐common	☐abundant	☐rare	☒common	☐abundant
Low disturbance at AA (12i)	--	--	--	--	--	--	--	--	--
Moderate disturbance at AA (12i)	--	--	--	--	--	--	--	.3L	--
High disturbance at AA (12i)	--	--	--	--	--	--	--	--	--

Comments: _____

14L. RECREATION / EDUCATION POTENTIAL

i. Is the AA a known recreational or educational site? ☐ **Yes** [**Rate** ☐ **High (1.0)**, then proceed to 14L(ii) only] ☐ **No** [Proceed to 14L(iii)]

ii. Check categories that apply to the AA: ☐ Educational / scientific study ☐ Consumptive rec. ☐ Non-consumptive rec. ☐ Other

iii. Based on the location, diversity, size, and other site attributes, is there a strong potential for recreational or educational use?

☐ **Yes** [Proceed to 14L (ii) and then 14L(iv)] ☐ **No** [Rate as low in 14L(iv)]

iv. Rating Use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.

Ownership	Disturbance at AA from 12(i)		
	☐ Low	☒ Moderate	☐ High
Public ownership	--	--	--
Private ownership	--	.3(L)	--

Comments: _____

FUNCTION, VALUE SUMMARY, AND OVERALL RATING

Function and Value Variables	Rating	Actual Functional Points	Possible Functional Points	Functional Units (Actual Points x Estimated AA Acreage)
A. Listed/Proposed T&E Species Habitat	moderate	0.80	1	
B. MT Natural Heritage Program Species Habitat	high	1.00	1	
C. General Wildlife Habitat	moderate	0.70	1	
D. General Fish/Aquatic Habitat	moderate	0.70	1	
E. Flood Attenuation	N/A	0.00	--	
F. Short and Long Term Surface Water Storage	high	1.00	1	
G. Sediment/Nutrient/Toxicant Removal	high	0.90	1	
H. Sediment/Shoreline Stabilization	high	1.00	1	
I. Production Export/Food Chain Support	high	0.80	1	
J. Groundwater Discharge/Recharge	high	1.00	1	
K. Uniqueness	low	0.30	1	
L. Recreation/Education Potential	low	0.30	1	
	Total:	**8.50**	**11.00**	____
		Percent of Total Possible Points:	**77%** (Actual / Possible) x 100 [rd to nearest whole #]	

Category I Wetland: (Must satisfy **one** of the following criteria. If not satisfied, proceed to Category II.)
- ☐ Score of 1 functional point for Listed/Proposed Threatened or Endangered Species; **or**
- ☐ Score of 1 functional point for Uniqueness; **or**
- ☐ Score of 1 functional point for Flood Attenuation **and** answer to Question 14E(ii) is "yes"; **or**
- ☐ Percent of total Possible Points is > 80%.

Category II Wetland: (Criteria for Category I not satisfied **and** meets any **one** of the following Category II criteria. If not satisfied, proceed to Category IV.)
- ☒ Score of 1 functional point for Species Rated S1, S2, or S3 by the MT Natural Heritage Program; **or**
- ☐ Score of .9 or 1 functional point for General Wildlife Habitat; **or**
- ☐ Score of .9 or 1 functional point for General Fish/Aquatic Habitat; **or**
- ☐ "High" to "Exceptional" ratings for **both** General Wildlife Habitat **and** General Fish / Aquatic Habitat; **or**
- ☐ Score of .9 functional point for Uniqueness; **or**
- ☒ Percent of total possible points is > 65%.

☐ **Category III Wetland:** (Criteria for Categories I, II, or IV not satisfied.)

Category IV Wetland: (Criteria for Categories I or II are not satisfied **and** all of the following criteria are met; If not satisfied, return to Category III.)
- ☐ "Low" rating for Uniqueness; **and**
- ☐ "Low" rating for Production Export / Food Chain Support; **and**
- ☐ Percent of total possible points is < 30%.

OVERALL ANALYSIS AREA (AA) RATING: (Check appropriate category based on the criteria outlined above.)

☐ **I** ☒ **II** ☐ **III** ☐ **IV**

MDT MONTANA WETLAND ASSESSMENT FORM (revised May 25, 1999)

1. Project Name: Kleinschmidt Creek **2. Project #:** 33054.00 0112 **Control #:** AA 2

3. Evaluation Date: 8/16/2006 **4. Evaluator(s):** G.Howard **5. Wetland / Site #(s):** Excavated wetland & emergent fringe

6. Wetland Location(s) i. T: 14 N **R:** 11 E **S:** 5 & 8 **T:** __ N **R:** __ E **S:** _____

ii. Approx. Stationing / Mileposts: _____

iii. Watershed: 2 - Upper Clark Fork **GPS Reference No. (if applies):** _____

Other Location Information: _____

7. A. Evaluating Agency MDT

8. Wetland Size (total acres): _____ (visually estimated)
1.55 (measured, e.g. GPS)

B. Purpose of Evaluation:
- ☐ Wetlands potentially affected by MDT project
- ☐ Mitigation wetlands; pre-construction
- ☒ Mitigation wetlands; post-construction
- ☐ Other

9. Assessment Area (total acres): _____ (visually estimated)
1.55 (measured, e.g. GPS)

Comments: _____

10. CLASSIFICATION OF WETLAND AND AQUATIC HABITATS IN AA

HGM CLASS [1]	SYSTEM [2]	SUBSYSTEM [2]	CLASS [2]	WATER REGIME [2]	MODIFIER [2]	% OF AA
Riverine	Palustrine	None	Unconsolidated Bottom	Permanently Flooded	Excavated	60
Riverine	Palustrine	None	Emergent Wetland	Intermittently Exposed	Excavated	25
Riverine	Palustrine	None	Unconsolidated Shore	Intermittently Exposed	Excavated	10
Riverine	Palustrine	None	Aquatic Bed	Permanently Flooded	Excavated	5

[1] = Smith et al. 1995. [2] = Cowardin et al. 1979.

Comments: _____

11. ESTIMATED RELATIVE ABUNDANCE (of similarly classified sites within the same Major Montana Watershed Basin)
Common **Comments:** _____

12. GENERAL CONDITION OF AA

i. Regarding Disturbance: (Use matrix below to select appropriate response.)

Conditions Within AA	Predominant Conditions Adjacent (within 500 Feet) To AA		
	Land managed in predominantly natural state; is not grazed, hayed, logged, or otherwise converted; does not contain roads or buildings.	Land not cultivated, but moderately grazed or hayed or selectively logged or has been subject to minor clearing; contains few roads or buildings.	Land cultivated or heavily grazed or logged; subject to substantial fill placement, grading, clearing, or hydrological alteration; high road or building density.
AA occurs and is managed in predominantly a natural state; is not grazed, hayed, logged, or otherwise converted; does not contain roads or occupied buildings.	---	---	---
AA not cultivated, but moderately grazed or hayed or selectively logged or has been subject to relatively minor clearing, or fill placement, or hydrological alteration; contains few roads or buildings.	---	moderate disturbance	---
AA cultivated or heavily grazed or logged; subject to relatively substantial fill placement, grading, clearing, or hydrological alteration; high road or building density.	---	---	---

Comments: (types of disturbance, intensity, season, etc.) Livestock grazing and hay production.

ii. Prominent weedy, alien, & introduced species: Spotted knapweed, Canada thistle, oxeye daisy, black henbane, pennycress, musk thistle, and butter & eggs.

iii. Briefly describe AA and surrounding land use / habitat: AA is a riparian corridor with spring fed Kleinschmidt creek and adjacent wetlands. Surrounding land use includes livestock grazing and hay fields. AA located along HWY 200, 5 miles E. of Ovando.

13. STRUCTURAL DIVERSITY (Based on 'Class' column of #10 above.)

Number of 'Cowardin' Vegetated Classes Present in AA	≥3 Vegetated Classes or ≥ 2 if one class is forested	2 Vegetated Classes or 1 if forested	≤ 1 Vegetated Class
Select Rating	---	Moderate	---

Comments: _____

14A. HABITAT FOR FEDERALLY LISTED OR PROPOSED THREATENED OR ENDANGERED PLANTS AND ANIMALS

i. AA is Documented (D) or Suspected (S) to contain (check box):

Primary or Critical habitat **(list species)**	☐ D	☐ S	_____
Secondary habitat **(list species)**	☐ D	☐ S	_____
Incidental habitat **(list species)**	☒ D	☐ S	Bald eagle
No usable habitat	☐ D	☐ S	_____

ii. Rating (Based on the strongest habitat chosen in 14A(i) above, find the corresponding rating of High (H), Moderate (M), or Low (L) for this function.

Highest Habitat Level	doc/primary	sus/primary	doc/secondary	sus/secondary	doc/incidental	sus/incidental	none
Functional Point & Rating	---	---	---	---	.5 (L)	---	---

If documented, list the source (e.g., observations, records, etc.)**:** FWP

14B. HABITAT FOR PLANTS AND ANIMALS RATED AS S1, S2, OR S3 BY THE MONTANA NATURAL HERITAGE PROGRAM.
Do not include species listed in 14A(i).

i. AA is Documented (D) or Suspected (S) to contain (check box):

Primary or Critical habitat **(list species)**	☐ D	☐ S	_____
Secondary habitat **(list species)**	☐ D	☐ S	_____
Incidental habitat **(list species)**	☐ D	☒ S	Common loon
No usable habitat	☐ D	☐ S	_____

ii. Rating: Based on the strongest habitat chosen in 14B(i) above, find the corresponding rating of High (H), Moderate (M), or Low (L) for this function.

Highest Habitat Level	doc/primary	sus/primary	doc/secondary	sus/secondary	doc/incidental	sus/incidental	none
Functional Point & Rating	---	---	---	---	---	.1 (L)	---

If documented, list the source (e.g., observations, records, etc.)**:** FWP

14C. GENERAL WILDLIFE HABITAT RATING

i. Evidence of overall wildlife use in the AA: Check either substantial, moderate, or low.

☐ **Substantial** (based on any of the following)
- ☐ observations of abundant wildlife #s or high species diversity (during any period)
- ☐ abundant wildlife sign such as scat, tracks, nest structures, game trails, etc.
- ☐ presence of extremely limiting habitat features not available in the surrounding area
- ☐ interviews with local biologists with knowledge of the AA

☐ **Low** (based on any of the following)
- ☐ few or no wildlife observations during peak use periods
- ☐ little to no wildlife sign
- ☐ sparse adjacent upland food sources
- ☐ interviews with local biologists with knowledge of AA

☒ **Moderate** (based on any of the following)
- ☒ observations of scattered wildlife groups or individuals or relatively few species during peak periods
- ☒ common occurrence of wildlife sign such as scat, tracks, nest structures, game trails, etc.
- ☒ adequate adjacent upland food sources
- ☒ interviews with local biologists with knowledge of the AA

ii. Wildlife Habitat Features: Working from top to bottom, select the AA attribute to determine the exceptional (E), high (H), moderate (M), or low (L) rating. Structural diversity is from 13. For class cover to be considered evenly distributed, vegetated classes must be within 20% of each other in terms of their percent composition in the AA (see 10). Duration of Surface Water: P/P = permanent/perennial; S/I = seasonal/intermittent; T/E = temporary/ephemeral; A= absent.

Structural Diversity (from 13)	☐**High**								☒**Moderate**								☐**Low**			
Class Cover Distribution (all vegetated classes)	☐**Even**				☐**Uneven**				☒**Even**				☐**Uneven**				☐**Even**			
Duration of Surface Water in ≥ 10% of AA	**P/P**	**S/I**	**T/E**	**A**	**P/P**	**S/I**	**T/E**	**A**	**P/P**	**S/I**	**T/E**	**A**	**P/P**	**S/I**	**T/E**	**A**	**P/P**	**S/I**	**T/E**	**A**
Low disturbance at AA (see 12)	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Moderate disturbance at AA (see 12)	--	--	--	--	--	--	--	--	H	--	--	--	--	--	--	--	--	--	--	--
High disturbance at AA (see 12)	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

iii. Rating: Use 14C(i) and 14C(ii) above and the matrix below to arrive at the functional point and rating of exceptional (E), high (H), moderate (M), or low (L) for this function.

Evidence of Wildlife Use from 14C(i)	**Wildlife Habitat Features Rating** from 14C(ii)			
	☐ **Exceptional**	☒ **High**	☐ **Moderate**	☐ **Low**
Substantial	--	--	--	--
Moderate	--	.7 (M)	--	--
Low	--	--	--	--

Comments: _____

14D. GENERAL FISH / AQUATIC HABITAT RATING ☒ **NA** (proceed to 14E)

If the AA is not or was not historically used by fish due to lack of habitat or excessive gradient, then check the NA box above.
Assess if the AA is used by fish or the existing situation is "correctable" such that the AA could be used by fish [*e.g.* fish use is precluded by perched culvert or other barrier, etc.]. If fish use occurs in the AA but is not desired from a resource management perspective (*e.g.* fish use within an irrigation canal], then Habitat Quality [14D(i)] below should be marked as "Low", applied accordingly in 14D(ii) below, and noted in the comments.

i. Habitat Quality: Pick the appropriate AA attributes in matrix to determine the quality rating of exceptional (E), high (H), moderate (M), or low (L).

Duration of Surface Water in AA	☐ **Permanent/Perennial**			☐ **Seasonal / Intermittent**			☐ **Temporary / Ephemeral**		
Cover - % of waterbody in AA containing cover objects (*e.g.* submerged logs, large rocks & boulders, overhanging banks, floating-leaved vegetation)	**>25%**	**10-25%**	**<10%**	**>25%**	**10-25%**	**<10%**	**>25%**	**10-25%**	**<10%**
Shading - >75% of streambank or shoreline of AA contains riparian or wetland scrub-shrub or forested communities	--	--	--	--	--	--	--	--	--
Shading – 50 to 75% of streambank or shoreline of AA contains riparian or wetland scrub-shrub or forested communities.	--	--	--	--	--	--	--	--	--
Shading - < 50% of streambank or shoreline of AA contains riparian or wetland scrub-shrub or forested communities.	--	--	--	--	--	--	--	--	--

ii. Modified Habitat Quality: Is fish use of the AA precluded or significantly reduced by a culvert, dike, other man-made structure or activity **or** is the waterbody included on the 'MDEQ list of waterbodies in need of TMDL development' with 'Probable Impaired Uses' listed as cold or warm water fishery or aquatic life support**?**
☐ **Y** ☐ **N** If yes, reduce the rating from 14D(i) by one level and check the modified habitat quality rating: ☐ E ☐ H ☐ M ☐ L

iii. Rating: Use the conclusions from 14D(i) and 14D(ii) above and the matrix below to arrive at the functional point and rating of exceptional (E), high (H), moderate (M), or low (L).

Types of Fish Known or Suspected within AA	**Modified Habitat Quality** from 14D(ii)			
	☐ **Exceptional**	☐ **High**	☐ **Moderate**	☐ **Low**
Native game fish	--	--	--	--
Introduced game fish	--	--	--	--
Non-game fish	--	--	--	--
No fish	--	--	--	--

Comments: _____

14E. FLOOD ATTENUATION ☒ **NA** (proceed to 14G)

Applies only to wetlands subject to flooding via in-channel or overbank flow. If wetlands in AA do not flood from in-channel or overbank flow, then check NA.

i. Rating: Working from top to bottom, mark the appropriate attributes to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.

Estimated wetland area in AA subject to periodic flooding	☐ **≥ 10 acres**			☐ **<10, >2 acres**			☐ **≤2 acres**		
% of flooded wetland classified as forested, scrub/shrub, or both	**75%**	**25-75%**	**<25%**	**75%**	**25-75%**	**<25%**	**75%**	**25-75%**	**<25%**
AA contains **no outlet or restricted outlet**	--	--	--	--	--	--	--	--	--
AA contains **unrestricted outlet**	--	--	--	--	--	--	--	--	--

ii. Are residences, businesses, or other features which may be significantly damaged by floods located within 0.5 miles downstream of the AA? (check)
☐**Y** ☐**N** **Comments:** _____

14F. SHORT AND LONG TERM SURFACE WATER STORAGE ☐ **NA** (proceed to 14G)

Applies to wetlands that flood or pond from overbank or in-channel flow, precipitation, upland surface flow, or groundwater flow.
If no wetlands in the AA are subject to flooding or ponding, then check NA above.

i. Rating: Working from top to bottom, use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.
P/P = permanent/perennial; S/I = seasonal/intermittent; T/E = temporary/ephemeral.

Estimated maximum acre feet of water contained in wetlands within the AA that are subject to periodic flooding or ponding**.**	☒ **>5 acre feet**			☐ **<5, >1 acre feet**			☐ **≤1 acre foot**		
Duration of surface water at wetlands within the AA	**P/P**	**S/I**	**T/E**	**P/P**	**S/I**	**T/E**	**P/P**	**S/I**	**T/E**
Wetlands in AA flood or pond **≥ 5 out of 10 years**	1 (H)	--	--	--	--	--	--	--	--
Wetlands in AA flood or pond **< 5 out of 10 years**	--	--	--	--	--	--	--	--	--

Comments: _____

14G. SEDIMENT/NUTRIENT/TOXICANT RETENTION AND REMOVAL ☐ **NA** (proceed to 14H)

Applies to wetlands with the potential to receive excess sediments, nutrients, or toxicants through influx of surface or ground water or direct input.
If no wetlands in the AA are subject to such input, check NA above.

i. Rating Working from top to bottom, use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.

Sediment, Nutrient, and Toxicant Input Levels Within AA	AA receives or surrounding land use has potential to deliver low to moderate levels of sediments, nutrients, or compounds such that other functions are not substantially impaired. Minor sedimentation, sources of nutrients or toxicants, or signs of eutrophication present.				Waterbody on MDEQ list of waterbodies in need of TMDL development for "probable causes" related to sediment, nutrients, or toxicants **or** AA receives or surrounding land use has potential to deliver high levels of sediments, nutrients, or compounds such that other functions are substantially impaired. Major sedimentation, sources of nutrients or toxicants, or signs of eutrophication present.			
% cover of wetland vegetation in AA	☐ **≥ 70%**		☐ **< 70%**		☐ **≥ 70%**		☐ **< 70%**	
Evidence of flooding or ponding in AA	☐ **Yes**	☐ **No**	☒ **Yes**	☐ **No**	☐ **Yes**	☐ **No**	☐ **Yes**	☐ **No**
AA contains **no or restricted outlet**	--	--	.7 (M)	--	--	--	--	--
AA contains **unrestricted outlet**	--	--	--	--	--	--	--	--

Comments: _____

14H. SEDIMENT/SHORELINE STABILIZATION ☐ **NA** (proceed to 14I)

Applies only if AA occurs on or within the banks of a river, stream, or other natural or man-made drainage, or on the shoreline of a standing water body that is subject to wave action. If this does not apply, then check NA above.

i. Rating: Working from top to bottom, use the matrix below to arrive at the functional point and rating exceptional (E), high (H), moderate (M), or low (L) for this function.

% Cover of wetland streambank or shoreline by species with deep, binding rootmasses.	**Duration of Surface Water Adjacent to Rooted Vegetation**		
	☐**Permanent / Perennial**	☐**Seasonal / Intermittent**	☐**Temporary / Ephemeral**
≥ 65 %	--	--	--
35-64 %	.7 (M)	--	--
< 35 %	--	--	--

Comments: _____

14I. PRODUCTION EXPORT / FOOD CHAIN SUPPORT

i. Rating: Working from top to bottom, use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function. **A** = acreage of vegetated component in the AA. **B** = structural diversity rating from #13. **C** = Yes (Y) or No (N) as to whether or not the AA contains a surface or subsurface outlet. **P/P** = permanent/perennial; **S/I** = seasonal/intermittent; **T/E/A**= temporary/ephemeral/absent.

A	☐ **Vegetated component >5 acres**						☒ **Vegetated component 1-5 acres**						☐ **Vegetated component <1 acre**					
B	☐ **High**		☐ **Moderate**		☐ **Low**		☐ **High**		☒ **Moderate**		☐ **Low**		☐ **High**		☐ **Moderate**		☐ **Low**	
C	☐**Y**	☐**N**	☐**Y**	☐**N**	☐**Y**	☐**N**	☐**Y**	☐**N**	☐**Y**	☒**N**	☐**Y**	☐**N**	☐**Y**	☐**N**	☐**Y**	☐**N**	☐**Y**	☐**N**
P/P	--	--	--	--	--	--	--	--	--	.7M	--	--	--	--	--	--	--	--
S/I	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
T/E/A	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Comments: _____

14J. GROUNDWATER DISCHARGE / RECHARGE (DR) (Check the indicators in i & ii below that apply to the AA.)

i. ☒ **Discharge Indicators**

- ☒ Springs are known or observed.
- ☐ Vegetation growing during dormant season / drought.
- ☐ Wetland occurs at the toe of a natural slope.
- ☒ Seeps are present at the wetland edge.
- ☒ AA permanently flooded during drought periods.
- ☐ Wetland contains an outlet, but no inlet.
- ☐ Other _____

ii. ☒ **Recharge Indicators**

- ☒ Permeable substrate presents without underlying impeding layer.
- ☐ Wetland contains inlet but not outlet.
- ☐ Other _____

iii. Rating: Use information from 14J(i) and 14J(ii) above and the table below to arrive at the functional point and rating of high (H) or low (L) for this function.

Criteria	**Functional Point and Rating**
AA has known Discharge/Recharge area or one or more indicators of D/R present	1 (H)
No Discharge/Recharge indicators present	--
Available Discharge/Recharge information inadequate to rate AA D/R potential	--

Comments: _____

14K. UNIQUENESS

i. Rating: Working from top to bottom, use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.

Replacement Potential	**AA contains fen, bog, warm springs or mature (>80 yr-old) forested wetland or plant association listed as "S1" by the MTNHP.**			**AA does not contain previously cited rare types and structural diversity (#13) is high or contains plant association listed as "S2" by the MTNHP.**			**AA does not contain previously cited rare types or associations and structural diversity (#13) is low-moderate.**		
Estimated Relative Abundance from 11	☐rare	☐common	☐abundant	☐rare	☐common	☐abundant	☐rare	☒common	☐abundant
Low disturbance at AA (12i)	--	--	--	--	--	--	--	--	--
Moderate disturbance at AA (12i)	--	--	--	--	--	--	--	.3L	--
High disturbance at AA (12i)	--	--	--	--	--	--	--	--	--

Comments: _____

14L. RECREATION / EDUCATION POTENTIAL

i. Is the AA a known recreational or educational site? ☐ **Yes** [**Rate** ☐ **High (1.0)**, then proceed to 14L(ii) only] ☐ **No** [Proceed to 14L(iii)]

ii. Check categories that apply to the AA: ☐ Educational / scientific study ☐ Consumptive rec. ☐ Non-consumptive rec. ☐ Other

iii. Based on the location, diversity, size, and other site attributes, is there a strong potential for recreational or educational use?

☐ **Yes** [Proceed to 14L (ii) and then 14L(iv)] ☐ **No** [Rate as low in 14L(iv)]

iv. Rating Use the matrix below to arrive at the functional point and rating of high (H), moderate (M), or low (L) for this function.

Ownership	**Disturbance at AA from 12(i)**		
	☐ Low	☒ Moderate	☐ High
Public ownership	--	--	--
Private ownership	--	.3(L)	--

Comments: _____

FUNCTION, VALUE SUMMARY, AND OVERALL RATING

Function and Value Variables	Rating	Actual Functional Points	Possible Functional Points	Functional Units (Actual Points x Estimated AA Acreage)
A. Listed/Proposed T&E Species Habitat	low	0.50	1	
B. MT Natural Heritage Program Species Habitat	low	0.10	1	
C. General Wildlife Habitat	moderate	0.70	1	
D. General Fish/Aquatic Habitat	N/A	0.00	--	
E. Flood Attenuation	N/A	0.00	--	
F. Short and Long Term Surface Water Storage	high	1.00	1	
G. Sediment/Nutrient/Toxicant Removal	moderate	0.70	1	
H. Sediment/Shoreline Stabilization	moderate	0.70	1	
I. Production Export/Food Chain Support	moderate	0.70	1	
J. Groundwater Discharge/Recharge	high	1.00	1	
K. Uniqueness	low	0.30	1	
L. Recreation/Education Potential	low	0.30	1	
	Total:	**6.00**	**10.00**	____
		Percent of Total Possible Points:	**60%** (Actual / Possible) x 100 [rd to nearest whole #]	

Category I Wetland: (Must satisfy **one** of the following criteria. If not satisfied, proceed to Category II.)
- ☐ Score of 1 functional point for Listed/Proposed Threatened or Endangered Species; **or**
- ☐ Score of 1 functional point for Uniqueness; **or**
- ☐ Score of 1 functional point for Flood Attenuation **and** answer to Question 14E(ii) is "yes"; **or**
- ☐ Percent of total Possible Points is > 80%.

Category II Wetland: (Criteria for Category I not satisfied **and** meets any **one** of the following Category II criteria. If not satisfied, proceed to Category IV.)
- ☐ Score of 1 functional point for Species Rated S1, S2, or S3 by the MT Natural Heritage Program; **or**
- ☐ Score of .9 or 1 functional point for General Wildlife Habitat; **or**
- ☐ Score of .9 or 1 functional point for General Fish/Aquatic Habitat; **or**
- ☐ "High" to "Exceptional" ratings for **both** General Wildlife Habitat **and** General Fish / Aquatic Habitat; **or**
- ☐ Score of .9 functional point for Uniqueness; **or**
- ☐ Percent of total possible points is > 65%.

☒ **Category III Wetland:** (Criteria for Categories I, II, or IV not satisfied.)

Category IV Wetland: (Criteria for Categories I or II are not satisfied **and** all of the following criteria are met; If not satisfied, return to Category III.)
- ☐ "Low" rating for Uniqueness; **and**
- ☐ "Low" rating for Production Export / Food Chain Support; **and**
- ☐ Percent of total possible points is < 30%.

OVERALL ANALYSIS AREA (AA) RATING: (Check appropriate category based on the criteria outlined above.)

☐ **I** ☐ **II** ☒ **III** ☐ **IV**

Appendix C

2006 REPRESENTATIVE PHOTOGRAPHS

MDT Wetland Mitigation Monitoring
Kleinschmidt Creek
Montana

2006 KLEINSCHMIDT CREEK WETLAND MITIGATION SITE

Photo Point No. 1: View looking north near vegetation transect. Vegetation community types include upland, emergent and aquatic bed. types

Photo Point No. 1: View looking west towards upland vegetation adjacent to wetland corridor.

Photo Point No. 2: View looking east across excavated wetland and outer fringes. Fringe planted with riparian shrubs and trees. Excavated wetland dominated by emergent wetlands.

Photo Point No. 2: View looking southeast at the start of vegetation transect. Emergent vegetation developing in shallow waters.

Photo Point No. 4: View looking north at end of transect. Enhanced wetland pads dominated by herbaceous wetland species.

Photo Point No. 5: View looking south at the end of transect from opposite side of the reconstructed creek.

2006 KLEINSCHMIDT CREEK WETLAND MITIGATION SITE

Photo Point No. 6: View looking west across the mitigation site. Mitigation types include reconstructed channel, enhanced wetlands and excavated wetlands.

Photo Point No. 7: View looking northwest across smaller excavated wetland on lower section of the project. Shallow water dominated by aquatic and emergent vegetation.

Photo Point No. 8: View looking northwest along reconstructed channel on lower section.

Photo Point No. 9: View looking southeast along channel and adjacent wetlands dominated by emergent vegetation.

Photo Point No. 9: View looking northwest along the channel and emergent vegetation on lower section.

Photo Point No. 10: View looking northwest towards the end of mitigation site. Dry side slope area with increasing spotted knapweed cover values.

Photo Point No. 11: View looking northwest near lowest sections of mitigation site. Area dominated by emergent vegetation type.

Photo Point No. 3: Split panoramic view looking from west to east. Upper reaches of mitigation work. Area includes upland, excavated wetland, reconstructed channel and enhanced wetlands.

Appendix D

ORIGINAL SITE PLAN

MDT Wetland Mitigation Monitoring
Kleinschmidt Creek
Montana


KLEINSCHMIDT CREEK
STREAM AND WETLAND
RESTORATION PROJECT
NOTES:
1. AERIAL PHOTO AND LINE WORK ARE NOT PRECISELY GEOREFERENCED
2. SHRUB AND TREE REVEGETATION TO TAKE PLACE AT LOCALIZED AREAS THROUGHOUT EXISTING WETLANDS WITHIN EASEMENT BOUNDARY. EMPHASIS WILL BE PLACED ON REVEGETATING AREAS WHERE EXISTING HYDROLOGY AND SOILS APPEAR CONDUCIVE TO DEVELOPMENT OF SHRUB COMMUNITY.
Upper Reach Plan View
Scale: 1"=120'
N
E
W
S
PRESERVED EASEMENT AREA 12.66 ACRES (3.7 CREDIT ACRES * 4:1)
RESTORED WETLANDS 8.00 ACRES (8.00 CREDIT ACRES * 1)
CREATED WETLANDS 3.19 ACRES (1.9 CREDIT ACRES * 1:1)
HIGH INTENSITY ENHANCEMENT 8.05 Acres (4.02 CREDIT ACRES * 2:1)
LOW INTENSITY ENHANCEMENT 3.43 ACRES (1.14 CREDIT ACRES * 3:1)
RESTORED CREEK
EASEMENT BOUNDARY C.O.E No. 596
WETLAND LIMITS PER LAND + WATER 5-2-01
Photo Point Location
SEE BELOW
SEE ABOVE
EASEMENT BOUNDARY
WETLAND LIMITS PER LAND + WATER MAY 2, 2001
Highway 200
Lower Reach Plan View
Scale: 1"=120'
N
E
W
S
EASEMENT BOUNDARY
WETLAND LIMITS PER LAND AND WATER MAY 2, 2001
Highway 200

Appendix E

GPS PROTOCOL

MDT Wetland Mitigation Monitoring
Kleinschmidt Creek
Montana

GPS Mapping and Aerial Photo Referencing Procedure

The wetland boundaries, photograph location points and sampling locations were field located with mapping grade Trimble Geo III GPS units. The data was collected with a minimum of three positions per feature using Course/Acquisition code. The collected data was then transferred to a PC and differentially corrected to the nearest operating Community Base Station. The corrected data was then exported to ACAD drawings in Montana State Plain Coordinates NAD 83 international feet.

The GPS positions collected and processed had a 68% accuracy of 7 feet except in isolated areas of Tasks .008 and .011, where it went to 12 feet. This is within the 1 to 5 meter range listed as the expected accuracy of the mapping grade Trimble GPS.

Aerial reference points were used to position the aerial photographs. This positioning did not remove the distortion inherent in all photos; this imagery is to be used as a visual aide only. The located wetland boundaries were given a final review by the wetland biologist and adjustments were made if necessary.

Any relationship of features located to easement or property lines are not to be construed from these figures. These relationships can only be determined with a survey by a licensed surveyor.

Appendix F

2006 MACROINVERTEBRATE SAMPLING PROTOCOL AND DATA

MDT Wetland Mitigation Monitoring
Kleinschmidt Creek
Montana

AQUATIC INVERTEBRATE SAMPLING PROTOCOL

Equipment List

- D-frame sampling net with 1 mm mesh. Wildco is a good source of these.
- Spare net.
- 1-liter plastic sample jars, wide-mouth. VWR has these: catalog #36319-707.
- 95% ethanol: Northwest Scientific in Billings carries this.

All these other things are generally available at hardware or sporting goods stores. Make the labels on an ink jet printer preferably.

- hip waders.
- pre-printed sample labels (printed on Rite-in-the-Rain or other coated paper, two labels per sample).
- pencil.
- plastic pail (3 or 5 gallon).
- large tea strainer or framed screen.
- towel.
- tape for affixing label to jar.
- cooler with ice for sample storage.

Site Selection

Select the sampling site with these considerations in mind:

- Select a site accessible with hip waders. If substrates are too soft, lay a wide board down to walk on.
- Determine a location that is representative of the overall condition of the wetland.

Sampling

Wetland invertebrates inhabit the substrate, the water column, the stems and leaves of aquatic vegetation, and the water surface. Your goal is to sweep the collecting net through each of these habitat types, and then to combine the resulting samples into the 1-liter sample jar.

Dip out about a gallon of water into the pail. Pour about a cup of ethanol into the sample jar. Fill out the top half of the sample labels, using pencil, since ink will dissolve in the ethanol.

Ideally, you can sample a swath of water column from near-shore outward to a depth of approximately 3 feet with a long sweep of the net, keeping the net at about half the depth of the water throughout the sweep. Sweep the water surface as well. Pull the net through a vegetated area, beneath the water surface, for at least a meter of distance.

Sample the substrate by pulling the net along the bottom, bumping it against the substrate several times as you pull.

This step is optional, but it gives you a chance to <u>see</u> that you've collected some invertebrates. Rinse the net out into the bucket, and look for insects, crustaceans, etc. If necessary, repeat the sampling process in a nearby location, and add the net contents to the bucket. Remember to sample all four environments.

Sieve the contents of the bucket through the straining device and pour or carefully scrape the contents of the strainer into the sample jar.

If you skip the bucket-and-sieve steps, simply lift handfuls of material out of the sampling net into the jars. In either case, please include some muck or mud and some vegetation in the jar. Often, you will have collected a large amount of vegetable material. If this is the case, lift out handfuls of material from the sieve into the jar, until the jar is about half full. Please limit material you include in the sample, so that there is only a single jar for each sample.

Top off the sample jar with enough ethanol to cover all the material in the jar. Leave as little headroom as possible.

It is not necessary to sample habitats in any specified order. Keep in mind that disturbing the habitats prior to sampling will chase off the animals you are trying to capture.

Complete the sample labels. Place one label inside the sample jar and tape the other label securely to the outside of the jar. Dry the jar before attaching the outer label if necessary. In some situations, it may be necessary to collect more than one sample at a site. If you take multiple samples from the same site, clearly indicate this by using individual sample numbers, along with the total number of samples collected at the site (e.g. Sample #3 of 5 total samples).

Photograph the sampled site.

Sample Handling/Shipping

- In the field, keep collected samples cool by storing them in a cooler. Only a small amount of ice is necessary.
- Inventory all samples, preparing a list of all sites and enumerating all samples, before shipping or delivering to the laboratory.
- Deliver samples to Rhithron.

MDT Mitigated Wetland Monitoring Project: Aquatic Invertebrate Monitoring Summary 2001 – 2006

Prepared for PBS&J, Inc.
Prepared by W.Bollman, Rhithron Associates, Inc.

INTRODUCTION

Among other monitoring activities, aquatic invertebrate assemblages were collected at a number of mitigated wetlands throughout Montana. This report summarizes data generated from six years of collection. Over all years of sampling, a total of 182 invertebrate samples were collected. Table 2 summarizes sites and sampling years.

METHODS

Sample processing

Aquatic invertebrate samples were collected at mitigated wetland sites in the summer months of 2001, 2002, 2003, 2004, 2005 and 2006 by personnel of PBS&J, Inc. Sampling procedures utilized were based on the protocols developed by the Montana Department of Environmental Quality (MT DEQ). Sampling consisted of D-frame net sweeps through emergent vegetation (when present), the water column, and over the water surface, and included disturbing and scraping substrates at each sampled site. These sample components were composited and preserved in ethanol at each wetland site. Samples were delivered to Rhithron Associates, Inc. for processing, taxonomic determinations, and data analysis.

At Rhithron's laboratory, Caton subsamplers and stereomicroscopes with 10X magnification were used to randomly select a minimum of 100 organisms from each sample. In some instances, the entire sample contained fewer than 100 organisms; in these cases, all organisms from the sample were taken. Animals were identified to lowest practical taxonomic levels using relevant published resources. Quality control (QC) procedures were applied to sample sorting, taxonomic determinations and enumeration, and data entry. QC statistics are presented in Table 3. The identified samples have been archived at Rhithron's laboratory.

Assessment

The method employed to assess these wetlands is based on an index incorporating a battery of 12 bioassessment metrics or attributes (Table 1) tested and recommended by Stribling et al. (1995) in a report to the Montana Department of Health and Environmental Science. In that study, it was determined that some of the metrics were of limited use in some geographic regions, and for some wetland types. Despite that finding, all 12 metrics are used in this evaluation of mitigated wetlands, since detailed geographic information and wetland classifications were unavailable.

Scoring criteria for metrics were developed by generally following the tactic used by Stribling et al. Boxplots were generated using a statistical software package (Statistica™), and distributions, median values, ranges, and quartiles for each metric were examined. All sites in all years of sampling were used. Camp Creek, which was sampled in 2002, 2003, 2004, 2005 and 2006, and Kleinschmidt Creek, sampled in 2003, 2004, 2005 and 2006, were assessed using the tested metric battery developed for montane streams of Western Montana (Bollman 1998).Invertebrate assemblages at these sites differed from those of the other sites, and suggested montane or foothill stream conditions rather than wetland conditions. For the wetland sites, "optimal" scores were generally those that fell above the 75th percentile (for those metrics that decrease in value in response to stress) or below the 25th percentile (for metrics that respond to stress by an increase in value) of all scores. Additional scoring ranges were established by bisecting the range below the 75th percentile for decreasing scores (or above the 25th percentile for increasing scores) into "sub-optimal" and "poor" assessment categories. A score of 5, 3, or 1 was assigned to optimal, sub-optimal, and poor metric performance, respectively. In this way, metric values were translated into normalized metric scores, and scores for all metrics were summed to produce a total bioassessment score. Total bioassessment scores were classified according to a similar process, using the ranges and distributions of total scores for all sites studied in all years.

The purpose of constructing an index from biological attributes or metrics is to provide a means of integrating information to facilitate the determination of whether management action is needed. The nature of the action needed is not determined solely by the index score, however, but by consideration of an

analysis of the component metrics, the taxonomic composition of the assemblages, and other issues. The diagnostic functions of the metrics and taxonomic data need more study since our understanding of the interrelationships of natural environmental factors and anthropogenic disturbances is tentative. Thus, the further interpretive remarks accompanying the raw taxonomic and metric data in this summary are offered cautiously. Year-to-year comparisons depend on an assumption that specific sites were revisited in each year, and that equivalent sampling methods were utilized at each site revisit.

Bioassessment metrics

An index based on the performance of 12 metrics was constructed, as described above. Table 2 lists those metrics, describes their calculation and the expected response of each to increased degradation or impairment of the wetland.

In addition to the summed scores of each metric and the associated impairment classification described above, each individual metric informs the bioassessment to some degree. The four richness metrics (Total taxa, POET, Chironomidae taxa, and Crustacea taxa + Mollusca taxa) can be interpreted to express habitat complexity as well as water quality. Complex, diverse habitats consist of variable substrates, emergent vegetation, variable water depths and other factors, and are potential features of long-established stable wetlands with minimal human disturbance. In the study conducted by Stribling et al. (1995), all four richness metrics were found to be significantly associated with water quality parameters including conductance, salinity, and total dissolved solids.

Four composition metrics (%Chironomidae, %Orthocladiinae of Chironomidae, %Crustacea + %Mollusca, and %Amphipoda) measure the relative contributions of certain taxonomic groups that may have significant responses to habitat and/or water quality impacts. For example, amphipods have been demonstrated to increase in abundance in alkaline conditions. Short-lived, relatively mobile taxa such as chironomids dominate ephemeral environments; many are hemoglobin-bearers capable of tolerating de-oxygenated conditions.

Two tolerance metrics (the Hilsenhoff Biotic Index and %Dominant taxon) were included in the bioassessment battery. The HBI indicates the overall invertebrate assemblage tolerance to nutrient enrichment, warm water, and/or low dissolved oxygen conditions. The percent abundance of the dominant taxon has been demonstrated to be strongly associated with pH, conductance, salinity, total organic carbon, and total dissolved solids.

Two trophic measures (%Collector-gatherers and %Filterers) may be helpful in expressing functional integrity of the invertebrate assemblage, which can be impacted by poor water quality or habitat degradation. High proportions of filtering organisms suggest nutrient and/or organic enrichment, while abundant collectors suggest more positive functional conditions and well-developed wetland morphology. These organisms graze periphyton growing on stable surfaces such as macrophytes.

Metric scoring criteria were re-examined each year as new data was added. For 2005, all 151 records were utilized. Ranges of individual metrics, as well as median metric values remained remarkably consistent over all 5 years of analysis. Since metric value distributions changed insignificantly with the addition of the 2006 data, no changes were made to scoring criteria this year. Summary metric values and scores for the 2006 samples are given in Tables 3a-3d.

Quality control

Quality control procedures for initial sample processing and subsampling involved checking sorting efficiency. These checks were conducted on 100% of the samples by independent technicians who microscopically re-examined 20% of sorted substrate from each sample. All organisms that were missed were counted and this number was added to the total number obtained in the original sort. Sorting efficiency was evaluated by applying the following calculation:

$$SE = \frac{n_1}{n_2} \times 100$$

Where: SE is the sorting efficiency, expressed as a percentage, n_1 is the total number of specimens in the first sort, and n_2 is the total number of specimens in the first and second sorts combined.

Quality control procedures for taxonomic determinations involved checking accuracy, precision and enumeration. Four samples were randomly selected and all organisms re-identified by independent taxonomists. A Bray-Curtis similarity statistic (Bray and Curtis 1957) was generated to evaluate identifications.

Table 1. Montana Department of Transportation Mitigated Wetlands Monitoring Project sites. 2001 – 2006.

Site identifier	2001	2002	2003	2004	2005	2006
Beaverhead 1	+	+	+	+	+	+
Beaverhead 2	+	+				
Beaverhead 3	+	+		+	+	+
Beaverhead 4	+	+	+			
Beaverhead 5	+	+	+	+	+	+
Beaverhead 6	+	+	+	+	+	+
Big Sandy 1	+					
Big Sandy 2	+					
Big Sandy 3	+					
Big Sandy 4	+					
Johnson-Valier	+					
VIDA	+					
Cow Coulee	+	+	+			
Fourchette – Puffin	+	+	+	+		
Fourchette – Flashlight	+	+	+	+		
Fourchette – Penguin	+	+	+	+		
Fourchette – Albatross	+	+	+	+		
Big Spring	+	+	+	+	+	
Vince Ames	+					
Ryegate	+					
Lavinia	+					
Stillwater	+	+	+	+	+	
Roundup	+	+	+	+	+	+
Wigeon	+	+	+	+	+	+
Ridgeway	+	+	+	+	+	+
Musgrave – Rest. 1	+	+	+	+	+	+
Musgrave – Rest. 2	+	+	+	+	+	+
Musgrave – Enh. 1	+	+	+	+	+	+
Musgrave – Enh. 2	+					+
Hoskins Landing		+	+	+	+	
Hoskins Landing						
Peterson - 1		+	+	+	+	+
Peterson – 2		+		+	+	+
Peterson – 4		+	+	+	+	+
Peterson – 5		+	+	+	+	+
Jack Johnson - main		+	+			
Jack Johnson - SW		+	+			
Creston		+	+	+	+	
Lawrence Park		+				
Perry Ranch		+			+	
SF Smith River		+	+	+	+	+
Camp Creek		+	+	+	+	+
Camp Creek						+
Kleinschmidt		+	+	+	+	+
Kleinschmidt – stream			+	+	+	+
Ringling - Galt			+			
Circle				+		
Cloud Ranch Pond				+	+	
Cloud Ranch Stream				+		
American Colloid				+	+	+
Jack Creek				+	+	
Jack Creek						
Norem				+	+	+
Rock Creek Ranch					+	+
Wagner Marsh					+	+
Alkali Lake 1						+
Alkali Lake 2						+

Table 2. Aquatic invertebrate metrics employed in the MTDT mitigated wetland monitoring study, 2001-2005.

Metric	Metric calculation	Expected response to degradation or impairment
Total taxa	Count of unique taxa identified to lowest recommended taxonomic level	Decrease
POET	Count of unique Plecoptera, Trichoptera, Ephemeroptera, and Odonata taxa identified to lowest recommended taxonomic level	Decrease
Chironomidae taxa	Count of unique midge taxa identified to lowest recommended taxonomic level	Decrease
Crustacea taxa + Mollusca taxa	Count of unique Crustacea taxa and Mollusca taxa identified to lowest recommended taxonomic level	Decrease
% Chironomidae	Percent abundance of midges in the subsample	Increase
Orthocladiinae/Chironomidae	Number of individual midges in the sub-family Orthocladiinae / total number of midges in the subsample.	Decrease
%Amphipoda	Percent abundance of amphipods in the subsample	Increase
%Crustacea + %Mollusca	Percent abundance of crustaceans in the subsample plus percent abundance of molluscs in the subsample	Increase
HBI	Relative abundance of each taxon multiplied by that taxon's modified Hilsenhoff Biotic Index (tolerance) value. These numbers are summed over all taxa in the subsample.	Increase
%Dominant taxon	Percent abundance of the most abundant taxon in the subsample	Increase
%Collector-Gatherers	Percent abundance of organisms in the collector-gatherer functional group	Decrease
%Filterers	Percent abundance of organisms in the filterer functional group	Increase

RESULTS

(Note: Individual site discussions were removed from this report by PBS&J and are included in the macroinvertebrate sections of individual monitoring reports. Summary tables (4a – 4d) are provided on the following pages.)

.

Quality Assurance

Table 3 gives the results of quality assurance procedures for sample sorting and taxonomic determinations and enumeration.

Table 3. *Results of quality control procedures for subsampling and taxonomy.*

Sample ID	Site name	SE	Bray-Curtis similarity
MDT06PBSJ001	MUSGRAVE LAKE ES-1	91.67%	
MDT06PBSJ002	MUSGRAVE LAKE ES-2	94.44%	
MDT06PBSJ003	MUSGRAVE LAKE RS-1	87.30%	
MDT06PBSJ004	MUSGRAVE LAKE RS-2	100.00%	
MDT06PBSJ005	ROCK CREEK RANCH	96.49%	95.25%
MDT06PBSJ006	Alkali Lake Sample 1	100.00%	
MDT06PBSJ007	Alkali Lake Sample 2	100.00%	
MDT06PBSJ008	Peterson Ranch Pond # 4	100.00%	
MDT06PBSJ009	Peterson Ranch Pond # 1	97.35%	
MDT06PBSJ010	Peterson Ranch Pond # 5	91.67%	
MDT06PBSJ011	South Fork Smith River	100.00%	
MDT06PBSJ012	Beaverhead 1	100.00%	
MDT06PBSJ013	Beaverhead 3	95.65%	
MDT06PBSJ014	Beaverhead 5	100.00%	
MDT06PBSJ015	Beaverhead 6	94.12%	98.38%
MDT06PBSJ016	Peterson Ranch Pond # 2	91.67%	99.66%
MDT06PBSJ017	American Colloid	100.00%	
MDT06PBSJ018	Norem	100.00%	
MDT06PBSJ019	Cloud Ranch	85.56%	98.89%
MDT06PBSJ020	Jack Creek Pond	100.00%	
MDT06PBSJ021	Jack Creek Stream	100.00%	
MDT06PBSJ022	Camp Creek 1	99.10%	
MDT06PBSJ023	Camp Creek 2	100.00%	
MDT06PBSJ024	Kleinschmidt Pond	100.00%	
MDT06PBSJ025	Kleinschmidt Stream	96.49%	
MDT06PBSJ026	Hoskins Landing 1	97.35%	
MDT06PBSJ027	Hoskins Landing 2	96.49%	
MDT06PBSJ028	Wagner Marsh	100.00%	
MDT06PBSJ029	Wigeon Reservoir	100.00%	
MDT06PBSJ030	Ridgeway	98.21%	
MDT06PBSJ031	Roundup	100.00%	

Table 4a. Metric values and scores for Montana Department of Transportation mitigated wetland sites. 2006.

	BEAVERHEAD #1	BEAVERHEAD #3	BEAVERHEAD #5	BEAVERHEAD #6	ROUNDUP	WIDGEON	RIDGEWAY	MUSGRAVE RS-1
Total taxa	12	11	4	15	11	11	21	23
POET	1	0	1	3	2	1	3	4
Chironomidae taxa	5	3	1	7	4	3	10	7
Crustacea + Mollusca	1	4	2	3	2	2	5	7
% Chironomidae	52.38%	25.22%	0.69%	63.06%	18.87%	6.42%	37.25%	9.62%
Orthocladiinae/Chir	0.181818	0.965517	0	0.142857	0.2	0.285714	0.289474	0.7
%Amphipoda	0.00%	0.00%	0.00%	0.90%	0.00%	6.42%	11.76%	1.92%
%Crustacea + %Mollusca	9.52%	69.57%	98.62%	3.60%	73.58%	79.82%	45.10%	51.92%
HBI	7.857143	7.773913	7.97931	7.243243	8.09434	8.100917	7.127451	7.403846
%Dominant taxon	33.33%	39.13%	97.93%	27.93%	72.64%	73.39%	28.43%	23.08%
%Collector-Gatherers	61.90%	68.70%	100.00%	84.68%	87.74%	6.42%	49.02%	47.12%
%Filterers	0.00%	2.61%	0.00%	1.80%	0.00%	0.00%	0.00%	4.81%
Total taxa	1	1	1	3	1	1	5	5
POET	1	1	1	3	1	1	3	5
Chironomidae taxa	3	3	1	5	3	3	5	5
Crustacea + Mollusca	1	3	1	1	1	1	3	5
% Chironomidae	1	3	5	1	3	5	3	5
Orthocladiinae/Chir	1	5	1	1	3	3	3	5
%Amphipoda	5	5	5	5	5	3	3	5
%Crustacea + %Mollusca	5	1	1	5	1	1	3	3
HBI	1	1	1	3	1	1	3	3
%Dominant taxon	5	3	1	5	1	1	5	5
%Collector-Gatherers	3	3	5	5	5	1	3	3
%Filterers	3	3	3	3	3	3	3	3
Total score	30	32	26	40	28	24	42	52
Percent of maximum score	0.5	0.533333	0.433333	0.666667	0.466667	0.4	0.7	0.866667
Impairment classification	**poor**	**poor**	**poor**	**sub-optimal**	**poor**	**poor**	**optimal**	**optimal**

Table 4b. Metric values and scores for Montana Department of Transportation mitigated wetland sites. 2006.

	MUSGRAVE RS- 2	MUSGRAVE ES- 1	MUSGRAVE ES- 2	HOSKINS LANDING 1	HOSKINS LANDING 2	PETERSON RANCH 1	PETERSON RANCH 2	PETERSON RANCH 4	PETERSON RANCH 5
Total taxa	10	21	10	22	29	19	17	28	26
POET	1	2	1	5	4	2	2	3	4
Chironomidae taxa	2	7	4	6	6	7	4	13	9
Crustacea + Mollusca	3	6	0	5	9	5	6	5	6
% Chironomidae	3.96%	10.89%	10.00%	18.18%	11.71%	64.08%	7.48%	27.52%	14.29%
Orthocladiinae/Chir	0	0.181818	0.125	0.055556	0.307692	0.757576	0.75	0.6	0.75
%Amphipoda	0.00%	2.97%	0.00%	5.05%	1.80%	1.94%	22.43%	2.75%	15.18%
%Crustacea + %Mollusca	8.91%	75.25%	0.00%	20.20%	23.42%	8.74%	42.06%	19.27%	40.18%
HBI	6.326733	6.940594	6	7.111111	7.585586	6.631068	6.719626	7.293578	7.321429
%Dominant taxon	70.30%	38.61%	83.75%	25.25%	42.34%	47.57%	28.04%	20.18%	16.07%
%Collector-Gatherers	15.84%	8.91%	3.75%	64.65%	62.16%	72.82%	31.78%	34.86%	50.89%
%Filterers	0.00%	0.00%	0.00%	6.06%	5.41%	3.88%	3.74%	8.26%	0.89%
Total taxa	1	5	1	5	5	3	3	5	5
POET	1	1	1	5	5	1	1	3	5
Chironomidae taxa	1	5	3	3	3	5	3	5	5
Crustacea + Mollusca	1	5	1	3	5	3	5	3	5
% Chironomidae	5	5	5	3	5	1	5	3	5
Orthocladiinae/Chir	1	1	1	1	3	5	5	5	5
%Amphipoda	5	5	5	3	5	5	3	5	3
%Crustacea + %Mollusca	5	1	5	5	5	5	3	5	3
HBI	5	3	5	3	3	5	5	3	3
%Dominant taxon	1	3	1	5	3	3	5	5	5
%Collector-Gatherers	1	1	1	3	3	3	1	1	3
%Filterers	3	3	3	1	3	3	3	1	3
Total score	30	38	32	40	48	42	42	44	50
Percent of maximum score	0.5	0.633333	0.533333	0.666667	0.8	0.7	0.7	0.733333	0.833333
Impairment classification	**poor**	**sub-optimal**	**poor**	**sub-optimal**	**optimal**	**optimal**	**optimal**	**optimal**	**optimal**

Table 4c. Metric values and scores for Montana Department of Transportation mitigated wetland sites. 2006

	SOUTH FORK SMITH RIVER	CAMP CREEK 1*	CAMP CREEK 2*	KLEINSCH MIDT POND	KLEINSCH MIDT STREAM*	CLOUD RANCH	COLLOID	JACK CREEK POND	JACK CREEK STREAM
Total taxa	14	31	29	20	22	13	7	7	5
POET	4	8	8	5	1	1	2	0	0
Chironomidae taxa	3	10	8	6	8	6	4	4	0
Crustacea + Mollusca	4	1	3	2	5	3	0	2	2
% Chironomidae	18.02%	45.87%	16.07%	8.04%	77.68%	23.81%	84.21%	75.00%	0.00%
Orthocladiinae/Chir	0.05	0.26	0.277778	0.222222	0.448276	0.65	0.25	0.555556	0
%Amphipoda	18.02%	0.00%	0.00%	25.00%	0.00%	4.76%	0.00%	0.00%	5.00%
%Crustacea + %Mollusca	58.56%	0.92%	3.57%	25.89%	5.36%	11.90%	0.00%	16.67%	7.50%
HBI	7.540541	4.504587	4.294643	7.241071	5.928571	7.535714	6.315789	8.833333	7.325
%Dominant taxon	25.23%	24.77%	37.50%	25.00%	33.93%	36.90%	52.63%	33.33%	60.00%
%Collector-Gatherers	41.44%	48.62%	31.25%	62.50%	46.43%	64.29%	21.05%	58.33%	67.50%
%Filterers	15.32%	6.42%	7.14%	3.57%	38.39%	2.38%	0.00%	0.00%	0.00%
Total taxa	1	5	5	3	5	1	1	1	1
POET	5	5	5	5	1	1	1	1	1
Chironomidae taxa	3	5	5	3	5	3	3	3	1
Crustacea + Mollusca	3	1	1	1	3	1	1	1	1
% Chironomidae	3	1	5	5	1	3	1	1	5
Orthocladiinae/Chir	1	3	3	3	3	5	3	5	1
%Amphipoda	3	5	5	1	5	3	5	5	3
%Crustacea + %Mollusca	3	5	5	5	5	5	5	5	5
HBI	3	5	5	3	5	3	5	1	3
%Dominant taxon	5	5	3	5	5	3	1	5	1
%Collector-Gatherers	1	3	1	3	3	3	1	3	3
%Filterers	1	1	1	3	1	3	3	3	3
Total score	32	44	44	40	42	34	30	34	28
Percent of maximum score	0.533333	*0.733333*	*0.733333*	0.666667	*0.7*	0.566667	0.5	0.566667	0.466667
Impairment classification	**poor**	***optimal***	***optimal***	**sub-optimal**	***optimal***	**sub-optimal**	**poor**	**sub-optimal**	**poor**

*Sites indicated by asterisks were dominated by lotic fauna, and were evaluated with the MDEQ index for streams in the text and charts. Scores and impairment classifications in this table (italicized) are included only for completeness and are not reliable indications of conditions at these sites. See text.

Table 4d. Metric values and scores for Montana Department of Transportation mitigated wetland sites. 2006.

	NOREM	ROCK CREEK RANCH	WAGNER MARSH	ALKALI LAKE 1	ALKALI LAKE 2
Total taxa	6	15	11	6	5
POET	1	0	0	0	0
Chironomidae taxa	2	4	4	3	0
Crustacea + Mollusca	1	4	3	1	1
% Chironomidae	82.93%	8.40%	13.51%	42.86%	0.00%
Orthocladiinae/Chir	0	0.2	0.6	0.666667	0
%Amphipoda	0.00%	0.00%	0.00%	0.00%	0.00%
%Crustacea + %Mollusca	7.32%	65.55%	23.42%	7.14%	9.52%
HBI	7.317073	7.638655	7.036036	7.785714	7.904762
%Dominant taxon	65.85%	47.06%	45.95%	42.86%	52.38%
%Collector-Gatherers	68.29%	56.30%	47.75%	28.57%	9.52%
%Filterers	17.07%	0.00%	0.90%	0.00%	0.00%
Total taxa	1	3	1	1	1
POET	1	1	1	1	1
Chironomidae taxa	1	3	3	3	1
Crustacea + Mollusca	1	3	1	1	1
% Chironomidae	1	5	5	1	5
Orthocladiinae/Chir	1	3	5	5	1
%Amphipoda	5	5	5	5	5
%Crustacea + %Mollusca	5	1	5	5	5
HBI	3	1	3	1	1
%Dominant taxon	1	3	3	3	1
%Collector-Gatherers	3	3	3	1	1
%Filterers	1	3	3	3	3
Total score	24	34	38	30	26
Percent of maximum score	0.4	0.566667	0.633333	0.5	0.433333
Impairment classification	**poor**	**sub-optimal**	**sub-optimal**	**poor**	**poor**

Literature cited

Bollman, W. 1998. Montana Valleys and Foothill Prairies Ecoregion. Master's Thesis. (M.S.) University of Montana. Missoula, Montana.

Bukantis, R. 1998. Rapid bioassessment macroinvertebrate protocols: Sampling and sample analysis SOP's. Working draft. Montana Department of Environmental Quality. Planning Prevention and Assistance Division. Helena, Montana.

McCune, B. and J.B. Grace. 2002. Analysis of Ecological Communities. MjM Software Design, Gleneden Beach, Oregon, USA.

McCune, B. and M.J. Mefford. 2002. PC-ORD. Multivariate Analysis of Ecological Data, Version 4. MjM Software Design, Gleneden Beach, Oregon, USA.

Stribling, J.B., J. Lathrop-Davis, M.T. Barbour, J.S. White, and E.W. Leppo. 1995. Evaluation of environmental indicators for the wetlands of Montana: the multimetric approach using benthic macroinvertebrates. Report to the Montana Department of Health and Environmental Science. Helena, Montana.

Taxa Listing

Project ID: MDT06PBSJ
RAI No.: MDT06PBSJ024

RAI No.: MDT06PBSJ024 **Sta. Name:** Kleinschmidt Pond
Client ID:
Date Coll.: 8/16/2006 **No. Jars:** 1 **STORET ID:**

Taxonomic Name	Count	PRA	Unique	Stage	Qualifier	BI	Function
Non-Insect							
Enchytraeidae							
Enchytraeidae	7	6.25%	Yes	Unknown		4	CG
Glossiphoniidae							
Helobdella stagnalis	1	0.89%	Yes	Unknown		10	PR
Naididae							
Naididae	14	12.50%	Yes	Unknown		8	CG
Planorbidae							
Gyraulus sp.	1	0.89%	Yes	Unknown		8	SC
Talitridae							
Hyalella sp.	28	25.00%	Yes	Unknown		8	CG
Tubificidae							
Tubificidae	1	0.89%	Yes	Unknown		10	CG
Odonata							
Coenagrionidae							
Amphiagrion sp.	3	2.68%	Yes	Larva		7	PR
Enallagma sp.	22	19.64%	Yes	Larva		7	PR
Lestidae							
Lestes sp.	1	0.89%	Yes	Larva		9	PR
Ephemeroptera							
Baetidae							
Callibaetis sp.	15	13.39%	Yes	Larva		9	CG
Heteroptera							
Nepidae							
Ranatra sp.	1	0.89%	Yes	Larva		11	PR
Notonectidae							
Notonecta sp.	4	3.57%	Yes	Adult		5	PR
Trichoptera							
Leptoceridae							
Mystacides sp.	1	0.89%	Yes	Larva		4	CG
Diptera							
Ceratopogonidae							
Ceratopogoninae	4	3.57%	Yes	Larva		6	PR
Chironomidae							
Chironomidae							
Cladotanytarsus sp.	1	0.89%	Yes	Larva		7	CG
Corynoneura sp.	1	0.89%	Yes	Larva		7	CG
Cricotopus (Isocladius) sp.	1	0.89%	Yes	Larva		7	SH
Micropsectra sp.	2	1.79%	Yes	Larva		4	CG
Tanytarsini	1	0.89%	No	Larva	Early Instar	6	CF
Tanytarsus sp.	3	2.68%	Yes	Larva		6	CF
Sample Count	**112**						

Metrics Report

Project ID: MDT06PBSJ
RAI No.: MDT06PBSJ024
Sta. Name: Kleinschmidt Pond
Client ID:
STORET ID:
Coll. Date: 8/16/2006

Abundance Measures

Sample Count: 112
Sample Abundance: 560.00 20.00% of sample used

Coll. Procedure:
Sample Notes:

Taxonomic Composition

Category	R	A	PRA
Non-Insect	6	52	46.43%
Odonata	3	26	23.21%
Ephemeroptera	1	15	13.39%
Plecoptera			
Heteroptera	2	5	4.46%
Megaloptera			
Trichoptera	1	1	0.89%
Lepidoptera			
Coleoptera			
Diptera	1	4	3.57%
Chironomidae	5	9	8.04%



Dominant Taxa

Category	A	PRA
Hyalella	28	25.00%
Enallagma	22	19.64%
Callibaetis	15	13.39%
Naididae	14	12.50%
Enchytraeidae	7	6.25%
Notonecta	4	3.57%
Ceratopogoninae	4	3.57%
Tanytarsus	3	2.68%
Amphiagrion	3	2.68%
Micropsectra	2	1.79%
Tubificidae	1	0.89%
Tanytarsini	1	0.89%
Ranatra	1	0.89%
Corynoneura	1	0.89%
Cladotanytarsus	1	0.89%

Functional Composition

Category	R	A	PRA
Predator	7	36	32.14%
Parasite			
Collector Gatherer	9	70	62.50%
Collector Filterer	1	4	3.57%
Macrophyte Herbivore			
Piercer Herbivore			
Xylophage			
Scraper	1	1	0.89%
Shredder	1	1	0.89%
Omivore			
Unknown			



Metric Values and Scores

Metric	Value	BIBI	MTP	MTV	MTM
Composition					
Taxa Richness	19	1	2		1
Non-Insect Percent	46.43%				
E Richness	1	1		0	
P Richness	0	1		0	
T Richness	1	1		0	
EPT Richness	2		0		0
EPT Percent	14.29%		1		0
Oligochaeta+Hirudinea Percent	20.54%				
Baetidae/Ephemeroptera	1.000				
Hydropsychidae/Trichoptera	0.000				
Dominance					
Dominant Taxon Percent	25.00%		3		2
Dominant Taxa (2) Percent	44.64%				
Dominant Taxa (3) Percent	58.04%	3			
Dominant Taxa (10) Percent	91.07%				
Diversity					
Shannon H (loge)	2.263				
Shannon H (log2)	3.265		3		
Margalef D	3.822				
Simpson D	0.138				
Evenness	0.085				
Function					
Predator Richness	7		3		
Predator Percent	32.14%	5			
Filterer Richness	1				
Filterer Percent	3.57%			3	
Collector Percent	66.07%		2		2
Scraper+Shredder Percent	1.79%		0		0
Scraper/Filterer	0.250				
Scraper/Scraper+Filterer	0.200				
Habit					
Burrower Richness	1				
Burrower Percent	3.57%				
Swimmer Richness	3				
Swimmer Percent	17.86%				
Clinger Richness	2	1			
Clinger Percent	3.57%				
Characteristics					
Cold Stenotherm Richness	0				
Cold Stenotherm Percent	0.00%				
Hemoglobin Bearer Richness	3				
Hemoglobin Bearer Percent	5.36%				
Air Breather Richness	1				
Air Breather Percent	0.89%				
Voltinism					
Univoltine Richness	12				
Semivoltine Richness	0	1			
Multivoltine Percent	21.43%		3		
Tolerance					
Sediment Tolerant Richness	2				
Sediment Tolerant Percent	1.79%				
Sediment Sensitive Richness	0				
Sediment Sensitive Percent	0.00%				
Metals Tolerance Index	2.895				
Pollution Sensitive Richness	0	1		0	
Pollution Tolerant Percent	19.64%	3		1	
Hilsenhoff Biotic Index	7.315		0		0
Intolerant Percent	0.00%				
Supertolerant Percent	54.46%				
CTQa	100.500				

Bioassessment Indices

BioIndex	Description	Score	Pct	Rating
BIBI	B-IBI (Karr et al.)	18	36.00%	
MTP	Montana DEQ Plains (Bukantis 1998)	17	56.67%	Slight
MTV	Montana Revised Valleys/Foothills (Bollman 1998)	4	22.22%	Moderate
MTM	Montana DEQ Mountains (Bukantis 1998)	5	23.81%	Moderate



Taxa Listing

Project ID: MDT06PBSJ
RAI No.: MDT06PBSJ025

RAI No.: MDT06PBSJ025 **Sta. Name:** Kleinschmidt Stream
Client ID:
Date Coll.: 8/16/2006 **No. Jars:** 1 **STORET ID:**

Taxonomic Name	Count	PRA	Unique	Stage	Qualifier	BI	Function
Non-Insect							
Acari	1	0.89%	Yes	Unknown		5	PR
Copepoda	1	0.89%	Yes	Unknown		8	CG
Nematoda	5	4.46%	Yes	Unknown		5	PA
Ostracoda	2	1.79%	Yes	Unknown		8	CG
Enchytraeidae							
Enchytraeidae	1	0.89%	Yes	Unknown		4	CG
Lymnaeidae							
Lymnaeidae	1	0.89%	No	Immature		6	SC
Stagnicola sp.	1	0.89%	Yes	Unknown		6	SC
Naididae							
Naididae	3	2.68%	Yes	Unknown		8	CG
Physidae							
Physidae	1	0.89%	Yes	Unknown		8	SC
Heteroptera							
Corixidae							
Callicorixa sp.	2	1.79%	Yes	Adult		11	PR
Trichoptera							
Hydroptilidae							
Hydroptila sp.	3	2.68%	Yes	Larva		6	PH
Coleoptera							
Haliplidae							
Haliplus sp.	2	1.79%	Yes	Larva		5	PH
Diptera							
Stratiomyidae							
Caloparyphus sp.	1	0.89%	Yes	Larva		7	CG
Tipulidae							
Dicranota sp.	1	0.89%	Yes	Larva		3	PR
Chironomidae							
Chironomidae							
Micropsectra sp.	2	1.79%	Yes	Larva		4	CG
Orthocladiinae	1	0.89%	No	Larva	Early Instar	6	CG
Orthocladius sp.	27	24.11%	Yes	Larva		6	CG
Pagastia sp.	2	1.79%	Yes	Larva		1	CG
Parakiefferiella sp.	11	9.82%	Yes	Larva		6	CG
Potthastia Gaedii Gr.	1	0.89%	Yes	Larva		2	CG
Tanytarsini	5	4.46%	No	Larva	Early Instar	6	CF
Tanytarsus sp.	38	33.93%	Yes	Larva		6	CF
Sample Count	**112**						

Metrics Report

Project ID: MDT06PBSJ
RAI No.: MDT06PBSJ025
Sta. Name: Kleinschmidt Stream
Client ID:
STORET ID:
Coll. Date: 8/16/2006

Abundance Measures

Sample Count: 112
Sample Abundance: 1,680.00 6.67% of sample used

Coll. Procedure:
Sample Notes:

Taxonomic Composition

Category	R	A	PRA
Non-Insect	8	16	14.29%
Odonata			
Ephemeroptera			
Plecoptera			
Heteroptera	1	2	1.79%
Megaloptera			
Trichoptera	1	3	2.68%
Lepidoptera			
Coleoptera	1	2	1.79%
Diptera	2	2	1.79%
Chironomidae	6	87	77.68%



Dominant Taxa

Category	A	PRA
Tanytarsus	38	33.93%
Orthocladius	27	24.11%
Parakiefferiella	11	9.82%
Tanytarsini	5	4.46%
Nematoda	5	4.46%
Naididae	3	2.68%
Hydroptila	3	2.68%
Pagastia	2	1.79%
Ostracoda	2	1.79%
Micropsectra	2	1.79%
Haliplus	2	1.79%
Callicorixa	2	1.79%
Physidae	1	0.89%
Caloparyphus	1	0.89%
Acari	1	0.89%

Functional Composition

Category	R	A	PRA
Predator	3	4	3.57%
Parasite	1	5	4.46%
Collector Gatherer	10	52	46.43%
Collector Filterer	1	43	38.39%
Macrophyte Herbivore			
Piercer Herbivore	2	5	4.46%
Xylophage			
Scraper	2	3	2.68%
Shredder			
Omivore			
Unknown			



Metric Values and Scores

Metric	Value	BIBI	MTP	MTV	MTM
Composition					
Taxa Richness	19	1	2		1
Non-Insect Percent	14.29%				
E Richness	0	1		0	
P Richness	0	1		0	
T Richness	1	1		0	
EPT Richness	1		0		0
EPT Percent	2.68%		0		0
Oligochaeta+Hirudinea Percent	3.57%				
Baetidae/Ephemeroptera	0.000				
Hydropsychidae/Trichoptera	0.000				
Dominance					
Dominant Taxon Percent	33.93%		2		2
Dominant Taxa (2) Percent	58.04%				
Dominant Taxa (3) Percent	67.86%	3			
Dominant Taxa (10) Percent	87.50%				
Diversity					
Shannon H (loge)	2.033				
Shannon H (log2)	2.934		2		
Margalef D	3.868				
Simpson D	0.207				
Evenness	0.092				
Function					
Predator Richness	3		1		
Predator Percent	3.57%	1			
Filterer Richness	1				
Filterer Percent	38.39%			0	
Collector Percent	84.82%		1		0
Scraper+Shredder Percent	2.68%		0		0
Scraper/Filterer	0.070				
Scraper/Scraper+Filterer	0.065				
Habit					
Burrower Richness	1				
Burrower Percent	0.89%				
Swimmer Richness	2				
Swimmer Percent	3.57%				
Clinger Richness	2	1			
Clinger Percent	36.61%				
Characteristics					
Cold Stenotherm Richness	0				
Cold Stenotherm Percent	0.00%				
Hemoglobin Bearer Richness					
Hemoglobin Bearer Percent					
Air Breather Richness	2				
Air Breather Percent	1.79%				
Voltinism					
Univoltine Richness	7				
Semivoltine Richness	1	1			
Multivoltine Percent	88.39%		0		
Tolerance					
Sediment Tolerant Richness	2				
Sediment Tolerant Percent	2.68%				
Sediment Sensitive Richness	0				
Sediment Sensitive Percent	0.00%				
Metals Tolerance Index	3.943				
Pollution Sensitive Richness	1	1		1	
Pollution Tolerant Percent	8.04%	5		2	
Hilsenhoff Biotic Index	5.855		2		0
Intolerant Percent	2.68%				
Supertolerant Percent	6.25%				
CTQa	98.143				

Bioassessment Indices

BioIndex	Description	Score	Pct	Rating
BIBI	B-IBI (Karr et al.)	16	32.00%	
MTP	Montana DEQ Plains (Bukantis 1998)	10	33.33%	Moderate
MTV	Montana Revised Valleys/Foothills (Bollman 1998)	3	16.67%	Severe
MTM	Montana DEQ Mountains (Bukantis 1998)	3	14.29%	Severe



Thursday, September 14, 2006

Appendix G

PLANTING SPECIFICATIONS

MDT Wetland Mitigation Monitoring
Kleinschmidt Creek
Montana

Kleinschmidt Plantings Fall 2001, Spring & Fall 2002

Willow planting:

Fall 2001 sprigging
6000

Containerized seedlings:

Scientific name	Common Name	Fall 2001	Spring 20002	Fall 2002	Total
Alnus incana	Alder	250	1250	0	**1500**
Betula glandulosa	Bog birch	0	700	0	**700**
Cornus stolonifera	Dogwood	0	0	1250	**1250**
Crataegus douglasii	Hawthorne	250	0	1250	**1500**
Populus tremuloides	Quaking Aspen	0	1000	0	**1000**
Populus trichocarpa	Black cottonwood	0	500	0	**500**
Rosa woodsii	Woods rose	0	250	0	**250**
Salix boothii	Booth's willow	250	1000	0	**1250**
Salix lutea	Yellow willow	250	1250	0	**1500**
Salix bebbiana	Bebb's willow	0	1200	0	**1200**
Salix drummondia	Drummonds willow	0	1000	0	**1000**
Salix geyeriana	Geyer willow	0	1250	0	**1250**
		1000	9400	2500	**12900**