


INDEX

T.24N. R.4E. W.M.
City of Seattle

SHEET NO.	PLAN REFERENCE NO.	TITLE
1	INVM1	INDEX AND VICINITY MAP
2-3	S01-502	SUMMARY OF QUANTITIES
4	TCEE1	TEMPORARY CONSTRUCTION EASEMENT EXHIBIT
5-6	SP1-SP2	SITE PREPARATION
7	UT1	EXISTING UTILITIES
8	UT2	WATER MAIN THRUST COLLAR
9-11	EM1-EM3	ENVIRONMENTAL COMPLIANCE NOTES
12	EM4	ENVIRONMENTAL COMPLIANCE DETAIL
13	EC1	TESC PLAN
14	UT3	STORM DRAIN RELOCATION
15	DD1	DRAINAGE DETAILS
16	LSMK1	LANDSCAPE/PAVEMENT MARKINGS
17	PV1	PAVING PLAN
18	BRIDGE SHEET 1	LAYOUT - PLAN
19	BRIDGE SHEET 2	ELEVATION
20	BRIDGE SHEET 3	PILE LAYOUT - BENTS 93 & 94
21	BRIDGE SHEET 4	PLAN TEMPORARY SUPPORT SYSTEM
22	BRIDGE SHEET 5	STAGE 1 PILES BENTS 93 & 94
23-26	BRIDGE SHEETS 6-9	TEMPORARY SUPPORT SYSTEM SECTIONS AND DETAILS
27	BRIDGE SHEET 10	REMOVAL DETAILS - BENT 93
28	BRIDGE SHEET 11	BENT 93 DONEL PLACEMENT PLAN
29-31	BRIDGE SHEETS 12-14	BENT 93 FOOTING DETAILS
32	BRIDGE SHEET 15	REMOVAL DETAILS - BENT 94
33	BRIDGE SHEET 16	BENT 94 DONEL PLACEMENT PLAN
34-36	BRIDGE SHEETS 17-19	BENT 94 FOOTING DETAILS
37	BRIDGE SHEET 20	BEAM REPAIRS
38	BRIDGE SHEET 21	BARLIST
39-40	TC1-TC2	TRAFFIC CONTROL PLAN



END ER-0101(304)
END PROJECT
SR99 MP 31.06
STA. 83+24.96

BEGIN ER-0101(304)
BEGIN PROJECT
SR99 MP 31.05
STA. 83+93.50

NOTE: ALL SHEET REFERENCES, FIRST NOS. OF STRUCTURE CODE DESIGNATIONS AND MATCH LINE SHEET REFERENCES, ETC., THROUGHOUT THE PLANS, REFER TO THE ENTRY IN THE PLAN REFERENCE NUMBER BOX.

PLAN REFERENCE NO.	SHEET OF SHEETS

FILE NAME	C:\AAWork\pwork\AWV\GonzoiY\dms03626\1.3082.PS_INV.M.dgn		
TIME	1:49:30 PM	STATE	FED. AID PROJ. NO.
DATE	7/30/2007	10 WASH	ER-0101(304)
PLOTTED BY	GONZOIY	JOB NUMBER	07805
DESIGNED BY	R. A. BEAN	CONTRACT NO.	
CHECKED BY	Y. GONZALEZ	LOCATION NO.	
PROJ. ENGR.	P. LACY		
REGIONAL ADM.	D. DYE		

INVM1	SR 99	YESLER WAY VICINITY	INDEX AND VICINITY MAP
		FOUNDATION STABILIZATION	



Washington State
Department of Transportation

SR 99
YESLER WAY VICINITY
FOUNDATION STABILIZATION

INDEX AND VICINITY MAP

SHEET 1 OF 40 SHEETS

SUMMARY OF QUANTITIES

DOT_RGG900
8/15/2007

ITEM NO	TOTAL QUANTITY	SUB-TOTAL SECTION 147.2(1) OF STANDARD SPECS	SUB-TOTAL SECTION 147.2(2) OF STANDARD SPECS	STD. ITEM NO.	UNIT	ITEM	GROUP 1 BENTS	GROUP 2 THIRD PARTY DAMAGE
						PREPARATION		
1	LUMP SUM	LUMP SUM	0001	L.S.	MOBILIZATION		L.S.	
2	LUMP SUM	LUMP SUM	0035	L.S.	CLEARING AND GRUBBING		L.S.	
3	LUMP SUM	LUMP SUM	0050	L.S.	REMOVAL OF STRUCTURE AND OBSTRUCTION		L.S.	
4	LUMP SUM	LUMP SUM	0061	L.S.	REMOVING PORTION OF EXISTING BRIDGE NO. 99/540		L.S.	
5	387.00	387.00		C.Y.	CONTAMINATED MATERIAL EXCAVATION INCL. HAUL		387.00	
6	846.00	846.00		TON	DISPOSAL OF CONTAMINATED MATERIAL		846.00	
7	LUMP SUM	LUMP SUM		L.S.	GRADING		L.S.	
8	540.00	540.00	0431	TON	WATERFRONT PEDESTRIAN/BICYCLE FACILITY GRAVEL BORROW INCL. HAUL		540.00	
9	290.00	290.00	0470	C.Y.	EMBANKMENT COMPACTION		290.00	
10	200.00	200.00	1170	L.F.	DRAINAGE DRAIN PIPE 6 IN. DIAM.		200.00	
11	LUMP SUM	LUMP SUM		L.S.	WATER LINES WATER MAIN CONC. THRUST COLLAR AND MECH. JT. RESTRAINTS		L.S.	
12	LUMP SUM	LUMP SUM	4013	L.S.	STRUCTURE SHORING OR EXTRA EXCAVATION CL. A - PIERS 93 & 94		L.S.	
13	88.00	88.00		EACH	MICROPILE		88.00	
14	2.00	2.00		EACH	MICROPILE VERIFICATION LOAD TESTING		2.00	
15	8.00	8.00		EACH	MICROPILE PROOF LOAD TESTING		8.00	
16	43900.00	43900.00	4148	LB.	ST. REINF. BAR FOR BRIDGE		43900.00	
17	266.00	266.00	4322	C.Y.	CONC. CLASS 4000 FOR BRIDGE		266.00	
18	-1.00	-1.00	4219	DOL	DEFICIENT STRENGTH CONC. PRICE ADJUSTMENT		-1.00	
19	LUMP SUM	LUMP SUM		L.S.	FURNISHING, INSTALLING, & REMOVING TEMP. SUPPORT SYS.		L.S.	
20	44.00	44.00	5100	TON	SURFACING CRUSHED SURFACING BASE COURSE		44.00	
21	130.00	130.00	5739	TON	HOT MIX ASPHALT HMA FOR PAVEMENT REPAIR CL. 1/2 IN. PG 64-22		130.00	
22	LUMP SUM	LUMP SUM	6071	L.S.	IRRIGATION AND WATER DISTRIBUTION IRRIGATION SYSTEM		L.S.	
23	4.00	4.00	6400	C.Y.	EROSION CONTROL AND PLANTING TOPSOIL TYPE C		4.00	
24	45.00	45.00	6403	DAY	ESC LEAD		45.00	
25	90.00	90.00	6470	HOUR	STREET CLEANING		90.00	
26	2.00	2.00	6471	EACH	INLET PROTECTION		2.00	
27	450.00	450.00	6472	L.F.	TEMPORARY CURB		450.00	
28	129000.00	129000.00	6490	DOL	EROSION/WATER POLLUTION CONTROL		129000.00	
29	8.00	8.00	6552	EACH	PSIPE SHRUBBERY JAPANESE HOLLY 2 GALLON		8.00	
30	15.00	15.00	6552	EACH	PSIPE SHRUBBERY DAYLILIES 1 GALLON		15.00	
31	15.00	15.00	6552	EACH	PSIPE SHRUBBERY JOHNSWORT 1 GALLON		15.00	

GROUP LEGEND :

GROUP NUMBER	SR	CONTROL SECTION	TAX SCHEDULE	FUND PARTICIPANTS
1	099	179101	*	FEDERAL,TPA
2	099	179101	*	STATE

08/14/07 REVISED BID ITEMS 8, 10, 28, 34, 48, ADDED 52, 53.		SS	REGION	STATE	FEDERAL AID PROJECT NO.
		10	WA	ER-0101(304)	
				JOB NUMBER	
				07A805/6	
				CONTRACT NO	
				007402	
DATE			REVISION		
Washington State Department of Transportation					SR 99
YESLER WAY VICINITY FOUNDATION STABILIZATION					SQ1
SUMMARY OF QUANTITIES					SHEET 2 OF 40 SHEETS

SUMMARY OF QUANTITIES

DOT_RGG900
8/15/2007

ITEM NO	TOTAL QUANTITY	SUB-TOTAL SECTION 1-07.2(1) OF STANDARD SPECS	SUB-TOTAL SECTION 1-07.2(2) OF STANDARD SPECS	STD. ITEM NO.	UNIT	ITEM	GROUP 1 BENTS	GROUP 2 THIRD PARTY DAMAGE
32	2.00	2.00		6580	C.Y.	BARK OR WOOD CHIP MULCH	2.00	
						TRAFFIC		
33	132.00	132.00		6707	L.F.	CEMENT CONC. PEDESTRIAN CURB	132.00	
34	600.00	600.00		6806	L.F.	PAINT LINE	600.00	
35	LUMP SUM	LUMP SUM		6971	L.S.	PROJECT TEMPORARY TRAFFIC CONTROL	L.S.	
						OTHER ITEMS		
36	721.00	721.00		7008	S.F.	SHORING OR EXTRA EXCAVATION CLASS B	721.00	
37	22.00	22.00		7013	C.Y.	GRAVEL BACKFILL FOR PIPE BEDDING	22.00	
38	5.00	5.00		9606	EACH	CONNECTION TO DRAINAGE STRUCTURE	5.00	
39	LUMP SUM	LUMP SUM		7350	L.S.	CLEANING EXISTING DRAINAGE STRUCTURE	L.S.	
40	10000.00	10000.00		7480	DOL	ROADSIDE CLEANUP	10,000.00	
41	50000.00	50000.00		7715	DOL	FORCE ACCOUNT BEAM REPAIR	50,000.00	
42	25000.00	25000.00		7715	DOL	FORCE ACCOUNT EPOXY CRACK SEALING	25,000.00	
43	77400.00	77400.00			DOL	ARCHAEOLOGICAL AND HISTORICAL SALVAGE	77,400.00	
44	5.00	5.00		7725	DOL	REIMBURSEMENT FOR THIRD PARTY DAMAGE	5.00	
45	-1.00	-1.00		7728	DOL	MINOR CHANGE	-1.00	
46	LUMP SUM	LUMP SUM		7736	L.S.	SPOC PLAN	L.S.	
47	LUMP SUM	LUMP SUM			L.S.	DEWATERING SYSTEM	L.S.	
48	3.00	3.00			MO.	MAINTENANCE AND OPERATION OF DEWATERING SYSTEM	3.00	
49	830.00	830.00			L.F.	TEMPORARY CONSTRUCTION FENCE	830.00	
50	LUMP SUM	LUMP SUM			L.S.	CONSTRUCTION SHIELD	L.S.	
51	LUMP SUM	LUMP SUM			L.S.	VIBRATION MONITORING	L.S.	
52	130.00	130.00		1171	L.F.	DRAIN PIPE 8 IN. DIAM.	130.00	
53	2.00	2.00			EACH	JUNCTION BOX FOR DRAINS	2.00	


GROUP LEGEND :

GROUP NUMBER	SR	CONTROL SECTION	TAX SCHEDULE	FUND PARTICIPANTS
1	069	179101	*	FEDERAL, TPA
2	069	179101	*	STATE

08/14/07 REVISED BID ITEMS 6, 10, 28, 34, 48, ADDED 52, 53	FEDERAL AID PROJECT. NO. ER-0101(304)	SQ2	SHEET 3 OF 40 SHEETS
Washington State Department of Transportation		SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION	
DATE		SUMMARY OF QUANTITIES	
REVISION		BY	
CONTRACT NO 07A80518		CONTRACT NO 007402	
JOB NUMBER 07A80518		STATE WA	
REGION 10		FUND PARTICIPANTS	

T.24N. R.4E. W.M.
City of Seattle

WESTERN AVE.



- LEGEND**
- EXISTING EASEMENT
 - CENTERLINE
 - TEMPORARY CONSTRUCTION EASEMENT
 - TEMPORARY CONSTRUCTION FENCE
 - PARCEL NUMBER




NOTE: THE BASIS OF BEARINGS AND DISTANCES ARE DETERMINED FROM WASHINGTON STATE PLANE COORDINATE SYSTEM NORTH ZONE (NAD 83/91, NAVD 1988). THE DISTANCES SHOWN ARE GROUND DISTANCES.

FILE NAME: C:\AWORK\PRWOK\AW\Gonzalez\dms03626\12219_MC_ICEE.dgn		REGION NO. 10	STATE WASH	FED. AID PROJ. NO.		P.E. STAMP BOX DATE: 7/24/07	
TIME: 1:40:03 PM	DATE: 7/24/2007	JOB NUMBER: 67805	CONTRACT NO.	LOCATION NO.			
DESIGNED BY: P. TSE	ENTERED BY: Y. GONZALEZ	DATE:	BY:	REVISION:			
CHECKED BY: K. JONES	PROJ. ENGR.: P. LACY						
REGIONAL ADM.: D. DYE							
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION TEMPORARY CONSTRUCTION EASEMENT EXHIBIT						TCEE1	
						SHEET 4 OF 46 SHEETS	




SCALE IN FEET
0 20 40

T.24N. R.4E. W.M. City of Seattle



LEGEND


- EXISTING RETAINING WALL
- EXISTING RAIL
- EXISTING EASEMENT
- EXISTING WOODEN GUARD RAIL
- TREE
- SHRUBS
- PARKING PAY STATION
- EXISTING PRECAST CONCRETE CURB
- EXISTING DOWNSPOUT
- EXISTING BOLLARD
- PATH LOCATION
- EDGE LINE
- TROLLEY SUPPORT PULL/STREET LIGHT
- TEST BORING LOCATION
- EXISTING SIGN, ONE POST
- EXISTING CATCH BASIN
- EXISTING MANHOLE
- EXISTING CONDUIT W/ JUNCTION BOX
- EXISTING DOWNSPOUT
- REMOVE PAVEMENT AND EXCAVATION LIMITS
- CONCRETE PARKING METER FOUNDATION
- EXISTING 6" SANITARY SEWER (ABANDONED)
- EXISTING 6" STORM DRAIN
- TEMPORARY CONSTRUCTION FENCE



GENERAL NOTES:

- EXISTING PATH MUST REMAIN OPEN DURING CONSTRUCTION OF THE WATERFRONT PEDESTRIAN/ BICYCLE FACILITY
- PLACE CONSTRUCTION GEOTEXTILE BETWEEN THE EXISTING BALLAST/WATERFRONT STREET CAR RAILS AND CRUSHED SURFACING ALONG THE LENGTH OF THE WATERFRONT PEDESTRIAN/BICYCLE FACILITY.
- SEE STANDARD PLANS H-13A, FOR BOLLARD TYPE II DETAILS.
- ALL DEPTHS ARE COMPACTED DEPTHS.
- ALL UTILITIES SHALL REMAIN, EXCEPT AS NOTED.
- NO OVER EXCAVATION WILL BE ALLOWED.
- MSDOT BRIDGE PRESERVATION WILL INSPECT BRIDGE FOOTINGS AFTER EXCAVATION. THE CONTRACTOR SHALL PROVIDE 3 DAYS NOTIFICATION PRIOR TO THE START OF EXCAVATION.





FILE NAME: C:\AAWOK\APW\WOK\K\AWV\Gonzalv\dms03962\AD_L3082_PS.SP_01.dgn		REGION: 10	STATE: WASH	FED.AID PROJ.NO.	DATE: 8/14/07
TIME: 10:46:43 AM	DATE: 8/15/2007	JOB NUMBER: 07A805	CONTRACT NO.	LOCATION NO.	REVISIONS: SHADED
DESIGNED BY: S. SOBANI	ENTERED BY: K. IRELAND	DATE: 8/14/07	BY: K.I.	REVISION:	
CHECKED BY: S. SOBANI	PROJ. ENGR. P. LACY				
REGIONAL ADM. D. DYE					



Washington State
Department of Transportation

SR 99
YESLER WAY VICINITY
FOUNDATION STABILIZATION
SITE PREPARATION

SHEET 5 OF 40 SHEETS



DOWNSPOUT REMOVAL DETAIL
N.T.S.

GENERAL NOTES:


- 8. QUANTITIES FOR INFORMATION ONLY:
 - REMOVE ASPHALT CONCRETE AND/OR PCC PAVEMENT 2,850 SQ. FT.
 - REMOVE OLD PARKING METER FOUNDATIONS 3
 - REMOVE NEW PARKING PAY STATIONS BY OTHERS
 - REMOVE PRECAST CONCRETE CURB 132 LF.
 - REMOVE ABANDONED RAILS 212 LF.
 - REMOVE TREES 3 @ 50 FT. TALL
 - REMOVE SHRUBS 1
 - REMOVE BURIED IRRIGATION SYSTEM (UNDERGROUND EXTENTS UNKNOWN) 52 LF.
 - REMOVE ABANDONED 6" SANITARY SEWER, 52 LF.
 - REMOVE EXISTING 6" PVC STORM DRAIN 52 LF.
- 9. REMOVE ABANDONED GAS LINE AND 6" DRAIN LINE IN EXCAVATION SITES.
- 10. ALL EXISTING UTILITIES NOT SHOWN FOR CLARITY. REFER TO SHEET UT1 FOR APPROXIMATE LOCATION OF ALL EXISTING UTILITIES.
- 11. PARKING SPACES NOT SHOWN FOR CLARITY. WITHIN THE WORK ZONE, THE MAXIMUM NUMBER OF PARKING SPACES IMPACTED BY CONSTRUCTION ACTIVITIES IS LIMITED TO 22 PUBLIC SPACES AND 22 PRIVATE SPACES. INSTALL TEMPORARY CONSTRUCTION FENCE AS SHOWN. REFER TO SHEET LSWK1 FOR LAYOUT AND LOCATION OF IMPACTED PARKING SPACES.
- 12. PROVIDE THE ENGINEER AT LEAST (7) SEVEN WORKING DAYS IN ADVANCE OF THE PAY STATION REMOVAL START DATE.

BENT DIMENSION DETAIL
BENT 93/94

ELEVATION PIERS 94E & 94W

ELEVATION PIERS 93E & 93W

SECTION: A-A
• APPROXIMATE ELEVATIONS BASED ON AVAILABLE AS-BUILT AND TEST HOLE DATA.



LEGEND


- EXISTING RETAINING WALL
- EXISTING RAIL
- EXISTING EASEMENT
- EXISTING WOODEN GUARD RAIL
- TREE
- SHRUBS
- PARKING PAY STATION
- EXISTING PRECAST CONCRETE CURB
- EXISTING DOWNSPOUT
- EXISTING BOLLARD
- TROLLEY SUPPORT PULL/STREET LIGHT
- TEST BORING LOCATION
- EXISTING SIGN, ONE POST
- EXISTING CATCH BASIN
- EXISTING MANHOLE
- EXISTING CONDUIT W/ JUNCTION BOX
- EXISTING DOWNSPOUT
- REMOVE PAVEMENT AND EXCAVATION LIMITS
- CONCRETE PARKING METER FOUNDATION
- EXISTING 6" SANITARY SEWER (ABANDONED)
- EXISTING 6" STORM DRAIN
- TEMPORARY CONSTRUCTION FENCE
- PATH LOCATION

FILE NAME: C:\AAWOT\K\PWOT\K\AW\Gonzalez\dms03962\AD_L3082_PS_SP_02.dgn		REGION NO. 10	STATE WASH	FED. AID PROJ. NO.
TIME 10:47:54 AM	DATE 8/15/2007	JOB NUMBER 07A805	CONTRACT NO.	LOCATION NO.
PLOTTED BY gonzalez	DESIGNED BY R. A. BEAN	ENTERED BY Y. GONZALEZ	CHECKED BY K. JONES	REVISIONS SHADED
PROJ. ENGR. P. LACY	REGIONAL ADM. D. DYE	DATE 8/14/07	DATE 8/15/07	BY
Washington State Department of Transportation		SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION		
SP2		SHEET 6 OF 40 SHEETS		
SITE PREPARATION		DATE		

T.24N. R.4E. W.M. City of Seattle


LEGEND

---W---	EXISTING WATER LINE
---ST---	EXISTING STORM DRAIN
---S---	EXISTING SANITARY SEWER
---BT---	EXISTING BURIED TELEPHONE
---BF---	EXISTING BURIED FIBER
---BP---	EXISTING BURIED POWER
---G---	EXISTING GAS
---	EXISTING FIBER OPTIC DUCT
---	EXISTING IRRIGATION
---	EXISTING UNKNOWN UTILITY
---	EXISTING THRUST BLOCK
⊗	POTHOLE
⊠	ELECTRICAL BOX METER
---	EXISTING EASEMENT




GENERAL NOTES:

- UTILITIES ARE SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR ONLY. DEPTH AND LOCATIONS SHOWN ARE APPROXIMATE AND ARE TAKEN FROM EXISTING RECORDS AND LIMITED TEST HOLE INFORMATION. A MINIMUM OF TWO (2) WORKING DAYS PRIOR TO ANY EXCAVATION, USE THE "ONE CALL" TELEPHONE NUMBER (1-800-424-5555) AND OTHER METHODS AS NECESSARY TO DETERMINE THE LOCATIONS OF THE UTILITIES.
- REFER TO SHEET SP2 FOR REMOVAL QUANTITY OF ABANDONED 6" SANITARY SEWER.
- 110 V SINGLE PHASE TO BE REMOVED WITHIN EXCAVATED AREAS. WIRING TO BE LEFT ABANDONED UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- REMOVE INACTIVE GAS LINE WITHIN EXCAVATED AREAS.




OVERHEAD UTILITY CLEARANCE DETAIL

BENT 93/94 FACING NORTH



FILE NAME	C:\A\work\KIP\work\AWV\Gonzalez\Gms03962\AD-L3082.PS-UT-01.dgn
TIME	10:49:15 AM
DATE	8/15/2007
PLOTTED BY	gonzalez
DESIGNED BY	R. A. BEAN
ENTERED BY	Y. GONZALEZ
CHECKED BY	K. JONES
PROJ. ENGR.	P. LACY
REGIONAL ADM.	D. DYE
STATE	10 WASH
CONTRACT NO.	074805
DATE	8/14/07 YG
BY	
REVISIONS	SHADED REVISION
FED. AID PROJ. NO.	
REGION NO.	
CONTRACT NO.	
LOCATION NO.	



Washington State
Department of Transportation


SR 99
YESLER WAY VICINITY
FOUNDATION STABILIZATION

EXISTING UTILITIES


UT1
SHEET 7 OF 39 SHEETS

T.24N. R.4E. W.M. City of Seattle

TWO EXISTING BURIED TRANSMISSION LINES, 115 KV




PLAN VIEW



SECTION: A

SCALE: 1/4" = 1'-0"

FILE NAME: C:\AAWork\pwwork\AWV\Gonzalez\dms03962\AD-L3082.PS-UT_02.dgn		REGION NO. 10	STATE WASH	FED. AID PROJ. NO.
TIME 10:50:24 AM	DATE 8/15/2007	JOB NUMBER 07A805	CONTRACT NO.	LOCATION NO.
DESIGNED BY B. BARTLE	CHECKED BY Y. GONZALEZ	DATE 8/14/07	BY YG	
ENTERED BY G. PIERSON	PROJ. ENGR. P. LACY	REVISIONS SHADED	REVISION	
REGIONAL ADM. D. DYE				




Washington State
Department of Transportation

SR 99
YESLER WAY VICINITY
FOUNDATION STABILIZATION
WATER MAIN THRUST COLLAR

UT2
SHEET 8 OF 40 SHEETS


GENERAL NOTES:

- PROTECT ALL EXISTING UTILITIES, SERVICE CONNECTIONS, AND SURFACE IMPROVEMENTS. REPAIR ALL UTILITIES DAMAGED DURING CONSTRUCTION WHETHER SHOWN ON THESE PLANS OR NOT.
- THE WATERLINE SHALL BE REMOVED FROM SERVICE FOR THE CONSTRUCTION AND INSTALLATION OF THE THRUST COLLARS AND MECHANICAL JOINT RESTRAINTS. CONTRACTOR SHALL CONTACT SEATTLE PUBLIC UTILITIES (SPU) A MINIMUM OF THREE (3) WEEKS PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES TO COORDINATE THE SHUT DOWN. REFER TO SPECIAL PROVISION, WATER MAIN.
- BLOCKING SHALL NOT COVER OR ENCLOSE BELL ENDS, JOINT BOLTS OR GLANDS. FUTURE ACCESS TO BOLTS AND GLANDS SHALL BE PROVIDED.
- CONCRETE FOR THRUST COLLAR SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI.
- CONCRETE THRUST COLLARS SHALL BE BACKFILLED AFTER 1 DAY.
- ALL BACKFILL SHALL BE COMPACTED TO 95% OF ASTM D1557, METHOD C.
- PROVIDE SPU AND THE ENGINEER AT LEAST ONE (1) WORKING DAY ADVANCE NOTICE FOR INSPECTION AND APPROVAL OF ALL CONCRETE BLOCKING PRIOR TO BACKFILLING. UNACCEPTABLE CONCRETE BLOCKING SHALL BE REPLACED AT NO ADDITIONAL EXPENSE TO THE CONTRACTING AGENCY.
- PIPELINE INSTALLATION WORK TO BE PERFORMED BY OTHERS. CONTRACTOR TO EXCAVATE AND EXPOSE PIPING. PROVIDE TRENCH SAFETY AND ASSIST WITH INSTALLATION AS REQUESTED. CONTRACTOR TO BE RESPONSIBLE FOR CONCRETE WORK, EXCAVATION, BACKFILL, SURFACE RESTORATION, TRENCH SAFETY, AND ALL OTHER ASSOCIATED WORK.




TYPICAL TRENCH ELEVATION
SCALE: 1/4" = 1'-0"

ENVIRONMENTAL COMPLIANCE NOTES


SHEET REFERENCE	SITE CODE	NOTE NUMBERS	NOTES	NOTES	NOTES	
NOT USED	NOT USED	NOT USED	<p>4. Hazardous Spill Prevention and Control (Continued)</p> <p>4g. Fuel hoses, oil drums, oil or fuel transfer valves and fittings, etc., shall be checked daily for drips or leaks, and shall be maintained and stored properly to prevent spills into waters of the state. All staging and storage sites containing equipment, fuel, oil, or any other toxic or hazardous materials shall be secured within fencing and locked gates, as approved by the Engineer.</p> <p>4h. The Contractor is responsible for concentrated waste or spilled chemicals and the Contractor shall transport off site for disposal at a facility approved by the Department of Ecology or appropriate County Health Department. These materials shall not be discharged to a sewer without approval of the local sewer authority.</p> <p>5. Spill Reporting</p> <p>5a. Any spill of fuel, oil, hydraulic fluid, solvents, paint, stored chemicals, toxic or hazardous materials into the ground, drainage structures, or into surface waters of the state shall be reported to the Engineer immediately. Containment and clean-up efforts shall begin immediately and be in accordance with the approved Spill Prevention, Control, and Countermeasures Plan, as specified in Section 1-07.15(1) of the Standard Specifications. All other work in the effected area shall be stopped until all clean up of the spill is completed. Containment and clean up shall take precedence over normal work activities. Normal work activities within the immediate spill area shall be stopped until the contents, clean up and disposal methods are completed as approved by the Engineer.</p> <p>5b. If fish are observed in distress, or a fish kill occurs (outside of normal spawning events), as a result of water quality problems (including equipment leaks or toxic and hazardous material spills into waters of the state), immediate notification shall be made to the Engineer.</p> <p>6. Ditch and Culvert Cleaning</p> <p>6a. Ditch and culvert cleaning activities shall take place when the ditch or culvert does not contain water whenever possible. If the ditch or culvert has flowing water that discharges to surface waters of the state at the time of the cleaning activity, temporary sediment traps shall be used to control turbid water created by the activity.</p>	<p>6b. All material excavated from roadside ditches or streams shall be completely removed and disposed of at an upland location. No material shall be side cast into adjacent wetlands, sensitive areas, or other waters of the state.</p> <p>6c. If material is placed on the upland to dewater, it shall be contained or placed in such a way that the runoff shall not flow into nearby storm drains, or water bodies, including wetlands and sensitive areas occurring adjacent to the ditch. Any flow of slurry water shall be controlled to reduce suspended sediment levels not exceeding state established water quality standards, prior to discharge back into any adjacent water body.</p> <p>7. Maintenance of Storm Water Control and Treatment Structures</p> <p>7a. Cleaning of storm water conveyance systems (catch basins, piping, vaults, detention/retention ponds) by use of vacator or eductor systems shall be performed to minimize discharge of turbid water. Accumulated sediments from vacator or eductor cleaning operations shall be disposed at locations appropriately permitted to receive these wastes. Decanting of the liquid portion of vacator wastes in the field shall be handled in the following manner:</p> <p style="padding-left: 20px;">Decant water shall be disposed to municipal decant stations appropriately permitted to receive the decant water.</p>	<p>7b. Cleaning of storm water treatment ponds or swales shall be performed when there is not a possibility of a discharge from the pond for at least 24 hours.</p> <p>7c. If upon inspection of a storm water facility, the water appears excessively oily, exhibits an unusual color or odor, or if staining or corrosion is observed, illicit dumping may be the cause and the storm water facility shall not be disposed or discharged until a characterization of the water can be performed to determine the presence of toxic or hazardous contaminants. Should these conditions be observed during wet weather, the material may need to be removed and stored for characterization to prevent a discharge and degradation of waters of the state. Proper disposal options will be determined based on the characterization. If there is a likely source of contamination nearby that may be causing any observed problems, contact the Engineer immediately to report the information.</p> <p>7d. Material that is placed on the upland to dewater, shall be contained or placed in such a way that the runoff will not flow directly into adjacent storm drains, or water bodies, including wetlands occurring adjacent to the ditch. Any flow of slurry water shall be controlled to reduce suspended sediment levels prior to discharging back into any adjacent water body. This return water shall not exceed the water quality standards.</p>	
<p>GENERAL NOTES: The information on the ECN sheets is derived from project-specific environmental commitment documents and regulatory approval. The Contractor shall abide by the commitments outlined in the commitment documents and regulatory approvals to stay in compliance with the legal regulations. The Contractor shall contact the Engineer and the Engineer will contact the appropriate resource agency through the Project Environmental Manager regarding approval issues. See ECN sheets for regulatory compliance for all work.</p> <p>* Permit/Approval Reference Regulatory Agencies and Permit</p> <p>DOE - WASH. STATE DEPT. OF ECOLOGY -IMPLEMENTING AGREEMENT between WSDOE & WSDOT Regarding Compliance with the state of Washington Surface Water Quality Standards, February, 1998</p>			 <p>Washington State Department of Transportation</p>			<p>SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION</p>
<p>DESIGNED BY C. KASSEBAUM 7/9/07 ENTERED BY C. KASSEBAUM 7/9/07 CHECKED BY S. SOBHANI 7/9/07 PROJ. ENGR. P. LACY 7/9/07 REGION ADM. D. DYE 7/9/07</p>			<p>REGION NO. 10 STATE WASH JOB NUMBER 07A805 CONTRACT NO.</p>		<p>EM 2</p> <p>SHEET 10 OF 40 SHEETS</p>	
			<p>ENVIRONMENTAL COMPLIANCE NOTES</p>			

ENVIRONMENTAL COMPLIANCE NOTES



SHEET REFERENCE	SITE CODE	NOTE NUMBERS	NOTES	NOTES
NOT USED	NOT USED	NOT USED	<p>8. Puget Sound Clean Air Agency (PSCAA) Fugitive Dust Control</p> <p>8a. The Contractor shall prepare a Fugitive Dust Control Plan and submit to the Engineer prior to start of construction. This Plan shall identify the selected BMPs relying on the Associated General Contractors of Washington (AGC) publication, Guide to Handling Fugitive Dust From Construction Projects.</p> <p>9. King County Dewatering Discharge Authorization</p> <p>9a. Prior to discharge to the sanitary sewer, the Contractor shall have preliminary samples taken of the wastewater and analyzed by a Washington State Department of Ecology accredited laboratory. The results of the sampling shall be submitted to King County for review to ensure the discharge meets King County Industrial Wastewater limits.</p> <p>9b. Discharge to the sanitary sewer shall consist primarily of construction process wastewater and groundwater from excavations which may be contaminated.</p> <p>9c. Wastes or contaminants from sources other than those permitted by the King County Discharge Authorization shall not be discharged to the sanitary sewer without prior approval by the Engineer.</p> <p>9d. The discharge shall not cause hydraulic overloading conditions of the sewerage conveyance system. During periods of peak hydraulic loading, King County and City of Seattle representatives reserve the authority to request that discharge to the sanitary sewer be stopped.</p> <p>9e. The Contractor shall implement erosion control BMP to minimize the amounts of solids discharge to the sanitary sewer system. As a minimum precaution, the wastewater shall be pumped to an appropriately sized settling tank prior to entering the sanitary sewer system.</p> <p>9f. The Contractor shall provide wastewater monitoring logs containing the results of the required field monitoring specified must be maintained on-site and must be available for review at reasonable times by authorized representatives of King County.</p> <p>9g. Prior to any discharge to the sanitary system, the Contractor shall have H₂S and salinity meters to appropriately monitor for atmospheric sulfides and salinity.</p> <p>10. City of Seattle Code Section 25.08.425 Noise Control and Temporary Noise Variances for Nighttime Noise</p> <p>10a. The Contractor shall comply with Section 25.08.425 of the Seattle Municipal Code which requires that any equipment used in commercial construction activities shall not exceed established maximum permissible sound levels.</p>	<p>10b. Should nighttime work be needed, the Contractor shall submit a Noise Attenuation Plan to the Engineer for approval 10 days prior to night time work. This Plan shall demonstrate how planned work means and methods comply with the special provision titled "NOISEVAR" and the temporary night time noise variances issued by the City of Seattle Department of Planning and Development as secured by the Contracting Agency.</p> <p>11. City of Seattle Department of Planning and Development Exemption From Shoreline Management Act Substantial Development Permit Requirement</p> <p>11a. The Contractor shall employ BMP's to minimize the amount of erosion and contamination of the shoreline environment caused by construction and associated storage and staging areas.</p> <p>12. City of Seattle Department of Transportation Street Use Permit</p> <p>12a. The Contractor shall comply with all conditions in the City of Seattle Department of Transportation Street Use Permit.</p> <p>13. City of Seattle Pioneer Square Preservation Board Certificate of Approval</p> <p>13a. The Contractor shall comply with all conditions in the City of Seattle Pioneer Square Preservation Board Certificate of Approval.</p> <p>14. State Historic Preservation Officer (SHPO)/ Department of Archaeology and Historic Preservation (DAHP) – Section 106</p> <p>14a. Contractor shall prepare an Archaeological Excavation Plan that complies with applicable conditions as contained in the referenced Section 106 correspondence between WSDOT and SHPO/DAHP. The Plan shall specifically address how the Contractor and Engineer's archaeologist will coordinate and work together to allow completion of the archaeological investigations within a maximum of 10 working day period. The Contractor shall consult with the Engineer's archaeologist to develop this Plan. This Plan shall be submitted to Engineer for approval 30 days prior to the start of Archaeological excavation.</p> <p>14b. Contractor shall comply with special provisions titled "Archaeological and Historical Objects" and "Vibration Monitoring".</p> <p>14c. Contractor shall not start construction, until the Engineer confirms in writing that the Contracting Agency has completed its photography and video recording of the adjacent historic structures.</p> <p>14d. Contractor shall return the project area to existing conditions with asphalt-paved street under the viaduct, following repairs.</p>
<p>GENERAL NOTES: The information on the ECN sheets is derived from project-specific environmental commitment documents and regulatory approvals. The Contractor shall abide by the commitments outlined in the commitment documents and regulatory approvals to stay in compliance with the legal regulations. The Contractor shall contact the Engineer and the Engineer will contact the appropriate resource agency through the Project Environmental Manager regarding approval issues. See ECN sheets for regulatory compliance for all work.</p> <p>*Permit/Approval, Regulatory Agencies and Permit Reference</p> <p>8. Puget Sound Clean Air Agency (PSCAA) - Memorandum of Agreement between WSDOT and PSCAA regarding fugitive dust control at construction sites, December 1999.</p> <p>9. King County Dewatering Discharge Authorization</p> <p>10. City of Seattle Code Section 25.08.425 Noise Control and Temporary Noise Variances for Nighttime Noise</p> <p>11. City of Seattle Department of Planning and Development Exemption From Shoreline Management Act Substantial Development Permit Requirement</p> <p>12. City of Seattle Department of Transportation Street Use Permit</p> <p>13. City of Seattle Pioneer Square Preservation Board Certificate of Approval</p> <p>14. State Historic Preservation Officer (SHPO)/ Department of Archaeology and Historic Preservation (DAHP) – Section 106 correspondence between WSDOT and SHPO/DAHP regarding archaeological monitoring and vibration and settlement monitoring of historic structures, and archeological excavation, June 19, 2007 and June 21, 2007, respectively.</p> <p>15. Transient Populations and Construction Safety</p> <p>16. Erosion Control and Temporary Erosion and Sediment Control (TESC) Plan</p>	<p>15. Transient Populations and Construction Safety</p> <p>15a. Contractor shall on a daily basis, prior to beginning any construction activity, visually inspect the construction site for people in otherwise inconspicuous areas such as under or inside machinery and dumpsters in order to prevent physical accidents and hazards.</p> <p>16. Erosion Control and Temporary Erosion and Sediment Control (TESC) Plan</p> <p>16a. The ESC lead shall be listed on the Emergency Contact List for the Project.</p>			

 <p>Washington State Department of Transportation</p>	<p>SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION</p>	<p>EM 3</p> <p>SHEET 11 OF 40 SHEETS</p>
<p>ENVIRONMENTAL COMPLIANCE NOTES</p>		

DESIGNED BY	C. KASSEBAUM	7/9/07	DATE	DATE	REVISION
ENTERED BY	C. KASSEBAUM	7/9/07			
CHECKED BY	S. SOBHANI	7/9/07			
PROJ. ENGR.	J. LACY	7/9/07			
REGION ADM.	D. DYE	08/14/07			



TEMPORARY NOISE SHIELD 8' X 8' (TNS)
NTS




PLAN VIEW
NTS


- NOTES:**
1. TEMPORARY NOISE SHIELD (TNS) SHALL FACE GRATED SURFACE TOWARD THE CONSTRUCTION EQUIPMENT OR NOISE SOURCE.
 2. THE TNS GRATED SURFACE SHALL BE BUILT USING CEDAR LATTICE OR BEVEL CEDAR GRATING AT 45 DEGREE ANGLE. ALTERNATE MATERIAL SHALL BE APPROVED BY THE ENGINEER.
 3. THE TNS SHALL BE CONSTRUCTED IN 8 ft. X 8 ft. UNITS OR AS APPROVED BY THE ENGINEER.
 4. WITH APPROVAL OF THE ENGINEER, THE CONFIGURATION OF THE TNS MAY BE ALTERED TO SUIT DIFFERENT WORK ZONE CONDITIONS IF THE ATTENUATION THRESHOLD IS NOT COMPROMISED.
 5. THE TNS SHALL BE PLACED AS CLOSE TO THE NOISE SOURCE OR CONSTRUCTION EQUIPMENT AS FEASIBLE.
 6. THE TNS SHALL BLOCK THE LINE OF SIGHT BETWEEN THE CONSTRUCTION EQUIPMENT OR NOISE SOURCE AND THE RECEIVER.

FILE NAME C:\AAwork\p\work\AWV\Gonzalez\cms03626\13082_MC_DE_EM.dgn		REGION 10	STATE WASH	FED. AID PROJ. NO.
TIME 2:40:22 PM	DATE 7/30/2007	JOB NUMBER 07A805	CONTRACT NO.	LOCATION NO.
DESIGNED BY gonzalez	ENTERED BY Y. GONZALEZ	DATE	BY	REVISION
CHECKED BY K. JONES	PROJ. ENGR. P. LACY	DATE	BY	REVISION
REGIONAL ADM. D. DYE	DATE	BY	REVISION	DATE
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION		ENVIRONMENTAL COMPLIANCE DETAIL		
EM4		SHEET 12 OF 40 SHEETS		


T.24N. R.4E. W.M. City of Seattle





TEMPORARY DOWNSPOUT CONNECTION N.T.S



BAFFLED SETTLING TANK DETAIL PLAN VIEW OF BAFFLED SETTLING TANK



TEMPORARY CURB PLAN VIEW OF TEMPORARY CURB PLACEMENT



SECTION TEMPORARY PIPE PROTECTION N.T.S

- LEGEND**
- S- - SANITARY SEWER
 - ST- - EXISTING STORM DRAIN
 - G- - EXISTING GAS
 - IRR- - EXISTING IRRIGATION LINE
 - W- - EXISTING WATER
 - EOL- - EXISTING UNKNOWN UTILITY
 - - - - EXISTING RETAINING WALL
 - - - - EXISTING RAIL
 - - - - EXISTING EASEMENT
 - - - - LIMIT OF EXCAVATION
 - - - - TEMPORARY CURB
 - ⊗ - CATCH BASIN
 - ⊠ - JUNCTION BOX
 - ⊡ - PARKING METER
 - ⊞ - INLET PROTECTION
 - ~ ~ ~ - FLEXIBLE DRAIN PIPE

- TEMPORARY DRAINAGE NOTES:**
- TEMPORARY DOWNSPOUT CONNECTIONS SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF EXCAVATION WORK ON EACH PIER.
 - TEMPORARILY PLUGGING EXISTING DOWNSPOUTS DURING CONSTRUCTION IS NOT ALLOWED.
 - LEAKS IN THE TEMPORARY CONNECTIONS SHALL BE REPAIRED IMMEDIATELY.
 - REMOVE AND REPLACE EXISTING CAST IRON DRAIN PIPE WITH 6" SCH 40 PVC PER ASTM 1785 AS SHOWN ON SHEET 40.
 - SEE STANDARD PLAN 1-7, FOR STORM DRAIN INLET PROTECTION INSERT DETAILS.
 - VACUUM OUT SOLIDS AND STANDING WATER FROM EXISTING DOWNSTREAM CATCH BASIN BEFORE AND AFTER CLEANING WORK ON UPSTREAM DOWNSPOUT CONNECTIONS.
 - DURING JETTING OR RODDING WORK, VACUUM OR REMOVE ANY MATERIALS (WATER, SOLIDS) AT THE DOWNSTREAM END, AND DISPOSE OF ALL VACUUM MATERIALS PROPERLY. DO NOT DISCHARGE DECANT OR SOLIDS TO SEATTLE PUBLIC UTILITIES (SPU) SYSTEMS IN THE PROJECT AREA.
 - NOTIFY THE ENGINEER IMMEDIATELY IF ANY SPU INFRASTRUCTURE IS DAMAGED DURING CLEANING OPERATIONS. INFORM HERMAN SMITH OF SPU MAINTENANCE AT (206) 386-4006.
 - REFER TO NOTES ON SHEET EMJ AND DEWATERING SPECIAL PROVISION.



GENERAL NOTES:

- STOCKPILED SOIL EXPOSED TO RAIN SHALL BE COVERED.
- THE LIMITS OF THE FOOTING EXCAVATION SHALL BE SWEPT FREE OF DEBRIS.
- ALL STORM WATER RUNOFF IN THE PROJECT AREA, INCLUDING RUN-ON WATER FROM OFF-SITE AND VIADUCT RUNOFF FROM DOWNSPOUTS, SHALL BE ROUTED TO THE STORM DRAIN SYSTEM USING THE INLET STRUCTURES SHOWN. STORM WATER SHALL BE PREVENTED FROM ENTERING THE EXCAVATIONS AND MIXING WITH GROUNDWATER, PROCESS WATER, OR BOTH.
- TEMPORARY CURB SHALL BE ASPHALT.
- WHERE PROTECTION IS REQUIRED FOR VEHICULAR ACCESS, COST OF PROTECTION IS INCLUDED IN UNIT PRICE FOR DRAIN PIPE 6" DIAM.
- ALL WORK SHALL COMPLY WITH THE CITY OF SEATTLE CONSTRUCTION STORMWATER CONTROL TECHNICAL REQUIREMENTS MANUAL (JULY, 2000) KEPT AT ENGINEERS OFFICE.

NOT TO SCALE

		SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION TESC PLAN		EC1 SHEET 13 OF 40 SHEETS
FILE NAME: C:\AWork\pwork\AWV\Gonzal\Gonzal\03962\AD_L13082-PS-EC.dgn TIME: 10:53:01 AM DATE: 8/15/2007		REGION: 10 STATE: WASH FED. AID PROJ. NO.: JOB NUMBER: 07A805 CONTRACT NO.: LOCATION NO.:		P.E. STAMP BOX DATE:
PLOTTED BY: gonzalv DESIGNED BY: S. SOBhani CHECKED BY: Y. GONZALEZ PROJ. ENGR.: P. LACY REGIONAL ADM.: D. DYE		REVISIONS: SHADED REVISION DATE: 8/14/07 BY: YG		P.E. STAMP BOX DATE: 8/15/07

T.24N. R.4E. W.M. City of Seattle



TYPICAL TRENCH SECTION
N.T.S

GENERAL NOTES:

- 12. REFER TO SHEET UT1 FOR ALL EXISTING UTILITY LOCATIONS.
- 13. SEE STANDARD PLAN B-55-20-00 FOR BACKFILL DETAILS.
- 14. PVC DRAIN PIPE 8" DIAM. TO BE CONSTRUCTED PARALLEL TO EXISTING 8" STORM DRAIN AT AN APPROXIMATE DISTANCE OF 4.0 FT.
- 15. REFER TO SHEET SP2 FOR REMOVAL OF EXISTING 8" STORM DRAIN.
- 16. PVC DRAIN PIPE 8" DIAM. SHALL MATCH GRADE OF EXISTING 8" STORM DRAIN TO ENSURE CONTINUOUS GRAVITY DRAINAGE.
- 17. SHORING TO BE COVERED UNDER SHORING OR EXTRA EXCAVATION CLASS B.
- 18. GRAVEL BACKFILL SHALL BE COMPACTED IN ACCORDANCE WITH SECTION 2-09.3(1)E
- 19. PVC DRAIN PIPE 8" DIAM. SHALL BE PLACED NO FARTHER THAN THE DIMENSION STATED IN PLAN.
- 20. REFER TO CITY OF SEATTLE STANDARD PLANS NO 277 & NO 230.
- 21. SHIELDED COUPLING SHALL BE EITHER MISSION FLEX SEAL ARC MODEL, ROMAC LESS REPAIR CLAMP, OR FERNCO 1002 SERIES WITH A SHEAR RING / BAND.
- 22. 8" DRAIN PIPE SHALL BE REPLACED WITH 8" SCH 40 PVC PER ASTM 1785.

NOT TO SCALE

FILE NAME C:\AAwork\K\PMwork\AWV\Gonzalez\gms03962\AD-L3082.PS-UT-03.dgn		REGION	STATE	FED. AID PROJ. NO.
TIME 11:22:02 AM	DATE 8/15/2007	10	WASH	
DESIGNED BY gonzalez	ENTERED BY L. BOYD	JOB NUMBER	CONTRACT NO.	LOCATION NO.
PROJ. ENGR. P. LACY	REGIONAL ADM. D. DYE	07805		
REVISIONS SHADED	REVISION	DATE	BY	
		8/14/07	YG	

P.E. STAMP BOX DATE 8/15/07


Washington State Department of Transportation

SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION

STORM DRAIN CONSTRUCTION


UT3

SHEET 14 OF 40 SHEETS



PLAN VIEW OF
PIPE CLAMP HOLDING PIPE OFFSET
FROM COLUMN FACE TO CLEAR INTERFERENCES

PIPE CLAMP DETAIL
N.T.S.




DRAIN PIPE REPAIR DETAIL
N.T.S.

CONNECT TO EXISTING 6" CAST IRON PIPE
WITH 6" SHIELDED COUPLING (SEE NOTE 5).
CLEAN LINE PRIOR TO MAKING CONNECTION.
REFER TO TEMPORARY DRAINAGE NOTES ON
SHEET EC1 FOR DETAILS ON CLEANING LINE


- GENERAL NOTES:**
1. REPLACE/REINSTALL ALL PIPE CLAMPS DAMAGED OR REMOVED DURING CONSTRUCTION.
 2. LOCATE THE RESIN BONDED ANCHORS FOR THE DRAIN ANCHORAGE TO CLEAR ALL EXISTING STEEL REINFORCING BARS IN THE CONCRETE COLUMN. IF INITIAL DRILLING ENCOUNTERS EXISTING STEEL REINFORCING BARS, THE HOLE SHALL BE COATED WITH TYPE II EPOXY BONDING AGENT CONFORMING TO SECTION 9-26.1, FILLED WITH GROUT CONFORMING TO SECTION 6-02.3(20), AND THE STRAP ANCHORAGE LOCATION SHIFTED TO CLEAR THE EXISTING STEEL REINFORCING BARS.
 3. TWO BROKEN PIPE CLAMPS LOCATED ON BENT 93E TO BE REPLACED.
 4. SHIELDED COUPLING SHALL BE EITHER MISSION FLEX SEAL ARC MODEL, ROMAC LSS REPAIR CLAMP, OR FERNCO 1002 SERIES WITH A SHEAR RING/BAND.
 5. SEE SHEETS SP2 AND UT3 FOR DETAILS.
 6. STEEL PIPE STRAPS SHALL MEET THE REQUIREMENTS OF SECTION 9-05.4(9)B.

NOT TO SCALE

FILE NAME: C:\AAWor\k\p\wor\k\AWV\Gonzal\y\dms03962\AD.L3082.DE_DR.dgn		REGION STATE		FED.AID PROJ.NO.	
TIME: 10:54:16 AM	DATE: 8/15/2007	NO. 10	WASH		
DESIGNED BY: S. SOBANI	ENTERED BY: Y. GONZALEZ	JOB NUMBER: 07A805	CONTRACT NO.	LOCATION NO.	
CHECKED BY: S. SOBANI	PROJ. ENGR: P. LACY	DATE: 8/14/07	Y.C.	REVISIONS SHADED	
REGIONAL ADM. D. DYE	REVISION	DATE	BY		
Washington State Department of Transportation		P.E. STAMP BOX		DATE	
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION		P.E. STAMP BOX		DATE	
DRAINAGE DETAIL		P.L. STAMP BOX		DATE	
DDI		PLOT1		SHEET 15 OF 40 SHEETS	





LANDSCAPING DETAIL: 4 SIMILAR AREAS
N.T.S.



INSTALL 1 IN. DIAM PVC IRRIGATION LINE TO REPLACE MINIMUM LENGTH 3 FOOT. LOCATION IS 14'-1/2" FEET SOUTH OF PIER 93M ALONG WESTERN FACE OF PIER TO 13'-1/2" FEET NORTH OF PIER. REPLACE SPRINKLER HEADS AS REQUIRED.



INSTALL 1 IN. DIAM PVC IRRIGATION LINE TO REPLACE MINIMUM LENGTH 3 FOOT. LOCATION IS 8'-1/2" FEET SOUTH OF PIER 94M ALONG WESTERN FACE OF PIER TO 9'-1/2" FEET NORTH OF PIER. REPLACE SPRINKLER HEADS AS REQUIRED.



GENERAL NOTES:


- IRRIGATION SYSTEM IN PLANTING STRIP CONTAINS 2-1/2" DIAM MAIN LINE AND 1" DIAM LATERAL PIPES. PIPES ARE APPROXIMATELY PARALLEL TO THE BRIDGE. USE HAND METHODS TO EXCAVATE FOR REPAIRS AND REPAIR ANY FURTHER DAMAGED LINES AT NO COST TO THE CONTRACTING AGENCY.
- PORTION OF EXISTING IRRIGATION SYSTEM WITHIN EXCAVATION AREAS SHALL BE REPLACED WITH NEW LINES TO CONSTRUCT AN OPERATIONAL SYSTEM. NEW IRRIGATION LINES SHALL BE CONNECTED TO INTERCEPT EXISTING IRRIGATION SYSTEM AFTER ADJACENT MICROPILE INSTALLATION WORK COMPLETE.
- WITHIN THE WORK ZONE, THE MAXIMUM NUMBER OF PARKING SPACES IMPACTED BY CONSTRUCTION ACTIVITIES IS LIMITED TO 22 PUBLIC SPACES AND 22 PRIVATE SPACES.
- JAPANESE HOLLY/DAYLILLIES/JOHNSWORT SHALL BE REPLACED IN KIND.

FILE NAME: C:\AAWork\K\P\Work\AWV\Gonzalez\dms03626\L_3082_PS_LSMK.dgn		FED.AID PROJ.NO.	
TIME: 7:36:53 AM	DATE: 7/31/2007	REGION NO.: 10	STATE: WASH
DESIGNED BY: R. A. BEAN	ENTERED BY: Y. GONZALEZ	JOB NUMBER: 07805	CONTRACT NO.:
CHECKED BY: K. JONES	PROJ. ENGR. P. LACY	DATE:	BY:
REGIONAL ADM. D. DYE	REVISION	DATE:	BY:
		P.E. STAMP BOX DATE:	
SR 99		LSTMK1	
YESLER WAY VICINITY		SHEET 16 OF 40 SHEETS	
FOUNDATION STABILIZATION			
LANDSCAPE/PAVEMENT MARKINGS			



LEGEND

- EXISTING RETAINING WALL
- EXISTING RAIL
- EXISTING EASEMENT
- EXISTING CLINE ROW
- |-|- EXISTING WOODEN GUARD RAIL
- TREE
- SHRUBS
- PARKING PAY STATION
- EXISTING PRECAST CONCRETE CURB
- ⊕ EXISTING CONDUIT W/ JUNCTION BOX
- ⊕ EXISTING DOWNSPOUT
- WASTE CONTAINER
- SEE NOTE 6




0 20 40
SCALE IN FEET

GENERAL NOTES:

1. REPLACE SPECIFIED ASPHALT CONCRETE TRAIL SECTIONS AND PERFORM PAVEMENT REPAIR AS SHOWN IN THE PLANS.
2. DO NOT USE ROLLERS ON VIBRATORY MODE WHEN COMPACTING ASPHALT. SMALL HAND OPERATED EQUIPMENT FOR COMPACTING EDGES OF ASPHALT MAY BE USED.
3. USE CRUSHED SURFACE BASE COURSE AND NON VIBRATORY EMBANKMENT COMPACTION EQUIPMENT TO RE-GRADE AREA DISTRIBUTED IN THE VICINITY OF PIERS AND TRACK REMOVAL AREA (4 LOCATIONS). SMALL HAND OPERATED EQUIPMENT FOR COMPACTION MAY BE USED.
4. PAY STATION EQUIPMENT WILL BE REMOVED BY THE CITY OF SEATTLE AND STORED FOR REPLACEMENT. THE CITY WILL REPLACE BOTH, THE FOUNDATIONS AND EQUIPMENT WHEN APPLICABLE.
5. CEMENT CONC. PEDESTRIAN CURB SHALL CONFORM TO CITY OF SEATTLE STANDARD PLAN 414 "BLOCK TRAFFIC CURBS. PRECAST CEMENT CONCRETE" 414 C BLOCK.
6. THESE AREAS SHALL BE PAVED TWICE. ONCE TO RESTORE THE WORK AREA FOR PUBLIC USE PER SPECIAL PROVISION "SUSPENSION OF WORK" AND ONCE TO RESTORE THE WORK AREA FOR PUBLIC USE BEFORE COMPLETION OF WORK.


FILE NAME	C:\AAW\K\PW\K\AWV\Gonzalez\dms03962\AD_L3082_PS_PV.dgn		
TIME	10:55:46 AM	REGION	STATE
DATE	8/15/2007	10	WASH
PLOTTED BY	gonzalez	JOB NUMBER	07805
DESIGNED BY	R. A. BEAN	CONTRACT NO.	
ENTERED BY	Y. GONZALEZ	DATE	8/14/07
CHECKED BY	K. JONES	BY	EM
PROJ. ENGR.	P. LACY	REVISIONS SHADED	
REGIONAL ADM.	D. DYE	REVISION	



Washington State
Department of Transportation

SR 99
YESLER WAY VICINITY
FOUNDATION STABILIZATION
PAVING PLAN

PV1
SHEET 17 OF 40 SHEETS



GENERAL NOTES

1. ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD, BRIDGE AND MUNICIPAL CONSTRUCTION-ENGLISH DATED 2006, AND AMENDMENTS.
2. CONCRETE PATCHING MATERIAL SHALL CONFORM TO STD. SPEC. SECTION 9-20.2(2). ALL OTHER CAST-IN-PLACE CONCRETE SHALL BE CLASS 4000.
3. UNLESS OTHERWISE SHOWN ON THE PLANS, THE CONCRETE COVER MEASURED FROM THE FACE OF ANY REINFORCING STEEL SHALL BE 3" AT THE TOP, BOTTOM AND SIDES OF THE FOOTING, AND 1 1/2" AT ALL OTHER LOCATIONS.
4. THE CONDUITS, JUNCTION BOXES AND UTILITIES ARE SHOWN FOR REFERENCE ONLY. THE CONTRACTOR SHALL COORDINATE THESE PLANS WITH THE ELECTRICAL AND OTHER CIVIL PLANS.
5. THIS FOUNDATION STABILIZATION HAS BEEN DESIGNED IN ACCORDANCE WITH THE REQUIREMENTS OF THE AASHTO STD. SPECS. FOR HIGHWAY BRIDGES, 17th EDITION 2002. THE SERVICE DESIGN LOAD FOR THE MICROPILES AT BENTS 93 AND 94 IS 95 TONS COMPRESSION. THE CONTRACTOR SHALL SUBMIT WORKING DRAWINGS AND DESIGN CALCULATIONS TO THE ENGINEER FOR APPROVAL AS SPECIFIED IN THE SPECIAL PROVISIONS. REFER TO THE SUMMARY OF GEOTECHNICAL CONDITIONS FOR SOIL AND GROUNDWATER INFORMATION.
6. THE DIMENSIONS SHOWN IN THE PLANS ARE BASED ON ORIGINAL CONSTRUCTION RECORDS, AS-BUILT PLANS AND FIELD SURVEY DATA. THESE DIMENSIONS AND ELEVATIONS SHALL BE MEASURED AND VERIFIED BY THE CONTRACTOR IN THE FIELD PRIOR TO FABRICATION.

PLAN - BENTS 92 TO 95
MICROPILES NOT SHOWN

LEGEND

- BORING
- UTILITY & FOUNDATION LOCATION TEST HOLE
- IDENTIFIES SECTION, VIEW OR DETAIL
- TAKEN OR SHOWN ON BRIDGE SHEET 15
- TAKEN OR SHOWN ON THE SAME SHEET

- EXISTING WATER LINE
- EXISTING STORM DRAIN
- EXISTING SANITARY SEWER
- EXISTING BURIED TELEPHONE
- EXISTING BURIED FIBER
- EXISTING BURIED POWER
- EXISTING GAS
- EXISTING FIBER OPTIC DUCT
- EXISTING IRRIGATION
- EXISTING TROLLEY (KING CO. METRO)

LOADING: HS-20


DATUM
N.A.V.D. OF 1988

Bridge Design Engr.	Kaput, J	REGION NO.	10	STATE	WASH.	FED. AID PROJ. NO.		SHEET NO.		TOTAL SHEETS	
Supervisor	Clarke, PT										
Designed By	Sweet, GD										
Checked By	Gallagher, P										
Detailed By	Schicchi, V.B.										
Bridge Projects Engr.											
Prelim. Plan By											
Architect/Specialist											

BRIDGE AND STRUCTURES OFFICE
WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
7-23-07 EXPIRES 5/15/08

SR 99
YESLER WAY VICINITY
FOUNDATION STABILIZATION
ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB
LAYOUT - PLAN

BRIDGE SHEET NO. 1
SHEET 18 OF 40 SHEETS



ELEVATION FOR BENT NO. 92 TO BENT NO. 95
(FACING EAST)


- * ELEVATIONS ARE AVERAGE GROUND ELEVATIONS AT EACH COLUMN.
- ** APPROXIMATE ELEVATIONS BASED ON AVAILABLE AS-BUILT AND TEST HOLE DATA.
- *** EXISTING STEEL H-FILES NOT SHOWN.

DATUM
NAVD 88

BRIDGE SHEET NO. 2		SHEET 19 OF 40	
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB ELEVATION			
 Washington State Department of Transportation		 BRIDGE AND STRUCTURES OFFICE 7-23-07	
M:\Z-Team\Alaskan way Ftgs\Window files\LAYOUT ELEV.WND			
Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Swett, GD Checked By Gallagher, P Detailed By Schiccht, V.B. Bridge Projects Engr. Prehm, Pam By	STATE WASH. REGION NO. 10 JOB NUMBER 07/A805	FED. AID PROJ. NO. SHEET NO.	TOTAL SHEETS
DATE	REVISION	BY	APPD

STA. 93+24.06
BENT 93

STA. 93+93.50
BENT 94



GRD. ELEVATION (AVG. @ COL. FACE):
 BENT 93E = 15.16
 BENT 93W = 15.72
 BENT 94E = 15.00
 BENT 94W = 15.31

HEX NUT (TYP.)
 R 1 x 13 x 1'-1" MINIMUM
 BOT. OF FTG. APPROX. ELEV.:
 BENT 93E & W = 6.3
 BENT 94E & W = 5.9

HIGH STRENGTH STEEL BAR IN EACH MICROPILE (TYP.) TO BE DESIGNED BY CONTRACTOR
 MINIMUM PERMANENT MICROPILE CASING TIP ELEVATIONS:
 BENT 93E & 93W = -26.0
 BENT 94W = -27.0
 BENT 94E = -23.0

TYPICAL PILE ELEVATION
 STAGE II MICROPILE. SEE BRIDGE SHEET 5 FOR STAGE I MICROPILE DETAILS.

DATUM
 NAVD 88

- STAGE I MICROPILES TO BE INSTALLED AS PART OF THE TEMPORARY SUPPORT SYSTEM. SEE BRIDGE SHEETS 4 TO 9 FOR DETAILS.
- STAGE II MICROPILES TO BE INSTALLED AFTER TEMPORARY SUPPORT SYSTEM IS IN PLACE.

NOTE:

THE ENGINEER WILL SELECT A MINIMUM OF TWO MICROPILE LOCATIONS AT EACH FOOTING FOR PROOF LOAD TESTING.

PILE LAYOUT


BRIDGE SHEET NO. 3		SHEET 20 OF 40	
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE NOS. 99I540NB&SB			
Washington State Department of Transportation		SR 99 PILE LAYOUT - BENTS 93 & 94	
BRIDGE AND STRUCTURES OFFICE 7-23-07			
M:\Z-Team\Alaskan way Ftgs\Window files\MICRO PILE LAYOUT.WND		REGION NO. 10	STATE WASH.
SUPERVISOR Clarke, J	DESIGNED BY Swett, GD	CHECKED BY Gallagher, P	DETAILED BY Schicchi, V.B.
BRIDGE PROJECTS ENGR.	PREPARED BY	DATE	REVISION
ARCHITECT/SPECIALIST	BY APPD	DATE	REVISION

TEMPORARY SUPPORT SYSTEM GENERAL NOTES

1. THE TEMPORARY SUPPORT SYSTEM HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 4TH EDITION 2007 AND THE AISC MANUAL OF STEEL CONSTRUCTION, 13TH EDITION. THE TEMPORARY SUPPORT SYSTEM HAS BEEN DESIGNED FOR THE LOADS AS DESCRIBED IN NOTES 2 AND 3. THIS TEMPORARY SUPPORT SYSTEM IS A PROPOSED SYSTEM. THE CONTRACTOR MAY PROPOSE ALTERNATE MEMBER SIZES, CONNECTIONS OR OTHER MODIFICATIONS TO THE SUPPORT SYSTEM IN ACCORDANCE WITH SECTION 6-01.9 OF THE STANDARD SPECIFICATIONS.
2. EACH TEMPORARY SUPPORT SYSTEM UNIT AT BENT 93E AND 94W HAS BEEN DESIGNED FOR THE FOLLOWING LOADS:
SERVICE VERTICAL LOAD = 290 KIPS
SERVICE WIND LOAD = 50 PSF
LATERAL LOAD = 5% OF SERVICE VERTICAL LOAD
3. EACH TEMPORARY SUPPORT SYSTEM UNIT AT BENT 94E AND 94W HAS BEEN DESIGNED FOR THE FOLLOWING LOADS:
SERVICE VERTICAL LOAD = 200 KIPS
SERVICE WIND LOAD = 50 PSF
LATERAL LOAD = 5% OF SERVICE VERTICAL LOAD
4. AS PART OF THE MICROPILE DESIGN SUBMITTAL, THE CONTRACTOR SHALL DESIGN TEMPORARY BRACING FOR THE STAGE I MICROPILES, IN BOTH HORIZONTAL PLANES, ALONG THE LENGTH EXTENDING FROM THE BOTTOM OF THE FOOTING TO THE BASE OF THE TEMPORARY SUPPORT SYSTEM. ALL BRACING TO THE EXISTING FOOTING OR COLUMN SHALL BE DESIGNED TO NOT INTERFERE WITH THE PERMANENT REHABILITATION WORK.

BRIDGE REHABILITATION WORK INSTALLATION AND REMOVAL SEQUENCE


1. REPAIR CROSSBEAMS AND EDGEBEAMS IN ACCORDANCE WITH THE DETAILS SHOWN ON BR. SHT. 20.
2. EXCAVATE TO A MINIMUM OF 6" BELOW EXISTING FOOTING PEDESTALS AT THE LOCATIONS OF THE STAGE I MICROPILES TO BE USED IN THE TEMPORARY SUPPORT SYSTEM. SHORE FOR EXCAVATION AT BENT 94E AND 94W (~5' TO 6' EXCAVATION REQUIRED).
3. INSTALL STAGE I MICROPILES IN ACCORDANCE WITH THE DETAILS SHOWN ON BR. SHT. 5. WELD TOP PLATE TO STAGE I MICROPILES AND SNUG TIGHTEN H.S. BAR NUTS.
5. INSTALL TEMPORARY SUPPORT SYSTEM IN ACCORDANCE WITH THE DETAILS SHOWN ON BR. SHTS. 6 THROUGH 9. STAGE I MICROPILES SHALL CURE A MINIMUM OF 3 DAYS PRIOR TO INSTALLING TEMPORARY SUPPORT SYSTEM.
6. COMPLETE EXCAVATION FOR FOOTING REHABILITATION AND INSTALL ALL STAGE II MICROPILES IN ACCORDANCE WITH DETAILS SHOWN ON BR. SHT. 3. THE CONTRACTOR SHALL USE EXTREME CARE WHEN EXCAVATING AROUND STAGE I MICROPILES. HAND TOOL EXCAVATION WILL BE REQUIRED BETWEEN PAIRS OF STAGE I MICROPILES.
7. COMPLETE FOOTING REHABILITATION INCLUDING PLACEMENT OF FOOTING CONCRETE. PROVIDE RECESS AROUND TEMPORARY SUPPORT SYSTEM VERTICAL POSTS IN ACCORDANCE WITH DETAILS ON BR. SHT. 5.
8. AFTER FOOTING HAS OBTAINED A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI, CUT OFF AND REMOVE TEMPORARY SUPPORT SYSTEM. FILL IN RECESSES IN FOOTINGS WITH GROUT CONFORMING TO SECTION 6-02.3(20).
9. RE-INSTALL TEMPORARY SUPPORT STRUT AT BENT 94W AND BACKFILL ALL FOOTINGS.




PLAN - TEMPORARY SUPPORT SYSTEM LAYOUT

Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Swett, GD 06/07 Checked By Detailed By Schitchi, VB 06/07 Bridge Projects Engr. Prelim. Plan By ARCHITECT/SPECIALIST DATE REVISION BY APPD		REGION NO. 10 STATE WASH. JOB NUMBER 07A905		FED. AID PROJ. NO. SHEET NO. TOTAL SHEETS		M:\Z-Team\Alaskan Way Frgs\Window files\SHORTING PLAN.WND FILE WINDOW	
BRIDGE AND STRUCTURES OFFICE 7-23-07 EXPIRES 5/15/08				WASHINGTON STATE DEPARTMENT OF TRANSPORTATION			
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE NOS. 99/54DNB&SB				BRIDGE SHEET NO. 4 SHEET 21 OF 40			

ROUGHEN SURFACE OF RECESS PRIOR TO PLACING GROUT.




HSS 10.000 x 0.500




HOLE TO ACCOMMODATE H.S. BAR.
R 2


AFTER FOOTING CONCRETE HAS REACHED A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI, CUT TEMPORARY SUPPORT POST A MINIMUM OF 1/2" BELOW TOP OF FOOTING AND PATCH RECESS WITH GROUT CONFORMING TO SECTION 6-02.3(2D).



DETAIL B




DETAIL A



TYPICAL PILE ELEVATION


STAGE I MICROPILE

TOP PLATE DETAIL



DETAIL C

FOOTING RECESS DETAIL
STAGE I MICROPILES



SECTION D


SHEAR COLLAR

Bridge Design Engr.	Kapur, J	Region No.	10	Fed. Aid Proj. No.		SHEET NO.		TOTAL SHEETS	
Supervisor	Clarke, PT	State	WASH.						
Designed By	Swett, GD	Job Number	07A805						
Checked By	Schicchi, VB	BY	APPD						
Detailed By		DATE							
Bridge Projects Engr.		REVISION							
Prinm. Plan By									
Architect/Specialist									

BRIDGE AND STRUCTURES DIVISION
WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
7-23-07
7/17/08

SR 99
YESLER WAY VICINITY
FOUNDATION STABILIZATION
ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB
STAGE I PILES
BENTS 93 & 94

BRIDGE NO.	5
SHEET	22
OF	40
SHEETS	




SECTION A
4

BENT 93W SHOWN, BENT 93E SIMILAR.

* AFTER TEMPORARY SUPPORT SYSTEM IS IN PLACE, PROVIDE ENOUGH SHIMS FOR A SNUG TIGHT FIT BETWEEN THE CONCRETE AND STEEL SUPPORT. INSTALL A 3/4" THICK NEOPRENE SHEET (50 DUROMETER) BETWEEN SHIMS AND CONCRETE TO COMPENSATE FOR CONCRETE IRREGULARITIES AND LIVE LOAD DEFLECTIONS. TACK WELD SHIMS IN PLACE TO PREVENT SHIMS FROM DISLODGING.

**FIELD VERIFY REQUIRED TEMPORARY SUPPORT POST LENGTH (TYP.)



SECTION B
4

BENT 93W SHOWN, BENT 93E SIMILAR.

Bridge Design Engr.	Kapur, J	DATE	
Supervisor	Clarke, PT	BY	APPD
Designed By	Swett, GD	REVISION	
Checked By			
Detailed By	schicchi, VB		
Bridge Projects Engr.			
Prelim. Plan By			
Architect/Specialist			

REGION NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
10	WASH.			

BRIDGE AND STRUCTURES OFFICE


WASHINGTON STATE DEPARTMENT OF TRANSPORTATION

7-23-07

EXPIRES 8/7/08


SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 991540NB&SB

TEMPORARY SUPPORT SYSTEM SECTIONS AND DETAILS



SECTION D
4

BENT 94W SHOWN, BENT 94E SIMILAR.




SECTION C
4

BENT 94W SHOWN, BENT 94E SIMILAR.


* AFTER TEMPORARY SUPPORT SYSTEM IS IN PLACE, PROVIDE ENOUGH SHIMS FOR A SNUG TIGHT FIT BETWEEN THE CONCRETE AND STEEL SUPPORT. INSTALL A 3/4" THICK NEOPRENE SHEET (50 DUROMETER) BETWEEN SHIMS AND CONCRETE TO COMPENSATE FOR CONCRETE IRREGULARITIES AND LIVE LOAD DEFLECTIONS. TACK WELD SHIMS IN PLACE TO PREVENT SHIMS FROM DISLODGING.

** FIELD VERIFY REQUIRED TEMPORARY SUPPORT POST LENGTH (TYP.)

Bridge Design Engr. Kapur, J	REGION NO. 10	STATE WASH.	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
Supervisor Clarke, PT				7	7
Designed By Swett, GD				24 of 40 SHEETS	
Checked By Schi cchi, VB				SR 99	
Bridge Projects Engr.				YESLER WAY VICINITY	
Prinln. Plan By				FOUNDATION STABILIZATION	
Architect/Specialist				ALASKAN WAY VIADUCT BRIDGE NOS. 99/540NB&SB	
				TEMPORARY SUPPORT SYSTEM	
				SECTIONS AND DETAILS	
				Washington State Department of Transportation	
				BRIDGE AND STRUCTURES OFFICE	
				7-23-07	
				EXPIRES 5/31/08	
				DATE	
				BY APPD	
				REVISION	
				M:\Z-Team\Alaskan way Figs\window files\SHORING DETAILS 2.WND	







VIEW F
7






VIEW E
6

** DRILL 6" DEEP HOLE AND INSTALL 3/4"Ø STAINLESS STEEL RESIN BONDED ANCHOR. PRIOR TO DRILLING, LOCATE EXISTING REINFORCEMENT IN COLUMN. AFTER REMOVAL OF BRACING, REMOVE ANCHOR A MINIMUM OF 1" FROM FACE OF CONCRETE AND PATCH WITH APPROVED GROUT (TYP.)

Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Swett, GD Checked By Swett, GD Detailed By Schicchi, VB Bridge Projects Engr. Prelim. Plan By Architect/Specialist	M:\Z-Team\Alaskan way Figs\window files\SHORING DETAILS 4.WND REGION NO. 10 STATE WASH. JOB NUMBER 07A205 DATE REVISION BY APPD	FEDERAL PROJ. NO. SHEET NO. TOTAL SHEETS	SR 99 JOB NO. 2021 SHEET 8
BRIDGE AND STRUCTURES OFFICE J. SHESH KAPUR BRIDGE ENGINEER LICENSE NO. 100000000 EXPIRES 7/17/09 7-23-07 EXPIRES 5/15/08		Washington State Department of Transportation SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE NOS. 99/540NB&SB TEMPORARY SUPPORT SYSTEM SECTIONS AND DETAILS	
BRIDGE NO. 2021 SHEET 8		SR 99 JOB NO. 2021 SHEET 8	




HP 14 x 102




NOTE:
L 3 x 3 x 3/8 BRACING AND C 6 x 13 CHANNELS
MAY BE SHOP OR FIELD WELDED TO TEMPORARY
SUPPORT POSTS.

Bridge Design Engr. Kapur, J	Supervisor Clarke, PT	Designed By Swett, GD	06/07	DATE	REVISION	BY	APPD
Checked By Schicchi, VB	06/07	JOB NUMBER 07A805	STATE WASH	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
M:\Z-Team\Alaskan way Ftgs\Window files\SHORING DETAILS 3.WND							
BRIDGE AND STRUCTURES OFFICE				Washington State Department of Transportation			
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE NOS. 99/540NB&SB				SR 99 108 NO. 7021 SHEET 9			
TEMPORARY SUPPORT SYSTEM SECTIONS AND DETAILS				SR 99 108 NO. 7021 SHEET 9			
BRIDGE AND STRUCTURES OFFICE				Washington State Department of Transportation			
7-23-07				EXPIRES 2/13/08			
LUCASH KAPUR				EXPIRES 8/17/08			




PLAN - BENT 93

* IT IS NOT CLEAR FROM THE AS-BUILT PLANS WHETHER THE PEDESTAL CONCRETE WAS PLACED MONOLITHICALLY WITH THE FOOTING AND COLUMN. CONTRACTOR SHALL USE CARE NOT TO REMOVE COLUMN OR FOOTING CONCRETE. TOLERANCE FOR THE PEDESTAL REMOVAL AROUND COLUMN SHALL BE ± 0 " +2" OF THE PLAN DIMENSIONS SHOWN.



VIEW F-F



TYP. PEDESTAL DOWEL INSTALLATION DETAIL
(EXISTING PILING NOT SHOWN FOR CLARITY)


**LIMITS OF EPOXY BONDING AGENT

REQUIRED CONSTRUCTION SEQUENCE:

- 1.) PRIOR TO REMOVING EXISTING PEDESTAL TO THE FACE OF COLUMN AND TOP OF FOOTING:
 - a.) DRILL HOLES THROUGH THE PEDESTAL AND A MINIMUM OF 2'-6" DEEP INTO THE FOOTING. (5'-0" MIN. TOTAL) AT ALL LOCATIONS SHOWN IN THE PLAN VIEW. OVERSIZED HOLES MAY BE DRILLED IN THE PEDESTAL.
 - b.) SET [1] #8 DOWELS IN EPOXY BONDING AGENT PER DETAIL THIS SHEET.
- 2.) AFTER DOWEL EPOXY HAS CURED ON THE LAST DOWEL INSTALLED, REMOVE PEDESTAL TO THE LIMITS SHOWN. TAKE CARE NOT TO DAMAGE DOWELS OR COLUMN AND FOOTING CONCRETE DURING REMOVAL. EPOXY CURE TIME SHALL BE AS SPECIFIED BY THE EPOXY MANUFACTURER, BUT NOT LESS THAN 2 HOURS.
- 3.) [1] #8 DOWELS ARE PROVIDED FOR FOOTING SHEAR STRENGTHENING AND SHALL BE INSTALLED PRIOR TO REMOVAL OF PEDESTAL.


*CONTAMINATED MATERIAL EXCAVATION PAY LIMITS. TYPICAL ALL SIDES OF FOOTING. VOLUME OF EXISTING FOOTING, PEDESTAL AND COLUMN ARE NOT INCLUDED IN EXCAVATION QUANTITIES.

Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Swett, GD Checked By Gallagher, P Detailed By Schicchi, V.B. Bridge Projects Engr. Prelim. Plan By Architect/Specialist		M.V. Team \ Alaskan way Figs \ window files \ BENT 93 REMOVAL.WND REGION NO. 10 STATE WASH. JOB NUMBER 07A905 DATE 8/14/07 REVISION 05 BY APPD		SHEET NO. 10 OF 27 SHEETS BRIDGE NO. 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB REMOVAL DETAILS - BENT 93	
BRIDGE AND STRUCTURES OFFICE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION JESS KAPUR 9/14/07		WASHINGTON STATE DEPARTMENT OF TRANSPORTATION			




VIEW G

1 #8 DOWELS NOT SHOWN FOR CLARITY. MICROPILES NOT SHOWN.



VIEW H

1 #8 DOWELS NOT SHOWN FOR CLARITY. MICROPILES NOT SHOWN.




PLAN @ BASE OF COLUMN - BENT 93

NOTES:


- * LOCATE ALL EXISTING COLUMN STEEL PRIOR TO DRILLING. DOWEL LOCATIONS MAY BE ADJUSTED ±1" TO AVOID ANY CONFLICTS.
- ** LOCATE EXISTING FOOTING STEEL (HOOKS) PRIOR TO DOWELING. DOWEL LOCATIONS MAY BE ADJUSTED ±2" TO AVOID CONFLICTS.

Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Swett, GD Checked By Gallagher, P Detailed By Schicchi, V.B. Bridge Projects Engr. Preim. Plan By Architect/Specialist		REGION NO. 10 STATE WASH. JOB NUMBER 07A805		FEDERAL AID PROJ. NO. SHEET NO. TOTAL SHEETS	
M:\Z-Team\Alaskan way Figs\Window files\BENT 93 DOWELS.WND		DATE REVISION BY APPD		SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB BENT 93 DOWEL PLACEMENT PLAN	
BRIDGE AND STRUCTURES OFFICE JUDGE SH KAPUR 7-23-07 EXPIRES 5/31/08		WASHINGTON STATE DEPARTMENT OF TRANSPORTATION		SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB BENT 93 DOWEL PLACEMENT PLAN	



BENT 93 - FOOTING REINF. (BOT. MAT)

FOR DIMENSIONS AND CALLOUTS NOT SHOWN SEE
"BENT 93-FOOTING REINF. (TOP MAT)" THIS SHEET




BENT 93 - FOOTING REINF. (TOP MAT)

FOR REINFORCEMENT SPACING SEE BRIDGE SHEETS 13 & 14.

BENT 93E FOOTING SHOWN, BENT 93W SYMMETRICAL ABOUT & VIADUCT.

NOTE:
● STAGE I MICROPILE

Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Sweet, GD Checked By Gallagher, P Detailed By Schitcchi, V. E. Bridge Projects Engr. Prelim. Plan By Architect/Specialist		REGION NO. 10 STATE WASH. JOB NUMBER 07A905		FEDERAL AID PROJ. NO. SHEET NO. TOTAL SHEETS		M:\Z-Team\Alaskan Way Fggs\Window files\BENT 93 NEW FTG 1.WND BY APPD DATE REVISION		EXP. 9/7/08 7-23-01 EXPIRES 3/15/08	
Washington State Department of Transportation				SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE NOS. 99/540NB&SB				BENT 93 FOOTING DETAILS	
BRIDGE NO. 12		SHEET 29 OF 40		JOB NO. 99-07A905		SHEET 12		SR 99	




VIEW **J** 12

3" CLEAR TO ALL BARS AROUND EXTERIOR FACES OF FOOTING. EXISTING PILING & REINFORCEMENT NOT SHOWN FOR CLARITY.

SECTION **JJ** 12

Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Snett, GD Checked By Ga'laghet, P Detailed By Schicchi, V.B. Bridge Projects Engr. Prelim. Plan By Architect/Specialist Mon. Jul 23 15:39:28 2007	REGION NO. 10 STATE WASH. JOB NUMBER 07/A005	SHEET NO. 13 TOTAL SHEETS 40	BRIDGE SHEET NO. 13 OF 40 SHEETS
M:\z-Team\Alaskan way Ftg\Window files\BENT 93 NEW FTG 2.WND	REVISION DATE BY APPD	WASHINGTON STATE DEPARTMENT OF TRANSPORTATION	SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB BENT 93 FOOTING DETAILS
BRIDGE AND STRUCTURES OFFICE TUGESH KAPUR LICENSED PROFESSIONAL ENGINEER EXPIRES 5/31/08	EXPIRES 9/7/08 7-23-07	BRIDGE AND STRUCTURES OFFICE	YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB BENT 93 FOOTING DETAILS



Bridge Design Engr.	Kapur, J	REGION NO.	10	FED. AID PROJ. NO.		SHEET NO.		TOTAL SHEETS	
Supervisor	Clarke, PT	STATE	WASH.						
Designed By	Sweett, GD	JOB NUMBER	07A805						
Checked By	Gallagher, P	DATE							
Detailed By	Schlicht, V.B.	REVISION							
Bridge Projects Engr.		BY	APPD						
Prelim. Plan By		DATE							
Architect/Specialist									

BRIDGE AND STRUCTURES OFFICE

7-23-07 [EXPIRES 3/19/08]


7-23-07 [EXPIRES 3/19/08]

BRIDGE ENGINEER

BRIDGE ENGINEER


Washington State Department of Transportation

SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE NOS. 99/540NB&SB BENT 93 FOOTING DETAILS




PLAN - BENT 94

* IT IS NOT CLEAR FROM THE AS-BUILT PLANS WHETHER THE PEDESTAL CONCRETE WAS PLACED MONOLITHICALLY WITH THE FOOTING AND COLUMN. CONTRACTOR SHALL USE CARE NOT TO REMOVE COLUMN OR FOOTING CONCRETE. TOLERANCE FOR THE PEDESTAL REMOVAL AROUND COLUMNS SHALL BE -0", +2" OF THE PLAN DIMENSIONS SHOWN.




VIEW J



VIEW K

REMOVE EXISTING LOWER EDGE BEAM STEEL SUPPORT STRUT AT BENT 94W. SAVE EXISTING CONNECTION BOLTS. LEAVE EXISTING 1/4" THICK ELASTOMERIC PAD IN PLACE (GLUED TO CONCRETE). RE-INSTALL STEEL STRUT AFTER FOOTING RETROFIT IS COMPLETE. MODIFY STEEL STRUT AS SHOWN ON BRIDGE SHEET 19. DETAILS OF EXISTING STEEL STRUT ARE AVAILABLE AT THE PROJECT ENGINEERS OFFICE.



TYP. PEDESTAL DOWEL INSTALLATION DETAIL

**LIMITS OF EPOXY BONDING AGENT

REQUIRED CONSTRUCTION SEQUENCE:

- 1.) PRIOR TO REMOVING EXISTING PEDESTAL TO THE FACE OF COLUMN AND TOP OF FOOTING:
 - a.) DRILL HOLES THROUGH THE PEDESTAL AND A MINIMUM OF 2'-3" DEEP INTO THE FOOTING. (4'-6" MIN. TOTAL) AT ALL LOCATIONS SHOWN IN THE PLAN VIEW. OVERSIZE HOLES MAY BE DRILLED IN THE PEDESTAL.
 - b.) SET [20] #8 DOWELS IN EPOXY BONDING AGENT PER DETAIL THIS SHEET.
- 2.) AFTER DOWEL EPOXY HAS CURED, REMOVE PEDESTAL TO THE LIMITS SHOWN. TAKE CARE NOT TO DAMAGE DOWELS OR COLUMN AND FOOTING CONCRETE DURING REMOVAL. EPOXY CURE TIME SHALL BE AS SPECIFIED BY THE EPOXY MANUFACTURER, BUT NOT LESS THAN 2 HOURS.
- 3.) [20] #8 DOWELS ARE PROVIDED FOR FOOTING SHEAR STRENGTHENING AND SHALL BE INSTALLED PRIOR TO REMOVAL OF PEDESTAL.


*CONTAMINATED MATERIAL EXCAVATION PAY LIMITS. TYPICAL ALL SIDES OF FOOTING. VOLUME OF EXISTING FOOTING, PEDESTAL AND COLUMN ARE NOT INCLUDED IN EXCAVATION QUANTITIES.

Bridge Design Engr.	Kapur, J	REGION NO.	10	REMOVAL - W/D	FILES	WINDOW	94	TOTAL SHEETS	15
Supervisor	Clarke, PT	STATE	WASH.					SHEET NO.	32
Designed By	Swett, GD							OF	40
Checked By	Gallagher, P								
Detailed By	SCHTCCHT, V.B.								
Bridge Projects Engr.									
Prelim. Plan By									
Architect/Specialist									
DATE	8/14/07	REVISION	05	BY	APPD				

BRIDGE AND STRUCTURES OFFICE
 8/14/07
 EXPIRES 3/7/08


Washington State Department of Transportation

SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB
 REMOVAL DETAILS - BENT 94



VIEW L


[20] #8 DOWELS NOT SHOWN FOR CLARITY. MICROPILES NOT SHOWN.



VIEW M

[20] #8 DOWELS NOT SHOWN FOR CLARITY. MICROPILES NOT SHOWN.

ADJUST THESE DOWELS UP AND DOWN 1" TO 2" TO AVOID CONFLICTS. (TYP. @ EACH CORNER)



PLAN @ BASE OF COLUMN - BENT 94

NOTES:

- * LOCATE ALL EXISTING COLUMN STEEL PRIOR TO DRILLING. DOWEL LOCATIONS MAY BE ADJUSTED ±1" TO AVOID ANY CONFLICTS.
- ** LOCATE EXISTING FOOTING STEEL (HOOKS) PRIOR TO DOWELING. DOWEL LOCATIONS MAY BE ADJUSTED ±2" TO AVOID CONFLICTS.

SYMM. ABT. FOOTING

TYPICAL BOTH SIDES

MICROPILE (TYP.)

Bridge Design Engr.	Kapur, J	REGION NO.	10	FED. AID PROJ. NO.		TOTAL SHEETS	
Supervisor	Clarke, PT	STATE	WASH.				
Designed By	Sweett, GD	JOB NUMBER	07A905				
Checked By	Gallagher, P	DATE					
Decalated By	Schitchi, V.B.	REVISION					
Bridge Projects Engr.		BY	APPD				
Prim. Plan By		DATE					
Architect/Specialist							

M: VZ-Team\Alaskan Way Frgs Window Files\BENT 94 DOWELS.WND


BRIDGE AND STRUCTURES OFFICE
7-23-07
EXPIRES 3/7/08




Washington State Department of Transportation

SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE NOS. 991540NB&SB BENT 94 DOWEL PLACEMENT PLAN

BRIDGE SHEET NO. 16
SHEET 33 OF 40
SERIES



BENT 94 - FOOTING REINF. (BOT. MAT)



BENT 94 - FOOTING REINF. (TOP MAT)


BENT 94W FOOTING SHOWN, BENT 94E SYMMETRICAL ABOUT & VIADUCT.

NOTE:
● STAGE I MICROPILE

Bridge No. 17 Sheet 34 of 40	
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE NOS. 99I540NB&SB BENT 94 FOOTING DETAILS	
Washington State Department of Transportation	
BRIDGE AND STRUCTURES OFFICE 7-23-07 EXPIRES 8/7/08	
M: VZ-Team\Alaskan way Frgs\Window Files\BENT 94 NEW FTG I.WND REGION NO. 30 STATE WASH. JOB NUMBER 07A805 BY APPD DATE REVISION	
Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Swett, GD Checked By Gallagher, P Detailed By Schicchi, V.B. Bridge Projects Engr. Preln. Plan By	TOTAL SHEETS SHEET NO.


NOTE:

STEEL STRUT AT BENT 94W TO BE RE-INSTALLED.
NOT SHOWN FOR CLARITY.




SECTION P 17

3" CLEAR TO ALL BARS AROUND EXTERIOR FACES OF FOOTING.
EXISTING PILING & REINFORCEMENT NOT SHOWN FOR CLARITY.




SECTION PP 17

Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Swett, GD Checked By Gallagher, P Detailed By Schicchi, V.B. Bridge Projects Engr. Prelm. Plan By Architect/Specialist		REGION NO. 10 STATE WASH. JOB NUMBER 07A205		FEDERAL AID PROJ. NO. SHEET NO. TOTAL SHEETS	
M:\Z-Team\Alaskan Way Flgs\Window Files\BENT 94 NEW FIG 2.WND DATE REVISION BY APPD		N.W. STATE OF WASHINGTON BRIDGE AND STRUCTURES OFFICE 7-23-07 EXPIRES 9/7/08		WASHINGTON STATE DEPARTMENT OF TRANSPORTATION	
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE NOS. 99/540NB&SB		BENT 94 FOOTING DETAILS		BRIDGE SHEET NO. 18 SHEET 35 OF 40	



1. CUT BOTTOM REINFORCEMENT FROM STEEL STRUT.
2. REMOVE 6" (-0,+1/4") OF THE STEEL STRUT.
3. GRIND BOTTOM OF STRUT AND BOTTOM REINFORCEMENT AT INTERFACE AND RE-WELD REINFORCEMENT TO STRUT.
4. EXTEND CUT-OUT FOR JACK TO PROVIDE A 2 1/2" X 8" SLOT.

EXISTING SUPPORT STRUT MODIFICATION DETAILS




SECTION N 17

3" CLEAR TO ALL BARS AROUND EXTERIOR FACES OF FOOTING.
EXISTING PILING & REINFORCEMENT NOT SHOWN FOR CLARITY.

STEEL STRUT MODIFICATION PROCEDURE

1. REMOVE STEEL STRUT AND PLASTIC PIPE.
2. MODIFY EXISTING STEEL STRUT AS SHOWN.
3. REPAIR SPALLS PER BRIDGE SHEET 20.
4. AFTER COMPLETION OF FOOTING RETROFIT RE-INSTALL STEEL STRUT AGAINST ELASTOMERIC BEARING PAD GLUED TO THE BOTTOM OF THE EXISTING CONCRETE EDGE BEAM. RE-INSTALL BOLTS BETWEEN THE CONNECTION ANGLES ATTACHED TO THE CONCRETE COLUMN AND THE ANGLES ON THE STRUT. LEAVE BOLTS LOOSE. PLACE TEMPORARY SHIMS UNDER STRUT BOTTOM BASE PLATE IF REQUIRED.
5. JACK STEEL STRUT AGAINST EDGE BEAM TO A FORCE OF 10 KIPS.
6. REMOVE ANY TEMPORARY SHIMS AND GROUT UNDER STRUT BASE PLATE.
7. RELEASE AND REMOVE JACK AFTER GROUT HAS ATTAINED A STRENGTH OF 4000 PSI.
8. TIGHTEN BOLTS IN CONNECTION ANGLES ATTACHED TO THE CONCRETE COLUMN AND STEEL STRUT.
9. RE-INSTALL PLASTIC PIPE AND BACKFILL FOOTING.



SECTION NN 17

Bridge Design Engr.	Kapur, J	REGION NO.	10	FED. AID PROJ. NO.		TOTAL SHEETS	
Supervisor	Clarke, PT	STATE	WASH.				
Designed By	Sweet, GD	JOB NUMBER	07A905				
Checked By	Gallagher, P	DATE					
Detailed By	Schicchi, V.B.	BY	APPD				
Bridge Projects Engr.		REVISION					
Prep. Plan By		DATE					
Architect/Specialist							

BRIDGE AND STRUCTURES OFFICE
7-23-07



BRUCE D. KAPUR
REGISTERED PROFESSIONAL ENGINEER
EXPIRES 3/31/08

Washington State
Department of Transportation



SR 99
YESLER WAY VICINITY
FOUNDATION STABILIZATION
ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB

BRIDGE NO. 19
SHEET 36 OF 40 SHEETS

BENT 94 FOOTING DETAILS




DETAIL D



SECTION C

SECTION B


* SAWCUT DEPTH MAY BE REDUCED OR ELIMINATED IF CONCRETE COVER OVER EXISTING REINFORCEMENT STEEL IS 3/4" OR LESS.



REPAIR PROCEDURE

1. REMOVE DAMAGED AND UNSOUND CONCRETE TO THE LIMITS SHOWN OR AS SPECIFIED BY THE ENGINEER. THE CONCRETE IN THE REPAIR AREA SHALL BE SOUNDED TO VERIFY ALL UNSOUND CONCRETE HAS BEEN REMOVED. PROVIDE A 3/4" DEEP SAWCUT AT ALL EDGES OF THE REPAIR. CONCRETE SHALL BE REMOVED AROUND ALL EXPOSED REBAR TO PROVIDE A MINIMUM OF 1" CLEARANCE AROUND THE BAR FOR CONCRETE PLACEMENT. EXTREME CARE SHALL BE TAKEN NOT TO DAMAGE EXISTING REINFORCEMENT. ANY DAMAGED REINFORCEMENT SHALL BE REPAIRED BY THE CONTRACTOR WITH A METHOD APPROVED BY THE ENGINEER.
2. SANDBLAST OR WIRE BRUSH RUST FROM EXPOSED AND RUSTED REINFORCEMENT.
3. INSTALL BEAM FORMWORK AND PLACE CONCRETE PATCHING MATERIAL. THE CONCRETE PATCHING MATERIAL SHALL CONFORM TO SECTION 9-20.2(2). THE CONTRACTOR SHALL SUBMIT, FOR APPROVAL BY THE ENGINEER, THE PATCHING MATERIAL AND METHOD OF PLACEMENT.
4. INSPECT THE REMAINING PORTIONS OF THE EDGEBEAMS AND CROSSBEAMS IN THE VICINITY OF BENT 93 AND 94 AND EPOXY INJECT ALL CRACKS AS SPECIFIED BY THE ENGINEER.

Bridge Design Engr. Kapur, J Supervisor Clarke, PT Designed By Swett, GD Checked By Gallagher, P Detailed By Schicchi, VB Bridge Projects Engr. Prelim. Plan By Architect/Specialist		M:\z-Team\Alaskan way Ftgs\window files\EDGEBEAM REPAIRS.WND REGION NO. 10 STATE WASH. JOB NUMBER 07/AC05		SHEET NO. 20 TOTAL SHEETS 40	
SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB BEAM REPAIRS		Washington State Department of Transportation		BRIDGE AND STRUCTURES OFFICE 7-23-07 EXPIRES 8/7/08 EXPIRES 5/19/08	
DATE	REVISION	BY	APPD		



MARK NO.	LOCATION	SIZE	NO. REINFORCING BARS	BEND TYPE	NO. OR STR.	LUMP SUM	SUBSTR.	EPOXY COAT	VARIES	DIMENSIONS (Out to Out)										WEIGHT Lbs.					
										U	W	X	Y	Z	θ ₁ Deg.	θ ₂ Deg.	Ft.	In.	Ft.		In.	Ft.	In.	Ft.	In.
S = Bar is included in substructure quantities. L = Lump sum quantity. T = Transverse or S = Seismic													E = Bar is to be epoxy coated. V = Bar dimensions vary between dimensions shown on this line and the following line.												
S = Bar is included in substructure quantities. L = Lump sum quantity. T = Transverse or S = Seismic													E = Bar is to be epoxy coated. V = Bar dimensions vary between dimensions shown on this line and the following line.												
S = Bar is included in substructure quantities. L = Lump sum quantity. T = Transverse or S = Seismic													E = Bar is to be epoxy coated. V = Bar dimensions vary between dimensions shown on this line and the following line.												

MARK NO.	LOCATION	SIZE	NO. REINFORCING BARS	BEND TYPE	NO. OR STR.	LUMP SUM	SUBSTR.	EPOXY COAT	VARIES	NO. EACH	DIMENSIONS (Out to Out)										WEIGHT Lbs.						
											U	W	X	Y	Z	θ ₁ Deg.	θ ₂ Deg.	Ft.	In.	Ft.	In.	Ft.	In.	Ft.	In.	Ft.	In.
S = Bar is included in substructure quantities. L = Lump sum quantity. T = Transverse or S = Seismic													E = Bar is to be epoxy coated. V = Bar dimensions vary between dimensions shown on this line and the following line.														
S = Bar is included in substructure quantities. L = Lump sum quantity. T = Transverse or S = Seismic													E = Bar is to be epoxy coated. V = Bar dimensions vary between dimensions shown on this line and the following line.														
S = Bar is included in substructure quantities. L = Lump sum quantity. T = Transverse or S = Seismic													E = Bar is to be epoxy coated. V = Bar dimensions vary between dimensions shown on this line and the following line.														
S = Bar is included in substructure quantities. L = Lump sum quantity. T = Transverse or S = Seismic													E = Bar is to be epoxy coated. V = Bar dimensions vary between dimensions shown on this line and the following line.														

BRIDGE SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION ALASKAN WAY VIADUCT BRIDGE Nos. 99/540NB&SB

BRIDGE SHEET NO. 21

38 of 40 SHEETS

Washington State Department of Transportation

BRIDGE AND STRUCTURES OFFICE

BRIDGE DESIGN ENGR. Kapur, J
 SUPERVISOR Clarke, PT
 DESIGNED BY
 CHECKED BY Schicchi, V.B.
 BRIDGE PROJECTS ENGR.
 PREP. PLAN BY
 ARCHITECT/SPECIALIST

REGION NO. 10 STATE WASH. JOB NUMBER 07/AB05


FED. AID PROJ. NO. SHEET NO. TOTAL SHEETS

M:\2-Team\Alaskan way Frgs\Window files\BarList1.WND

DATE REVISION BY APPD


Mon Jul 23 13:39:36 2007

T.24N. R.4E. W.M.
City of Seattle



CHANNELIZING DEVICE SPACING (feet)		
MPH	TAPER	TANGENT
50/70	40	80
35/45	30	60
25/30	20	40

- LEGEND**
- SIGN
 - ▬ TYPE II BARRICADE
 - FLAGGER STATION
 - WASTE CONTAINER
 - EXISTING EASEMENT
 - ⊠ TEMPORARY TRAFFIC CONTROL DEVICES
 - ⊞ TEMPORARY CONSTRUCTION FENCE



- GENERAL NOTES:**
- TYPE II BARRICADE AND TEMPORARY TRAFFIC CONTROL DEVICES SHALL BE PLACED DURING CONSTRUCTION OF THE WATERFRONT PEDESTRIAN/ BICYCLE FACILITY.
 - REMOVE TYPE II BARRICADE AND TEMPORARY TRAFFIC CONTROL DEVICES WHEN CONSTRUCTION OF THE WATERFRONT PEDESTRIAN/ BICYCLE FACILITY IS COMPLETE.
 - DETOUR TO REMAIN DURING CONTRACT SUSPENSION. SEE SPECIAL PROVISION, PROSECUTION & PROGRESS.

WATERFRONT PEDESTRIAN/ BICYCLE FACILITY DETOUR

FILE NAME: C:\AAwork\pwwork\AVV\JonesK\J\dms03962\AD.L3082_PS.TC_01.dgn		REGION NO. 10	STATE WASH	FED. AID PROJ. NO.	DATE 8/14/07	BY JGC
TIME 10:58:17 AM	DATE 8/15/2007	JOB NUMBER 07A805	CONTRACT NO.	LOCATION NO.		
PLOTTED BY JonesK	DESIGNED BY S. SOBHANI	ENTERED BY K. IRELAND	CHECKED BY S. SOBHANI	PROJ. ENGR. P. LACY	REVISIONS SHADED	REVISION
REGIONAL ADM. D. DYE						

Washington State
Department of Transportation

SR 99
YESLER WAY VICINITY
FOUNDATION STABILIZATION

TRAFFIC CONTROL PLAN

P.E. STAMP BOX

DATE


P.E. STAMP BOX

DATE

TC1

SHEET 39 OF 40 SHEETS

T.24N. R.4E. W.M. City of Seattle



- GENERAL NOTES:**
- ALL SIGNS ON THIS SHEET ARE CONSTRUCTION SIGNS CLASS A INCLUDED IN THE LUMP SUM ITEM, PROJECT TEMPORARY TRAFFIC CONTROL.
 - ALL DIMENSIONS SHOWN ARE IN FEET UNLESS OTHERWISE DESIGNATED.
 - DO NOT BLOCK ACCESS ON THE NORTH AND SOUTH ENDS OF THE LOADING DOCK.
 - DO NOT BLOCK ACCESS TO THE GARBAGE CONTAINERS LOCATED IN THE VICINITY OF COLUMBIA STREET WORK SITE ENTRANCE.
 - VERIFY PHONE NUMBER WITH ENGINEER PRIOR TO FABRICATION OF PROJECT INFORMATION SIGN.

TC2	SR 99 YESLER WAY VICINITY FOUNDATION STABILIZATION
SHEET 40 OF 40 SHEETS	TRAFFIC CONTROL PLAN



DATE	DATE
P.E. Stamp Box	P.E. Stamp Box

DATE	DATE
P.E. Stamp Box	P.E. Stamp Box

FED. AID PROJ. NO.	LOCATION NO.
--------------------	--------------

REGION NO.	STATE
10	WASH
JOB NUMBER	CONTRACT NO.
07805	

REVISIONS SHOWN	REVISION	DATE	BY
		8/14/07	Y.C.

FILE NAME	c:\AAAWORK\PW\work\AW\Jonesk\Jms03962\AD_L3082.PS.TC.02.dgn
TIME	10:55:53 AM
DATE	8/15/2007

PLOTTED BY	Jonesk J
DESIGNED BY	R. A. BEAN
ENTERED BY	Y. GONZALEZ
CHECKED BY	K. JONES
PROJ. ENGR.	P. LACY
REGIONAL ADM.	D. DYE

- LEGEND**
- SIGN
 - TYPE II BARRICADE
 - FLAGGER STATION
 - WASTE CONTAINER
 - EXISTING EASEMENT
 - TEMPORARY TRAFFIC CONTROL DEVICES
 - TEMPORARY CONSTRUCTION FENCE

ALLOW GARBAGE TRUCK TO ENTER THE WORK SITE FOR THE PURPOSE OF EMPTYING WASTE CONTAINERS